

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+07.00 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	90 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	700 SY		
0008	0199000000-E	SP	TEMPORARY SHORING	120 SF		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	40 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	130 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	52 LF		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	112 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	144 LF		
0014	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	60 LF		
0015	0995000000-E	340	PIPE REMOVAL	64 LF		
0016	1099500000-E	505	SHALLOW UNDERCUT	500 CY		
0017	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	475 TON		
0018	1121000000-E	520	AGGREGATE BASE COURSE	390 TON		
0019	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1275000000-E	600	PRIME COAT	292	GAL	
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	860	TON	
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	610	TON	
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,000	TON	
0024	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	130	TON	
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100	TON	
0026	2022000000-E	815	SUBDRAIN EXCAVATION	90	CY	
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	68	CY	
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400	LF	
0029	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0030	2077000000-E	815	6" OUTLET PIPE	6	LF	
0031	2209000000-E	838	ENDWALLS	4	CY	
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5	EA	
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5	EA	
0034	2556000000-E	846	SHOULDER BERM GUTTER	90	LF	
0035	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	125	LF	
0036	3030000000-E	862	STEEL BM GUARDRAIL	175	LF	
0037	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75	LF	
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0041	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	50 LF		
0042	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (III)	2 EA		
0043	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0044	3649000000-E	876	RIP RAP, CLASS B	55 TON		
0045	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,515 SY		
0046	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0047	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	160 LF		
0048	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0049	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		
0050	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	15 EA		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	328 SF		
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	256 SF		
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	113 SF		
0054	4430000000-N	1130	DRUMS	120 EA		
0055	4435000000-N	1135	CONES	30 EA		
0056	4445000000-E	1145	BARRICADES (TYPE III)	196 LF		
0057	4450000000-N	1150	FLAGGER	1,620 HR		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	4480000000-N	1165	TMA	2 EA		
0059	4516000000-N	1180	SKINNY DRUM	50 EA		
0060	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	53 EA		
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	24,261 LF		
0062	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	754 LF		
0063	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	86 LF		
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	116 LF		
0065	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	4 EA		
0066	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	14 EA		
0067	6000000000-E	1605	TEMPORARY SILT FENCE	2,400 LF		
0068	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	285 TON		
0069	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120 TON		
0070	6012000000-E	1610	SEDIMENT CONTROL STONE	410 TON		
0071	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0072	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0074	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0075	6029000000-E	SP	SAFETY FENCE	400 LF		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	603000000-E	1630	SILT EXCAVATION	430 CY		
0077	603600000-E	1631	MATTING FOR EROSION CONTROL	15,200 SY		
0078	603700000-E	SP	COIR FIBER MAT	55 SY		
0079	603800000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	225 SY		
0080	604200000-E	1632	1/4" HARDWARE CLOTH	555 LF		
0081	607000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0082	607101000-E	SP	WATTLE	90 LF		
0083	607102000-E	SP	POLYACRYLAMIDE (PAM)	40 LB		
0084	607103000-E	1640	COIR FIBER BAFFLE	245 LF		
0085	607105000-E	SP	*** SKIMMER (1-1/2")	6 EA		
0086	608400000-E	1660	SEEDING & MULCHING	4 ACR		
0087	608700000-E	1660	MOWING	2 ACR		
0088	609000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0089	609300000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0090	609600000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0091	610800000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
0092	611450000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0093	611700000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0094	612300000-E	1670	REFORESTATION	0.5 ACR		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0095	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+07.00-L-)	Lump Sum	L.S.	
0096	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+07.00-L-)	Lump Sum	L.S.	
0097	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+73.31-L-)	Lump Sum	L.S.	
0098	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	51 LF		
0099	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	48 LF		
0100	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	39 LF		
0101	8113000000-N	411	SID INSPECTIONS	1 EA		
0102	8114000000-N	411	SPT TESTING	1 EA		
0103	8115000000-N	411	CSL TESTING	1 EA		
0104	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+07.00-L-)	Lump Sum	L.S.	
0105	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	100.8 CY		
0106	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+07.00-L-)	Lump Sum	L.S.	
0107	8217000000-E	425	REINFORCING STEEL (BRIDGE)	20,110 LB		
0108	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,686 LB		
0109	8364000000-E	450	HP12X53 STEEL PILES	240 LF		
0110	8475000000-E	460	TWO BAR METAL RAIL	219.3 LF		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" X 2'-9 1/2")	235.48 LF		
0112	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	199 TON		
0113	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	221 SY		
0114	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0115	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,877.33 LF		

0836/Mar13/Q84599.91/D510069590000/E115

Total Amount Of Bid For Entire Project :

Contract No. **C202262**

County (ies): **Transylvania**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General