

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM BOARDWALK	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (24+02.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	21,400 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	820 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	400 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	22 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	70 SY		
0013	0335500000-E	305	30" DRAINAGE PIPE	24 LF		
0014	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (15", V)	112 LF		
0015	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	68 LF		
0016	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0017	0995000000-E	340	PIPE REMOVAL	46 LF		
0018	0996000000-N	350	PIPE CLEAN-OUT	1 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,170 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	970 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	710 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	145 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	20 EA		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0028	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0032	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0034	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	650 LF		
0035	2591000000-E	848	4" CONCRETE SIDEWALK	580 SY		
0036	3030000000-E	862	STEEL BM GUARDRAIL	1,050 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0038	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0039	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0040	3575000000-E	SP	GENERIC FENCING ITEM SAFETY RAIL	500 LF		
0041	3635000000-E	876	RIP RAP, CLASS II	310 TON		
0042	3649000000-E	876	RIP RAP, CLASS B	500 TON		
0043	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	3,580 SY		
0044	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	93 LF		
0045	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0046	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0047	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	9 EA		
0048	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	487 SF		
0049	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	88 SF		
0050	4445000000-E	1145	BARRICADES (TYPE III)	104 LF		
0051	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,853 LF		
0052	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,540 LF		
0053	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	840 LF		
0054	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	16 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6000000000-E	1605	TEMPORARY SILT FENCE	3,000 LF		
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	400 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	685 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	500 LF		
0063	6029000000-E	SP	SAFETY FENCE	1,100 LF		
0064	6030000000-E	1630	SILT EXCAVATION	710 CY		
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,000 SY		
0066	6037000000-E	SP	COIR FIBER MAT	20 SY		
0067	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	30 SY		
0068	6042000000-E	1632	1/4" HARDWARE CLOTH	680 LF		
0069	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	175 SY		
0070	6070000000-N	1639	SPECIAL STILLING BASINS	18 EA		
0071	6071010000-E	SP	WATTLE	200 LF		
0072	6071020000-E	SP	POLYACRYLAMIDE (PAM)	60 LB		
0073	6071030000-E	1640	COIR FIBER BAFFLE	255 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
0075	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0076	6087000000-E	1660	MOWING	3	ACR	
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150	LB	
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	4.25	TON	
0081	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0083	6123000000-E	1670	REFORESTATION	0.25	ACR	
0084	6135000000-E	SP	GENERIC EROSION CONTROL ITEM COMPOST BLANKET	2	ACR	

STRUCTURE ITEMS

0085	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24+00.00-L-)	Lump Sum	L.S.	
0086	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	168.5	LF	
0087	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	70	LF	
0088	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	102	LF	
0089	8113000000-N	411	SID INSPECTIONS	1	EA	
0090	8115000000-N	411	CSL TESTING	1	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (24+00.00-L-)	Lump Sum	L.S.	
0092	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	12,502 SF		
0093	8161000000-E	420	GROOVING BRIDGE FLOORS	9,342 SF		
0094	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	160.8 CY		
0095	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24+00.00-L-)	Lump Sum	L.S.	
0096	8217000000-E	425	REINFORCING STEEL (BRIDGE)	41,378 LB		
0097	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,473 LB		
0098	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	586.6 LF		
0099	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	786.59 LF		
0100	8364000000-E	450	HP12X53 STEEL PILES	320 LF		
0101	8475000000-E	460	TWO BAR METAL RAIL	539.44 LF		
0102	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-6")	279.92 LF		
0103	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 3'-0")	274.69 LF		
0104	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-4" X 3'-0")	326.13 LF		
0105	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	725 TON		
0106	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	810 SY		
0107	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0109	8867000000-E	SP	GENERIC STRUCTURE ITEM DOUBLE-FACED TWO-BAR METAL RAI L	318.63 LF		
0939/Mar06/Q129740.0/D505354690000/E109			Total Amount Of Bid For Entire Project :			

Contract No. **C202813**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General