

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	622 SY		
0003	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 3")	622 SY		
0004	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	25 TON		
0005	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	62 TON		
0006	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	5 TON		
0007	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	7.1 SY		
0008	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	240 SF		
0009	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
001C	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0011	4430000000-N	1130	DRUMS	300 EA		
0012	4435000000-N	1135	CONES	30 EA		
0013	4450000000-N	1150	FLAGGER	64 HR		
0014	4480000000-N	1165	TMA	2 EA		
0015	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (II)	1,150 LF		
0016	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	9,200 LF		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	58 EA		
001E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	1,412 SF		
001E	8161000000-E	420	GROOVING BRIDGE FLOORS	92,281.2 SF		
002C	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	5,791 LB		
0021	8296000000-N	442	POLLUTION CONTROL	Lump Sum	L.S.	
0022	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
002E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0024	8660000000-E	SP	CONCRETE REPAIRS	21.5 CF		
002E	8664000000-E	SP	SHOTCRETE REPAIRS	63.5 CF		
002E	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0027	8860000000-N	SP	GENERIC STRUCTURE ITEM CLEANING & REPAINTING OF BRIDGE #30	Lump Sum	L.S.	
002E	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE	Lump Sum	L.S.	
002E	8860000000-N	SP	GENERIC STRUCTURE ITEM RUBBER EXPANSION JOINT SEALS	Lump Sum	L.S.	
003C	8860000000-N	SP	GENERIC STRUCTURE ITEM STRUCTURAL STEEL REPAIR (APPROX. 7,600 LBS)	Lump Sum	L.S.	
0031	8860000000-N	SP	GENERIC STRUCTURE ITEM TEMPORARY STEEL COVER FOR EXP JOINT SEAL REPAIR	Lump Sum	L.S.	
003E	8860000000-N	SP	GENERIC STRUCTURE ITEM UNDER STRUCTURE WORK PLATFORM	Lump Sum	L.S.	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	8881000000-E	SP	GENERIC STRUCTURE ITEM LATEX MODIFIED CONCRETE OVER- LAY - VERY EARLY STRENGTH	672.1	CY	
0034	8893000000-E	SP	GENERIC STRUCTURE ITEM HYDRO-DEMOLITION OF BRIDGE DECK	11,773.2	SY	
0035	8893000000-E	SP	GENERIC STRUCTURE ITEM PLACING & FINISHING LATEX MOD- IFIED CONCRETE OVERLAY - VERY EARLY STRENGTH	11,906.3	SY	
0036	8893000000-E	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	11,773.2	SY	
0037	8897000000-N	SP	GENERIC STRUCTURE ITEM SPAN JACKING NEW HANOVER CO. BRIDGE #30	28	EA	

1408/Apr13/Q148124.1/D229179100000/E37

Total Amount Of Bid For Entire Project :

Contract No. **C203008**

County (ies): **New Hanover**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General