

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16 + 50.00-L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	3,100 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	150 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	600 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	15 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	40 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	60 LF		
0013	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	48 LF		
0015	0995000000-E	340	PIPE REMOVAL	23 LF		
0016	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0017	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	400 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1330000000-E	607	INCIDENTAL MILLING	150	SY	
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	375	TON	
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	210	TON	
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	575	TON	
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	65	TON	
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10	TON	
0025	2000000000-N	806	RIGHT OF WAY MARKERS	10	EA	
0026	2022000000-E	815	SUBDRAIN EXCAVATION	45	CY	
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35	CY	
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200	LF	
0029	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0030	2077000000-E	815	6" OUTLET PIPE	6	LF	
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0033	2556000000-E	846	SHOULDER BERM GUTTER	55	LF	
0034	3030000000-E	862	STEEL BM GUARDRAIL	425	LF	
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
003E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	732	LF	
003E	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	950	LF	
004C	3569000000-E	867	BARBED WIRE FENCE RESET	590	LF	
0041	3578000000-N	SP	GENERIC FENCING ITEM RESET 20' METAL GATE	1	EA	
0042	3578000000-N	SP	GENERIC FENCING ITEM RESET 24' METAL GATE	1	EA	
004E	3635000000-E	876	RIP RAP, CLASS II	270	TON	
0044	3649000000-E	876	RIP RAP, CLASS B	156	TON	
004E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,780	SY	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	76	LF	
0047	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	5	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	485	SF	
005C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	248	SF	
0051	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	1	EA	
0052	4445000000-E	1145	BARRICADES (TYPE III)	184	LF	
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	890	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	898	LF	
005E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	1,020	LF	
005E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	9	EA	
0057	6000000000-E	1605	TEMPORARY SILT FENCE	975	LF	
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200	TON	
006C	6012000000-E	1610	SEDIMENT CONTROL STONE	375	TON	
0061	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	260	LF	
006E	6029000000-E	SP	SAFETY FENCE	100	LF	
006E	6030000000-E	1630	SILT EXCAVATION	330	CY	
0067	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000	SY	
006E	6037000000-E	SP	COIR FIBER MAT	10	SY	
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	220	LF	
007C	6070000000-N	1639	SPECIAL STILLING BASINS	12	EA	
0071	6071010000-E	SP	WATTLE	110	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6071020000-E	SP	POLYACRYLAMIDE (PAM)	60	LB	
0073	6071030000-E	1640	COIR FIBER BAFFLE	70	LF	
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
007E	6084000000-E	1660	SEEDING & MULCHING	1	ACR	
007E	6087000000-E	1660	MOWING	0.5	ACR	
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
008C	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75	TON	
0081	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	

**STRUCTURE ITEMS**

0083	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 50.00-L-)	Lump Sum	L.S.	
0084	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	145	LF	
008E	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	52	LF	
008E	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	55	LF	
0087	8113000000-N	411	SID INSPECTIONS	1	EA	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8115000000-N	411	CSL TESTING	1 EA		
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16 + 50.00-L-)	Lump Sum	L.S.	
009C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	105 CY		
0091	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 50.00-L-)	Lump Sum	L.S.	
0092	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,956 LB		
009C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,812 LB		
0094	8364000000-E	450	HP12X53 STEEL PILES	350 LF		
009E	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	505.5 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	564 TON		
0097	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	628 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	2,776.13 LF		

1615/Apr09/Q57605.38/D424044940000/E99

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202818**

**County (ies):**    **Rowan**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General