

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	80,000 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21 + 31 -L-)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	1,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,060 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,000 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	130 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	400 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	252 LF		
0013	0335300000-E	305	18" DRAINAGE PIPE	368 LF		
0014	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	88 LF		
0015	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	308 LF		
0016	0453000000-E	310	*** PIPE END SECTION (18")	2 EA		
0017	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	108 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
001E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
002C	1121000000-E	520	AGGREGATE BASE COURSE	3,570 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0022	1231000000-E	560	SHOULDER BORROW	1,600 CY		
002E	1275000000-E	600	PRIME COAT	2,636 GAL		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,070 TON		
002E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,330 TON		
002E	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	135 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	29 EA		
002E	2209000000-E	838	ENDWALLS	6 CY		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
003C	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	4 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	54 LF		
003E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	150 SY		
0034	3030000000-E	862	STEEL BM GUARDRAIL	1,848 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0038	3628000000-E	876	RIP RAP, CLASS I	26	TON	
0039	3649000000-E	876	RIP RAP, CLASS B	369	TON	
0040	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,115	SY	
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	182	SF	
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	
0043	4430000000-N	1130	DRUMS	20	EA	
0044	4445000000-E	1145	BARRICADES (TYPE III)	144	LF	
0045	4455000000-N	1150	FLAGGER	60	DAY	
0046	4485000000-E	1170	PORTABLE CONCRETE BARRIER	60	LF	
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,070	LF	
0048	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,850	LF	
0049	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	36	LF	
0050	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	31	EA	
0051	6000000000-E	1605	TEMPORARY SILT FENCE	2,650	LF	
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105	TON	
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	540	TON	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	900 TON		
0055	6015000000-E	1615	TEMPORARY MULCHING	15.5 ACR		
0056	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	600 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.25 TON		
0058	6024000000-E	1622	TEMPORARY SLOPE DRAINS	730 LF		
0059	6029000000-E	SP	SAFETY FENCE	500 LF		
0060	6030000000-E	1630	SILT EXCAVATION	4,500 CY		
0061	6036000000-E	1631	MATTING FOR EROSION CONTROL	30,000 SY		
0062	6037000000-E	SP	COIR FIBER MAT	25 SY		
0063	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	405 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	3,400 LF		
0065	6071012000-E	SP	COIR FIBER WATTLE	125 LF		
0066	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15 LB		
0067	6071030000-E	1640	COIR FIBER BAFFLE	180 LF		
0068	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0069	6084000000-E	1660	SEEDING & MULCHING	13 ACR		
0070	6087000000-E	1660	MOWING	12 ACR		
0071	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0072	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0073	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	425 LB		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6108000000-E	1665	FERTILIZER TOPDRESSING	12.75 TON		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		
007E	6123000000-E	1670	REFORESTATION	0.5 ACR		
0077	6135000000-E	SP	GENERIC EROSION CONTROL ITEM SEEDING	5 ACR		
007E	6144000000-E	SP	GENERIC EROSION CONTROL ITEM BONDED FIBER MATRIX	17,500 LB		
007E	8070000000-E	410	FOUNDATION EXCAVATION	96 CY		
008C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	237.2 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 10.21-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	31,938 LB		
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,790 LB		
0084	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	3,144 LF		
008E	8391000000-N	450	STEEL PILE POINTS	60 EA		
008E	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	375.9 LF		
0087	8531000000-E	462	4" SLOPE PROTECTION	1,100 SY		
008E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	195 SY		
008E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009C	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,286.6 LF		
0091	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	963.5 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8867000000-E	SP	GENERIC STRUCTURE ITEM CHAIN LINK FENCE	371.9 LF		
1546/Apr11/Q216109.6/D388402712000/E92			Total Amount Of Bid For Entire Project :			

Contract No. C203044

County (ies): Rutherford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General