

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (5/8")	771 SY		
0003	1330000000-E	607	INCIDENTAL MILLING	156 SY		
0004	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	13 TON		
0005	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1 TON		
0006	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	224 SF		
0007	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	664 SF		
0008	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	64 SF		
0009	4415000000-N	1115	FLASHING ARROW BOARD	4 EA		
001C	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		
0011	4430000000-N	1130	DRUMS	101 EA		
0012	4435000000-N	1135	CONES	26 EA		
0013	4445000000-E	1145	BARRICADES (TYPE III)	100 LF		
0014	4455000000-N	1150	FLAGGER	20 DAY		
0015	4480000000-N	1165	TMA	3 EA		
0016	4510000000-N	SP	LAW ENFORCEMENT	1,000 HR		
0017	4516000000-N	1180	SKINNY DRUM	35 EA		
0018	4726100000-E	1205	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	428	LF	
0020	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	5,583	LF	
0021	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4	EA	
0022	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	856	LF	
0023	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	5,583	LF	
0024	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	64	EA	
002E	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
002E	8161000000-E	420	GROOVING BRIDGE FLOORS	36,756	SF	
0027	8217000000-E	425	REINFORCING STEEL (BRIDGE)	40	LB	
002E	8660000000-E	SP	CONCRETE REPAIRS	58	CF	
002E	8664000000-E	SP	SHOTCRETE REPAIRS	83	CF	
003C	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0031	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING	Lump Sum	L.S.	
0032	8860000000-N	SP	GENERIC STRUCTURE ITEM CLEANING & PAINTING EXISTING BEARING PLATES	Lump Sum	L.S.	
003E	8881000000-E	SP	GENERIC STRUCTURE ITEM LATEX MODIFIED CONCRETE OVER- LAY - VERY EARLY STRENGTH	239	CY	
0034	8892000000-E	SP	GENERIC STRUCTURE ITEM CLASS II CONC DECK REPAIRS FOR EPOXY OR ASPHALT OVERLAY	19,486	SF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	8892000000-E	SP	GENERIC STRUCTURE ITEM PLACEMENT OF EPOXY OVERLAY	62,450	SF	
0036	8892000000-E	SP	GENERIC STRUCTURE ITEM PLACEMENT OF PRE-TREATMENT	62,450	SF	
0037	8893000000-E	SP	GENERIC STRUCTURE ITEM HYDRO-DEMOLITION OF BRIDGE DECK	4,439	SY	
0038	8893000000-E	SP	GENERIC STRUCTURE ITEM PLACING & FINISHING LATEX MOD CONC OVERLAY - VERY EARLY STRENGTH	4,439	SY	
0039	8893000000-E	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	4,439	SY	

1343/Apr13/Q210592.0/D220443300000/E39

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202963**

**County (ies):**    **Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General