

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (12+32.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	350 SY		
0007	0223000000-E	275	ROCK PLATING	65 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	20 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	48 LF		
0011	1099500000-E	505	SHALLOW UNDERCUT	85 CY		
0012	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	160 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	310 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	270 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	30 TON		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0018	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002C	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	16 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	2 EA		
0027	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	4 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	860 SY		
003C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	379 LF		
0032	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	393 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	269 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	176 LF		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,840	LF	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	1,200	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
004C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	25	TON	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	160	TON	
0042	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
004E	6029000000-E	SP	SAFETY FENCE	300	LF	
0047	6030000000-E	1630	SILT EXCAVATION	60	CY	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500	SY	
004E	6037000000-E	SP	COIR FIBER MAT	200	SY	
005C	6042000000-E	1632	1/4" HARDWARE CLOTH	100	LF	
0051	6070000000-N	1639	SPECIAL STILLING BASINS	6	EA	
0052	6071010000-E	SP	WATTLE	50	LF	
0052	6071030000-E	1640	COIR FIBER BAFFLE	70	LF	
0054	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
005E	6084000000-E	1660	SEEDING & MULCHING	1	ACR	

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6087000000-E	1660	MOWING	0.5 ACR		
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006C	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0061	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

---

**STRUCTURE ITEMS**


---

006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12 + 32.50-L-)	Lump Sum	L.S.	
0064	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	34 LF		
006E	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	26 LF		
006E	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	30 LF		
0067	8113000000-N	411	SID INSPECTIONS	1 EA		
006E	8115000000-N	411	CSL TESTING	1 EA		
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12 + 32.50-L-)	Lump Sum	L.S.	
007C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	44.6 CY		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+32.50-L-)	Lump Sum	L.S.	
0072	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,403 LB		
0073	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,375 LB		
0074	8364000000-E	450	HP12X53 STEEL PILES	340 LF		
007E	8475000000-E	460	TWO BAR METAL RAIL	175.25 LF		
007E	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-9 3/4")	190.25 LF		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	290 TON		
007E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	325 SY		
007E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008C	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,045 LF		
1431/Jun04/Q29577.25/D378208430000/E80			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C202841**

**County (ies):**   **Gaston**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)