

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0015000000-N	205	SEALING ABANDONED WELLS	2 EA		
000E	0022000000-E	225	UNCLASSIFIED EXCAVATION	48,000 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (243 + 80.50)	Lump Sum	L.S.	
000E	0036000000-E	225	UNDERCUT EXCAVATION	325 CY		
000E	0038000000-E	SP	SHALLOW UNDERCUT	140 CY		
001C	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	390 CY		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	16,020 SY		
0013	0195000000-E	SP	SELECT GRANULAR MATERIAL	610 CY		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
001E	0199000000-E	SP	TEMPORARY SHORING	375 SF		
001E	0223000000-E	SP	ROCK PLATING	1,500 SY		
0017	0241000000-E	SP	GENERIC GRADING ITEM REINFORCED SOIL SLOPES	2,900 SY		
001E	0241000000-E	SP	GENERIC GRADING ITEM SOIL NAIL SLOPE STABILIZATION	2,500 SY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0262000000-N	SP	GENERIC GRADING ITEM SOIL NAIL PROOF TESTS	15 EA		
0020	0262000000-N	SP	GENERIC GRADING ITEM SOIL NAIL VERIFICATION TESTS	4 EA		
0021	0262000000-N	SP	GENERIC GRADING ITEM SUPPLEMENTAL SOIL NAILS	25 EA		
0022	0318000000-E	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,530 TON		
0023	0320000000-E	SP	FOUNDATION CONDITIONING FABRIC	3,430 SY		
0024	0335000000-E	SP	*** DRAINAGE PIPE (2")	96 LF		
002E	0335100000-E	SP	12" DRAINAGE PIPE	40 LF		
0026	0335200000-E	SP	15" DRAINAGE PIPE	2,112 LF		
0027	0335300000-E	SP	18" DRAINAGE PIPE	808 LF		
002E	0335400000-E	SP	24" DRAINAGE PIPE	56 LF		
0029	0335850000-E	SP	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
003C	0378000000-E	SP	24" RC PIPE CULVERTS, CLASS III	140 LF		
0031	0448200000-E	SP	15" RC PIPE CULVERTS, CLASS IV	628 LF		
0032	0448300000-E	SP	18" RC PIPE CULVERTS, CLASS IV	716 LF		
0033	0448400000-E	SP	24" RC PIPE CULVERTS, CLASS IV	316 LF		
0034	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (30", 0.138")	144 LF		
003E	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (42", 0.109")	184 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (48", 0.109")	88 LF		
0037	0576000000-E	SP	*** CS PIPE CULVERTS, ***** THICK (60", 0.138")	64 LF		
003E	0582000000-E	SP	15" CS PIPE CULVERTS, 0.064" THICK	212 LF		
003E	0588000000-E	SP	18" CS PIPE CULVERTS, 0.064" THICK	1,380 LF		
004C	0594000000-E	SP	24" CS PIPE CULVERTS, 0.064" THICK	252 LF		
0041	0600000000-E	SP	30" CS PIPE CULVERTS, 0.079" THICK	168 LF		
0042	0636000000-E	SP	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
004E	0995000000-E	340	PIPE REMOVAL	5,172 LF		
0044	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
004E	1121000000-E	520	AGGREGATE BASE COURSE	6,900 TON		
004E	1220000000-E	545	INCIDENTAL STONE BASE	10,000 TON		
0047	1231000000-E	560	SHOULDER BORROW	4,000 CY		
004E	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***** DEPTH (2")	2,380 SY		
004E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	16,500 TON		
005C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	18,700 TON		
0051	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	12,000 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1575000000-E	SP	ASPHALT BINDER FOR PLANT MIX	2,240 TON		
0053	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	400 TON		
0054	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	17,800 LF		
005E	2022000000-E	SP	SUBDRAIN EXCAVATION	67.2 CY		
005E	2033000000-E	SP	SUBDRAIN FINE AGGREGATE	50.4 CY		
0057	2044000000-E	SP	6" PERFORATED SUBDRAIN PIPE	300 LF		
005E	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	1 EA		
005E	2077000000-E	SP	6" OUTLET PIPE (SUBDRAINS)	6 LF		
006C	2209000000-E	838	ENDWALLS	18.7 CY		
0061	2220000000-E	838	REINFORCED ENDWALLS	5.6 CY		
0062	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	37 EA		
0063	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	11.81 LF		
0064	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	9 EA		
006E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	9 EA		
006E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0067	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
006E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	3 EA		
007C	2396000000-N	840	FRAME WITH COVER, STD 840.54	6 EA		
0071	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	190 LF		
0072	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	800 LF		
0073	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,370 LF		
0074	2556000000-E	846	SHOULDER BERM GUTTER	603 LF		
007E	2591000000-E	848	4" CONCRETE SIDEWALK	190 SY		
0076	2612000000-E	848	6" CONCRETE DRIVEWAY	210 SY		
0077	2619000000-E	850	4" CONCRETE PAVED DITCH	90 SY		
007E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	170 SY		
0079	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	300 LF		
008C	2738000000-E	SP	GENERIC PAVING ITEM 7" CONCRETE MONOLITHIC TRUCK APRON	220 SY		
0081	2752000000-E	SP	GENERIC PAVING ITEM PEDESTRIAN SAFETY RAIL	300 LF		
0082	2759000000-N	SP	GENERIC PAVING ITEM CONCRETE CURB RAMPS	2 EA		
0083	2830000000-N	858	ADJUSTMENT OF MANHOLES	6 EA		
0084	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	31 EA		
008E	3030000000-E	862	STEEL BM GUARDRAIL	3,500 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	400 LF		
0087	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	40 EA		
008E	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	1 EA		
008E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
009C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0091	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	26 EA		
0092	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
009C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	170 LF		
0094	3628000000-E	876	RIP RAP, CLASS I	150 TON		
009E	3642000000-E	876	RIP RAP, CLASS A	760 TON		
009E	3649000000-E	876	RIP RAP, CLASS B	730 TON		
0097	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	8,525 SY		
009E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,995 LF		
009E	4102000000-N	904	SIGN ERECTION, TYPE E	124 EA		
010C	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0101	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	82 EA		
0102	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,025 SF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
0104	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	309	SF	
0105	4430000000-N	1130	DRUMS	240	EA	
0106	4435000000-N	1135	CONES	10	EA	
0107	4445000000-E	1145	BARRICADES (TYPE III)	168	LF	
0108	4450000000-N	1150	FLAGGER	4,800	HR	
0109	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
011C	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	233	EA	
0111	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	50,372	LF	
0112	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	49,247	LF	
0113	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	267	LF	
0114	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	464	LF	
011E	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	34	LF	
0116	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	546	LF	
0117	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12	EA	
0118	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	41	EA	
0119	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	62,666	LF	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012C	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	344 LF		
0121	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	370 LF		
0122	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16 EA		
0123	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	640 EA		
0124	5325800000-E	1510	8" WATER LINE	240 LF		
012E	5326200000-E	1510	12" WATER LINE	1,930 LF		
012E	5546000000-E	1515	8" VALVE	4 EA		
0127	5558000000-E	1515	12" VALVE	16 EA		
012E	5648000000-N	1515	RELOCATE WATER METER	15 EA		
012E	5672000000-N	1515	RELOCATE FIRE HYDRANT	14 EA		
013C	5691200000-E	1520	6" SANITARY GRAVITY SEWER	75 LF		
0131	5691300000-E	1520	8" SANITARY GRAVITY SEWER	631 LF		
0132	5775000000-E	1525	4' DIA UTILITY MANHOLE	7 EA		
0133	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	10.3 LF		
0134	5800000000-E	1530	ABANDON 6" UTILITY PIPE	75 LF		
013E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	1,128 LF		
013E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	620 LF		
0137	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
013E	5828000000-N	1530	REMOVE UTILITY MANHOLE	7 EA		
013E	5835700000-E	1540	16" ENCASEMENT PIPE	30 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014C	5871900000-E	1550	TRENCHLESS INSTALLATION OF 16" IN SOIL	15 LF		
0141	5871910000-E	1550	TRENCHLESS INSTALLATION OF 16" NOT IN SOIL	15 LF		
0142	6000000000-E	1605	TEMPORARY SILT FENCE	25,125 LF		
0143	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,680 TON		
0144	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	4,955 TON		
014E	6012000000-E	1610	SEDIMENT CONTROL STONE	1,280 TON		
014E	6015000000-E	1615	TEMPORARY MULCHING	31 ACR		
0147	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	750 LB		
014E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3 TON		
014E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	585 LF		
015C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	12 EA		
0151	6029000000-E	SP	SAFETY FENCE	1,500 LF		
0152	6030000000-E	1630	SILT EXCAVATION	4,880 CY		
0153	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,675 SY		
0154	6037000000-E	SP	COIR FIBER MAT	660 SY		
015E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	600 SY		
015E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,680 LF		
0157	6045000000-E	SP	*** TEMPORARY PIPE (18")	35 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
015E	6069000000-E	1638	STILLING BASINS	14 CY		
015E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	285 LB		
016C	6071030000-E	SP	COIR FIBER BAFFLE	455 LF		
0161	6084000000-E	1660	SEEDING & MULCHING	21 ACR		
0162	6087000000-E	1660	MOWING	21 ACR		
0163	6090000000-E	1661	SEED FOR REPAIR SEEDING	350 LB		
0164	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
016E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	500 LB		
016E	6108000000-E	1665	FERTILIZER TOPDRESSING	15 TON		
0167	6111000000-E	SP	IMPERVIOUS DIKE	50 LF		
016E	6114500000-N	SP	SPECIALIZED HAND MOWING	25 MHR		
016E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	100 EA		
017C	6120000000-E	SP	CULVERT DIVERSION CHANNEL	363 CY		
0171	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/ COUNTDOWN)	4 EA		
0172	7060000000-E	1705	SIGNAL CABLE	2,090 LF		
0173	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	19 EA		
0174	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	8 EA		
017E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3 EA		
017E	7264000000-E	1710	MESSENGER CABLE (3/8")	1,130 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0177	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,160	LF	
017E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	13	EA	
017E	7360000000-N	1720	WOOD POLE	4	EA	
018C	7372000000-N	1721	GUY ASSEMBLY	8	EA	
0181	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1	EA	
0182	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4	EA	
018E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,750	LF	
0184	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	6,410	LF	
018E	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4	EA	
018E	7613000000-N	SP	SOIL TEST	4	EA	
0187	7614100000-E	SP	DRILLED PIER FOUNDATION	60	CY	
018E	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	1	EA	
018E	7636000000-N	1745	SIGN FOR SIGNALS	2	EA	
019C	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
0191	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2	EA	
0192	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	13	EA	
019E	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
0194	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1	EA	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
019E	8126000000-N	414	CULVERT EXCAVATION, STA ***** (374 + 00-L-)	Lump Sum	L.S.	
019E	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	75 TON		
0197	8196000000-E	420	CLASS A CONCRETE (CULVERT)	60.9 CY		
019E	8245000000-E	425	REINFORCING STEEL (CULVERT)	6,295 LB		
WALL ITEMS						
019E	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	1,780 SF		
STRUCTURE ITEMS						
020C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (243 + 80.50-L-)	Lump Sum	L.S.	
0201	8096000000-E	SP	PILE EXCAVATION IN SOIL	45 LF		
0202	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	59 LF		
020E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (243 + 80.50-L-)	Lump Sum	L.S.	
0204	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	77.8 CY		
020E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (243 + 80.50-L-)	Lump Sum	L.S.	
020E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,815 LB		
0207	8384000000-E	SP	HP14X73 STEEL PILES	405 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
020E	8391000000-N	SP	STEEL PILE POINTS	18 EA		
020E	8475000000-E	460	TWO BAR METAL RAIL	94.4 LF		
021C	8517000000-E	460	1'-***"X ***** CONCRETE PARA- PET (1'-2" X 2'-9 3/4")	110 LF		
0211	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	100 TON		
0212	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	90 SY		
021E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0214	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	715 LF		

1536/Jun12/Q464179.11/D887724024000/E214

Total Amount Of Bid For Entire Project :

Contract No **C202743**

County (ies): **Henderson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General