

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (11 + 04.50-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	20 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	20 SY		
0007	0199000000-E	SP	TEMPORARY SHORING	464 SF		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	3 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	7 SY		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	20 LF		
0011	1099500000-E	505	SHALLOW UNDERCUT	20 CY		
0012	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	20 TON		
0013	1121000000-E	520	AGGREGATE BASE COURSE	170 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1275000000-E	600	PRIME COAT	120 GAL		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	70 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	220 TON		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	17	TON	
001S	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20	TON	
002C	2022000000-E	815	SUBDRAIN EXCAVATION	11.2	CY	
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	8.4	CY	
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	50	LF	
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0024	2077000000-E	815	6" OUTLET PIPE	6	LF	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
0027	2556000000-E	846	SHOULDER BERM GUTTER	46	LF	
002E	3030000000-E	862	STEEL BM GUARDRAIL	12.5	LF	
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75	LF	
003C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0031	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	3	EA	
0032	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	4	EA	
0033	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	37.5	LF	
0034	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	175	LF	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	4	EA	
003E	3389000000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	3	EA	
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,300	SY	
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	130	LF	
003E	4102000000-N	904	SIGN ERECTION, TYPE E	7	EA	
004C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4	EA	
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	72	SF	
0042	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128	SF	
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	32	SF	
0044	4430000000-N	1130	DRUMS	20	EA	
004E	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	
004E	4450000000-N	1150	FLAGGER	1,000	HR	
0047	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
004E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	47	LF	
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,458	LF	
005C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	30	LF	
0051	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	5	EA	
0052	6000000000-E	1605	TEMPORARY SILT FENCE	1,600	LF	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	230 TON		
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	400 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
006C	6029000000-E	SP	SAFETY FENCE	700 LF		
0061	6030000000-E	1630	SILT EXCAVATION	50 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	600 LF		
0064	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	0.25 ACR		
006E	6087000000-E	1660	MOWING	0.15 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007C	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0071	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6123000000-E	1670	REFORESTATION	0.1	ACR	

WALL ITEMS						

0074	8802010000-E	SP	SOIL NAIL RETAINING WALLS	440	SF	

STRUCTURE ITEMS						

007E	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (11 + 04.50-L-)	Lump Sum	L.S.	

007E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (11 + 04.50-L-)	Lump Sum	L.S.	

0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11 + 04.50-L-)	Lump Sum	L.S.	

007E	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	41	LF	

007E	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	46	LF	

008C	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	32.4	LF	

0081	8115000000-N	411	CSL TESTING	1	EA	

0082	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (11 + 04.50-L-)	Lump Sum	L.S.	

0083	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	67.6	CY	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0084	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11 + 04.50-L-)	Lump Sum	L.S.	
008E	821700000-E	425	REINFORCING STEEL (BRIDGE)	23,191 LB		
008E	823800000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,853 LB		
0087	836400000-E	450	HP12X53 STEEL PILES	285 LF		
008E	846800000-E	460	ONE BAR METAL RAIL	295.5 LF		
008E	851700000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-10")	170.5 LF		
009C	851700000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-11 1/2")	140 LF		
0091	860800000-E	876	RIP RAP CLASS II (2'-0" THICK)	330 TON		
0092	862200000-E	876	GEOTEXTILE FOR DRAINAGE	367 SY		
009E	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	876200000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	935 LF		
009E	876300000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		

Contract No. **C202840**

County (ies): **Jackson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General

Signature Sheet (Bid - Acceptance by Department)