

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (18+31.08 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	115 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	30 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	24 LF		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	40 LF		
0013	0995000000-E	340	PIPE REMOVAL	42 LF		
0014	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0015	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	270 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	225 TON		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	30 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	325 LF		
0028	2619000000-E	850	4" CONCRETE PAVED DITCH	80 SY		
0029	3030000000-E	862	STEEL BM GUARDRAIL	350 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0032	3389000000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (TL-2)	4 EA		
0033	3435000000-N	SP	GENERIC GUARDRAIL ITEM EXTRA LENGTH GUARDRAIL POST, 8' STEEL	90 EA		
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	525 SY		
0035	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	30 LF		
0036	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	382 SF		
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	219 SF		
0040	4445000000-E	1145	BARRICADES (TYPE III)	144 LF		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,816 LF		
0042	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	61 EA		
0043	6000000000-E	1605	TEMPORARY SILT FENCE	1,150 LF		
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250 TON		
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	115 TON		
0047	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0051	6029000000-E	SP	SAFETY FENCE	100 LF		
0052	6030000000-E	1630	SILT EXCAVATION	90 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	355 LF		
0055	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		
0056	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6087000000-E	1660	MOWING	0.25	ACR	
0058	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0059	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0060	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	
0062	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0063	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	

---

**WALL ITEMS**


---

0064	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 1	3,330	SF	
------	--------------	----	--	-------	----	--

---

**STRUCTURE ITEMS**


---

0065	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+31.08-L-)	Lump Sum	L.S.	
0066	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (2,18+31.08-L-)	Lump Sum	L.S.	
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+31.08-L-)	Lump Sum	L.S.	
0068	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,815	SF	
0069	8161000000-E	420	GROOVING BRIDGE FLOORS	3,485	SF	
0070	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	84.2	CY	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+31.08-L-)	Lump Sum	L.S.	
0072	821700000-E	425	REINFORCING STEEL (BRIDGE)	12,413 LB		
0073	828000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	192,700 LS		
0074	836400000-E	450	HP12X53 STEEL PILES	160 LF		
0075	850300000-E	460	CONCRETE BARRIER RAIL	279.83 LF		
0076	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	869200000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
1513/Jun12/Q230600.28/D329843420000/E77			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C202843**

**County (ies):**   **Jackson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date.

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General