

County : Moore, Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	1,155 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	2,185 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	61.27 SMI		
000E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	22,475 SY		
000E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	2,700 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	5,625 SY		
000E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	8,840 TON		
000E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	18,200 TON		
001C	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	23,880 TON		
0011	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	3,079 TON		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	4,260 TON		
001E	2830000000-N	858	ADJUSTMENT OF MANHOLES	23 EA		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	33 EA		
001E	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
001E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	234,350 LF		
0017	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	130,850 LF		

County : Moore, Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,350	LF	
001E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	790	LF	
002C	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	380	LF	
0021	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	404	LF	
0022	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	22	EA	
0023	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	73	EA	
0024	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	2,200	LF	
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	439,950	LF	
002E	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	100	LF	
0027	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	280	LF	
002E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	4	EA	
002E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4	EA	
003C	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,200	LF	
0031	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,208	EA	
0032	6000000000-E	1605	TEMPORARY SILT FENCE	4,477	LF	
003E	6071010000-E	SP	WATTLE	11,190	LF	

County : Moore, Lee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	6084000000-E	1660	SEEDING & MULCHING	44.81	ACR	
003E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,100	LF	
1623/Jun07/Q927495.08/D126295110000/E35			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C203118**

**County (ies):**    **Moore & Lee**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General