

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	27,000 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	400 CY		
0007	0106000000-E	230	BORROW EXCAVATION	170,500 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,400 CY		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,540 SY		
0010	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	4,040 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0012	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	3,800 SY		
0013	0199000000-E	SP	TEMPORARY SHORING	4,874.5 SF		
0014	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION & STOCKPILING CONTAMINATED SOIL	200 TON		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	916 TON		
0016	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	7,260 SY		
0017	0342000000-E	310	*** SIDE DRAIN PIPE (30")	592 LF		
0018	0343000000-E	310	15" SIDE DRAIN PIPE	800 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0344000000-E	310	18" SIDE DRAIN PIPE	120 LF		
0020	0345000000-E	310	24" SIDE DRAIN PIPE	52 LF		
0021	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	5 EA		
0022	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	368 LF		
0023	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	412 LF		
0024	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	80 LF		
0025	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (66")	216 LF		
0026	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	2,044 LF		
0027	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	188 LF		
0028	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	136 LF		
0029	0453000000-E	310	*** PIPE END SECTION (18")	1 EA		
0030	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	12 LF		
0031	0986000000-E	SP	GENERIC PIPE ITEM 15" DUCTILE IRON PIPE (SEALED SYSTEM)	332 LF		
0032	0986000000-E	SP	GENERIC PIPE ITEM 18" DUCTILE IRON PIPE (SEALED SYSTEM)	164 LF		
0033	0986000000-E	SP	GENERIC PIPE ITEM 60" DUCTILE IRON PIPE (SEALED SYSTEM)	532 LF		
0034	0995000000-E	340	PIPE REMOVAL	1,784 LF		
0035	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1099500000-E	505	SHALLOW UNDERCUT	1,000 CY		
0037	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	2,000 TON		
0038	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0039	1121000000-E	520	AGGREGATE BASE COURSE	1,390 TON		
0040	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0041	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	5,080 SY		
0042	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	970 TON		
0043	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	9,880 TON		
0044	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	950 TON		
0045	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	9,710 TON		
0046	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,660 TON		
0047	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	9,040 TON		
0048	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,625 TON		
0049	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	98 TON		
0050	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	7,090 LF		
0051	1891000000-E	SP	GENERIC PAVING ITEM GEOTEXTILE FOR PAVEMENT STABILIZATION	13,000 SY		
0052	2220000000-E	838	REINFORCED ENDWALLS	16.6 CY		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2253000000-E	840	PIPE COLLARS	2.138 CY		
0054	2264000000-E	840	PIPE PLUGS	0.232 CY		
0055	2275000000-E	SP	FLOWABLE FILL	25 CY		
0056	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	57 EA		
0057	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	37.06 CY		
0058	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	12.91 LF		
0059	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
0060	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	9 EA		
0061	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0062	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	12 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	13 EA		
0065	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	12 EA		
0066	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0067	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	9 EA		
0068	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	1 EA		
0069	2538000000-E	846	***.*** CONCRETE CURB & GUTTER (2'-0")	130 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	4,160 LF		
0071	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	4,270 LF		
0072	2556000000-E	846	SHOULDER BERM GUTTER	310 LF		
0073	2591000000-E	848	4" CONCRETE SIDEWALK	1,220 SY		
0074	2605000000-N	848	CONCRETE CURB RAMP	20 EA		
0075	2612000000-E	848	6" CONCRETE DRIVEWAY	40 SY		
0076	2619000000-E	850	4" CONCRETE PAVED DITCH	370 SY		
0077	2627000000-E	852	4" CONCRETE ISLAND COVER	40 SY		
0078	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,280 SY		
0079	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (SINGLE SLOPE)	530 LF		
0080	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0081	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0082	3030000000-E	862	STEEL BM GUARDRAIL	2,762.5 LF		
0083	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	162.5 LF		
0084	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	4 EA		
0085	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	2 EA		
0086	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	4 EA		
0087	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0089	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7	EA	
0090	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,920	LF	
0091	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	125	LF	
0092	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (AT-1)	1	EA	
0093	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (III)	2	EA	
0094	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	5	EA	
0095	3500000000-E	866	WOVEN WIRE FENCE, *** FABRIC (48")	3,760	LF	
0096	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	240	EA	
0097	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	60	EA	
0098	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	1,440	LF	
0099	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	119	EA	
0100	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	17	EA	
0101	3628000000-E	876	RIP RAP, CLASS I	80	TON	
0102	3649000000-E	876	RIP RAP, CLASS B	35	TON	
0103	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,785	SY	
0104	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	27	CY	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0105	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 CY		
0106	4057000000-E	SP	OVERHEAD FOOTING	60 CY		
0107	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	21,210 LB		
0108	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,507 LF		
0109	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	4 EA		
0110	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (15+50-L-)	Lump Sum	L.S.	
0111	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (19+50-RP B-)	Lump Sum	L.S.	
0112	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (19+57-RP D-)	Lump Sum	L.S.	
0113	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (28+45-L-)	Lump Sum	L.S.	
0114	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0115	4102000000-N	904	SIGN ERECTION, TYPE E	69 EA		
0116	4108000000-N	904	SIGN ERECTION, TYPE F	7 EA		
0117	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	14 EA		
0118	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	8 EA		
0119	4114000000-N	904	SIGN ERECTION, MILEMARKERS	4 EA		
0120	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	7 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0122	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	7 EA		
0123	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	15 EA		
0124	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	49 EA		
0125	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1 EA		
0126	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2 EA		
0127	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	328 SF		
0128	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	688 SF		
0129	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0130	4415000000-N	1115	FLASHING ARROW BOARD	4 EA		
0131	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		
0132	4430000000-N	1130	DRUMS	470 EA		
0133	4445000000-E	1145	BARRICADES (TYPE III)	148 LF		
0134	4450000000-N	1150	FLAGGER	7,200 HR		
0135	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0136	4480000000-N	1165	TMA	4 EA		
0137	4485000000-E	1170	PORTABLE CONCRETE BARRIER	954 LF		
0138	4510000000-N	SP	LAW ENFORCEMENT	160 HR		
0139	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	80 EA		



County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,600 LF		
0141	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	7,844 LF		
0142	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	28,740 LF		
0143	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	6,622 LF		
0144	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	300 LF		
0145	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	925 LF		
0146	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,060 LF		
0147	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0148	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	101 EA		
0149	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	1,350 LF		
0150	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	43,660 LF		
0151	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	5,549 LF		
0152	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	10,504 LF		
0153	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	2,417 LF		
0154	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,205 LF		
0155	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	16 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0156	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	111 EA		
0157	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,813 LF		
0158	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	9,292 LF		
0159	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	50 LF		
0160	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	532 EA		
0161	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	130 EA		
0162	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	50 EA		
0163	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	10 EA		
0164	5025000000-E	SP	HIGH MOUNT FOUNDATIONS	14.8 CY		
0165	5070000000-N	1405	STANDARD FOUNDATION ***** (R1)	8 EA		
0166	5070000000-N	1405	STANDARD FOUNDATION ***** (R2)	2 EA		
0167	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30', CLASS 4)	1 EA		
0168	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/0 USE)	65 LF		
0169	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	85 LF		
0170	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	285 LF		
0171	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (4")	45 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0172	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	95 LF		
0173	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	130 LF		
0174	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	215 LF		
0175	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	1,135 LF		
0176	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	275 LF		
0177	5190000000-E	1410	***** FEEDER CIRCUIT (2 #1 W/G)	1,482 LF		
0178	5190000000-E	1410	***** FEEDER CIRCUIT (2 #1/0 W/G)	515 LF		
0179	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	2,754 LF		
0180	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	895 LF		
0181	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	311 LF		
0182	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	740 LF		
0183	5225000000-E	1410	** #1 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, IN 2" CONDUIT)	1,220 LF		
0184	5230000000-E	1410	***** FEEDER CIRCUIT IN ** CONDUIT (2 #1/0 W/G, 2")	1,095 LF		
0185	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	9 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0186	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC30)	3 EA		
0187	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC36)	2 EA		
0188	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0189	5270000000-N	SP	GENERIC LIGHTING ITEM FOUNDATION COVER	2 EA		
0190	5270000000-N	SP	GENERIC LIGHTING ITEM RELOCATE CONTROL SYSTEM	1 EA		
0191	5270000000-N	SP	GENERIC LIGHTING ITEM RELOCATE LIGHT STANDARD	10 EA		
0192	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE HIGH MAST LIGHT STAND- ARD	2 EA		
0193	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE HIGH MAST STANDARD FOUNDATION	2 EA		
0194	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE LIGHT STANDARD FOUNDA- TION	12 EA		
0195	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE SINGLE ARM LIGHT STAND- ARD	2 EA		
0196	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE TWIN ARM LIGHT STANDARD	2 EA		
0197	5270000000-N	SP	GENERIC LIGHTING ITEM REPLACE LUMINAIRE, TYPE HIGH MAST, 1KW, HPS	8 EA		
0198	5270000000-N	SP	GENERIC LIGHTING ITEM REPLACE LUMINAIRE, TYPE RDW 250W HPS, MS2	22 EA		
0199	5325200000-E	1510	2" WATER LINE	143 LF		
0200	5325600000-E	1510	6" WATER LINE	218 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0201	5326200000-E	1510	12" WATER LINE	571 LF		
0202	5536000000-E	1515	2" VALVE	2 EA		
0203	5540000000-E	1515	6" VALVE	3 EA		
0204	5558000000-E	1515	12" VALVE	4 EA		
0205	5589200000-E	1515	2" AIR RELEASE VALVE	2 EA		
0206	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0207	5649000000-N	1515	RECONNECT WATER METER	2 EA		
0208	5672000000-N	1515	RELOCATE FIRE HYDRANT	5 EA		
0209	5691500000-E	1520	12" SANITARY GRAVITY SEWER	20 LF		
0210	5709300000-E	1520	6" FORCE MAIN SEWER	299 LF		
0211	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	5 EA		
0212	5804000000-E	1530	ABANDON 12" UTILITY PIPE	280 LF		
0213	6000000000-E	1605	TEMPORARY SILT FENCE	12,600 LF		
0214	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,320 TON		
0215	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	3,040 TON		
0216	6012000000-E	1610	SEDIMENT CONTROL STONE	2,360 TON		
0217	6015000000-E	1615	TEMPORARY MULCHING	49 ACR		
0218	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,400 LB		
0219	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6.25 TON		
0220	6024000000-E	1622	TEMPORARY SLOPE DRAINS	4,000 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0221	6029000000-E	SP	SAFETY FENCE	1,300 LF		
0222	6030000000-E	1630	SILT EXCAVATION	6,010 CY		
0223	6036000000-E	1631	MATTING FOR EROSION CONTROL	30,000 SY		
0224	6037000000-E	SP	COIR FIBER MAT	1,300 SY		
0225	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	3,930 SY		
0226	6042000000-E	1632	1/4" HARDWARE CLOTH	2,850 LF		
0227	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA		
0228	6071010000-E	SP	WATTLE	2,400 LF		
0229	6071012000-E	SP	COIR FIBER WATTLE	100 LF		
0230	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1,200 LB		
0231	6071030000-E	1640	COIR FIBER BAFFLE	2,000 LF		
0232	6071050000-E	SP	*** SKIMMER (1-1/2")	10 EA		
0233	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0234	6071050000-E	SP	*** SKIMMER (2-1/2")	1 EA		
0235	6084000000-E	1660	SEEDING & MULCHING	48 ACR		
0236	6087000000-E	1660	MOWING	28 ACR		
0237	6090000000-E	1661	SEED FOR REPAIR SEEDING	500 LB		
0238	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.75 TON		
0239	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,175 LB		
0240	6108000000-E	1665	FERTILIZER TOPDRESSING	35 TON		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0241	6114500000-N	1667	SPECIALIZED HAND MOWING	60 MHR		
0242	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75 EA		
0243	7048500000-E	1705	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)	16 EA		
0244	7060000000-E	1705	SIGNAL CABLE	10,185 LF		
0245	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	49 EA		
0246	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	7 EA		
0247	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3 EA		
0248	7264000000-E	1710	MESSENGER CABLE (3/8")	2,045 LF		
0249	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	2,960 LF		
0250	7300000000-E	1715	UNPAVED TRENCHING (*****) (2, 2")	20 LF		
0251	7300000000-E	1715	UNPAVED TRENCHING (*****) (3, 2")	40 LF		
0252	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP-ORARY LEAD-IN	2,980 LF		
0253	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	440 LF		
0254	7301000000-E	1715	DIRECTIONAL DRILL (*****) (2, 2")	155 LF		
0255	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	50 EA		
0256	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	4 EA		
0257	7360000000-N	1720	WOOD POLE	7 EA		
0258	7372000000-N	1721	GUY ASSEMBLY	20 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0259	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0260	7420000000-E	1722	2" RISER WITH WEATHERHEAD	12 EA		
0261	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,600 LF		
0262	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	27,920 LF		
0263	7575142000-N	1736	900MHZ RADIO	6 EA		
0264	7575142060-N	SP	MODIFY RADIO INSTALLATION	1 EA		
0265	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	2,400 LF		
0266	7576000000-N	SP	METAL STRAIN SIGNAL POLE	5 EA		
0267	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	4 EA		
0268	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	2 EA		
0269	7613000000-N	SP	SOIL TEST	11 EA		
0270	7614100000-E	SP	DRILLED PIER FOUNDATION	77 CY		
0271	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	6 EA		
0272	7636000000-N	1745	SIGN FOR SIGNALS	19 EA		
0273	7642100000-N	1743	TYPE I POST WITH FOUNDATION	2 EA		
0274	7642200000-N	1743	TYPE II PEDESTAL WITH FOUND- ATION	17 EA		
0275	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0276	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0277	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		



County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0278	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	28 EA		
0279	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
0280	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	1 EA		
0281	7972000000-N	SP	METAL POLE REMOVAL	1 EA		
0282	7985000000-N	SP	GENERIC SIGNAL ITEM REMOVE OVER HEIGHT VEHICLE DETECTION SYSTEM	Lump Sum	L.S.	
0305	1330000000-E	607	INCIDENTAL MILLING	500 SY		
<b>WALL ITEMS</b>						
0283	8802031000-E	SP	PRECAST GRAVITY RETAINING WALLS	720 SF		
0284	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL #1	3,530 SF		
0285	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL #2	3,620 SF		
<b>STRUCTURE ITEMS</b>						
0286	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+37.56-L-SBL)	Lump Sum	L.S.	
0287	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (32+45.00-L-)	Lump Sum	L.S.	
0288	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 22+37.56-L-NBL)	Lump Sum	L.S.	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0289	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 22+37.56-L-SBL)	Lump Sum	L.S.	
0290	8112730000-N	450	PDA TESTING	2 EA		
0291	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	16,746 SF		
0292	8161000000-E	420	GROOVING BRIDGE FLOORS	16,021 SF		
0293	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	545.3 CY		
0294	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+37.56-L-NBL)	Lump Sum	L.S.	
0295	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+37.56-L-SBL)	Lump Sum	L.S.	
0296	8217000000-E	425	REINFORCING STEEL (BRIDGE)	88,074 LB		
0297	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,788 LB		
0298	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	1,872.56 LF		
0299	8364000000-E	450	HP12X53 STEEL PILES	6,420 LF		
0300	8393000000-N	450	PILE REDRIVES	22 EA		
0301	8475000000-E	460	TWO BAR METAL RAIL	1,020 LF		
0302	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	1,050.91 LF		
0303	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0304	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	

**Contract No.**     **C202847**

**County (ies):**   **Robeson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**

Signature Sheet (Bid - Acceptance by Department)