



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE  
GOVERNOR

EUGENE A. CONTI, JR.  
SECRETARY

August 10, 2012

**Addendum No. 2**

RE: Contract ID C202845  
WBS # 33725.3.1  
F. A. # BRSTP-1763(4)  
**Craven County (B-4488)**  
Bridge Over Slocum Creek And Approaches On SR-1763

**August 21, 2012 Letting**

To Whom It May Concern:

Reference is made to the proposal form recently furnished to you on this project.

The following revisions have been made to the proposal:

Page No. 66 has been revised to add the project special provision entitled "Impervious Dike". Please void Page No.66 in your proposal and staple the revised Page No. 66 thereto. Also, New Page No. 66-A has been added to include the project special provision entitled "Pumping Operations For Culvert Installation". Please staple New Page No. 66-A after revised Page No. 66 in your proposal.

On Page No. 4 of the item sheets the following pay items have been added:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
94-6070000000-N-1639	Special Stilling Basin	NEW ITEM	5 EA
95-6111000000-E-SP	Impervious Dike	NEW ITEM	300 LF

The Contractor's bid must include these new pay items. The contract will be prepared accordingly.

The Expedite File has been updated to reflect these revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,

R. A. Garris, PE  
Contract Officer

**MAILING ADDRESS:**

NC DEPARTMENT OF TRANSPORTATION  
CONTRACT STANDARDS AND DEVELOPMENT UNIT  
1591 MAIL SERVICE CENTER  
RALEIGH NC 27699-1591

TELEPHONE: 919-707-6900

FAX: 919-250-4119

WEBSITE: [WWW.NCDOT.ORG](http://WWW.NCDOT.ORG)

**LOCATION:**

CENTURY CENTER COMPLEX  
ENTRANCE B-2  
1020 BIRCH RIDGE DRIVE  
RALEIGH NC 27610

RAG/jag

Attachments

cc: Mr. Ron Hancock, PE  
Mr. C. E. Lassiter, PE  
Ms. D. M. Barbour, PE  
Mr. J. V. Barbour, PE  
Mr. R.E. Davenport, PE  
Mr. Ray Arnold, PE  
Project File (2)

Ms. Natalie Roskam, PE  
Ms. Marsha Sample  
Mr. Ronnie Higgins  
Mr. Larry Strickland  
Ms. Lori Strickland  
Ms. Penny Higgins  
Ms. Jaci Kincaid

**Measurement and Payment**

*Floating Turbidity Curtain* will be measured and paid for as the actual number of square yards of curtain furnished as specified and accepted. Such price and payment will be full compensation for the work as described in this section including but not limited to furnishing all materials, tools, equipment, and all incidentals necessary to complete the work.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Floating Turbidity Curtain	Square Yard

**IMPERVIOUS DIKE:****Description**

This work consists of furnishing, installing, maintaining, and removing an *Impervious Dike* for the purpose of diverting normal stream flow around the construction site. The Contractor shall construct an impervious dike in such a manner approved by the Engineer. The impervious dike shall not permit seepage of water into the construction site or contribute to siltation of the stream. The impervious dike shall be constructed of an acceptable material in the locations noted on the plans or as directed.

**Materials**

Acceptable materials shall include but not be limited to sheet piles, sandbags, and/or the placement of an acceptable size stone lined with polypropylene or other impervious geotextile.

Earth material shall not be used to construct an impervious dike when it is in direct contact with the stream unless vegetation can be established before contact with the stream takes place.

**Measurement and Payment**

*Impervious Dike* will be measured and paid as the actual number of linear feet of impervious dike(s) constructed, measured in place from end to end of each separate installation that has been completed and accepted. Such price and payment will be full compensation for all work including but not limited to furnishing materials, construction, maintenance, and removal of the impervious dike.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Impervious Dike	Linear Foot

**PUMPING OPERATIONS FOR CULVERT INSTALLATION:**

The pumping operations shall include but not be limited to, installation of impervious dikes, pumping the stream around the work area and pumping runoff from the work area into a stilling basin, special stilling basin or other sediment control device as directed. Payment for pumping operations for the installation of all pipes and culverts shall be considered incidental to the other erosion control items in the contract. No additional payment will be made for furnishing materials or maintenance of the pumping operations for the installation of pipes and culverts.