

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (25 + 55.00-L-)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (52 + 15.00-L-)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	800 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0106000000-E	230	BORROW EXCAVATION	28,000 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	800 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,000 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	1,120 SF		
0012	0241000000-E	SP	GENERIC GRADING ITEM REINFORCED SOIL SLOPES	950 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	626 TON		
0014	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	1,949 SY		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	696 LF		
0016	0344000000-E	310	18" SIDE DRAIN PIPE	40 LF		
0017	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	2,644 LF		
0018	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	344 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	20	LF	
0020	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (42", 0.109")	104	LF	
0021	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (42", 0.109")	2	EA	
0022	0995000000-E	340	PIPE REMOVAL	45	LF	
0023	1000000000-E	462	6" SLOPE PROTECTION	200	SY	
0024	1121000000-E	520	AGGREGATE BASE COURSE	130	TON	
0025	1220000000-E	545	INCIDENTAL STONE BASE	200	TON	
0026	1330000000-E	607	INCIDENTAL MILLING	280	SY	
0027	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	410	TON	
0028	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	3,635	TON	
0029	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	100	TON	
0030	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C	3,640	TON	
0031	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	160	TON	
0032	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,360	TON	
0033	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	250	TON	
0034	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	705	TON	
0035	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	94	TON	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2022000000-E	815	SUBDRAIN EXCAVATION	90 CY		
0037	2033000000-E	815	SUBDRAIN FINE AGGREGATE	69 CY		
003E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400 LF		
003E	2070000000-N	815	SUBDRAIN PIPE OUTLET	2 EA		
004C	2077000000-E	815	6" OUTLET PIPE	12 LF		
0041	2253000000-E	840	PIPE COLLARS	0.5 CY		
0042	2264000000-E	840	PIPE PLUGS	0.5 CY		
0043	2275000000-E	SP	FLOWABLE FILL	1.5 CY		
0044	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	54 EA		
004E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3.5 LF		
004E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	8 EA		
0047	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	12 EA		
004E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		
005C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	11 EA		
0051	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	11 EA		
0052	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	9 EA		
0054	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	5,375 LF		
0055	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0056	2605000000-N	848	CONCRETE CURB RAMP	6 EA		
0057	2619000000-E	850	4" CONCRETE PAVED DITCH	5 SY		
0058	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,630 SY		
0059	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (IV)	275 LF		
0060	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0061	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0062	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	1 EA		
0063	3030000000-E	862	STEEL BM GUARDRAIL	1,987.5 LF		
0064	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		
0065	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (NJ-25)	1 EA		
0066	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0067	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0068	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0069	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,100 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	200 LF		
0071	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	25 EA		
0072	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	25 EA		
0073	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	385 LF		
0074	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	32 EA		
007E	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	2 EA		
007E	3572000000-E	867	CHAIN LINK FENCE RESET	275 LF		
0077	3628000000-E	876	RIP RAP, CLASS I	20 TON		
007E	3649000000-E	876	RIP RAP, CLASS B	84 TON		
007E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	3,240 SY		
008C	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	1 CY		
0081	4057000000-E	SP	OVERHEAD FOOTING	20 CY		
0082	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	724 LB		
0083	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	876 LF		
0084	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (28+00-L-)	Lump Sum	L.S.	
008E	4096000000-N	904	SIGN ERECTION, TYPE D	8 EA		
008E	4102000000-N	904	SIGN ERECTION, TYPE E	36 EA		
0087	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	2	EA	
008E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1	EA	
009C	4149000000-N	907	DISPOSAL OF SIGN SYSTEM, OVER- HEAD	1	EA	
0091	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	29	EA	
0092	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	3	EA	
009E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1	EA	
0094	4360000000-N	SP	GENERIC SIGNING ITEM DISPOSAL OF SIGN SYSTEM ON SPAN WIRE	1	EA	
009E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	780	SF	
009E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	200	SF	
0097	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	240	SF	
009E	4415000000-N	1115	FLASHING ARROW BOARD	3	EA	
009E	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2	EA	
010C	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	84	DAY	
0101	4430000000-N	1130	DRUMS	120	EA	
0102	4435000000-N	1135	CONES	20	EA	
010E	4445000000-E	1145	BARRICADES (TYPE III)	220	LF	
0104	4450000000-N	1150	FLAGGER	300	HR	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
010E	4480000000-N	1165	TMA	2 EA		
0107	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	550 LF		
010E	4507000000-E	1170	WATER FILLED BARRIER	60 LF		
010E	4510000000-N	SP	LAW ENFORCEMENT	32 HR		
011C	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	310 EA		
0111	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	7,547 LF		
0112	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,995 LF		
0113	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	350 LF		
0114	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	664 LF		
011E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,420 LF		
011E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	6 EA		
0117	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	46 EA		
011E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	5,708 LF		
011E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,745 LF		
012C	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (IV)	12 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	6	EA	
0122	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	38,040	LF	
0123	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,230	LF	
0124	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	70	LF	
0125	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,200	LF	
0126	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	600	LF	
0127	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	55	LF	
0128	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	56	EA	
0129	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	312	EA	
0130	5325600000-E	1510	6" WATER LINE	185	LF	
0131	5326200000-E	1510	12" WATER LINE	1,763	LF	
0132	5540000000-E	1515	6" VALVE	2	EA	
0133	5558000000-E	1515	12" VALVE	5	EA	
0134	5572200000-E	1515	12" TAPPING VALVE	1	EA	
0135	5648000000-N	1515	RELOCATE WATER METER	1	EA	
0136	5649000000-N	1515	RECONNECT WATER METER	3	EA	
0137	5804000000-E	1530	ABANDON 12" UTILITY PIPE	939	LF	
0138	5836000000-E	1540	24" ENCASEMENT PIPE	118	LF	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0139	6000000000-E	1605	TEMPORARY SILT FENCE	6,050 LF		
0140	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	790 TON		
0141	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	770 TON		
0142	6012000000-E	1610	SEDIMENT CONTROL STONE	1,450 TON		
0143	6015000000-E	1615	TEMPORARY MULCHING	13 ACR		
0144	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	400 LB		
0145	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0146	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,950 LF		
0147	6029000000-E	SP	SAFETY FENCE	1,200 LF		
0148	6030000000-E	1630	SILT EXCAVATION	1,750 CY		
0149	6036000000-E	1631	MATTING FOR EROSION CONTROL	17,000 SY		
0150	6037000000-E	SP	COIR FIBER MAT	200 SY		
0151	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	3,400 SY		
0152	6042000000-E	1632	1/4" HARDWARE CLOTH	2,350 LF		
0153	6070000000-N	1639	SPECIAL STILLING BASINS	24 EA		
0154	6071010000-E	SP	WATTLE	1,110 LF		
0155	6071020000-E	SP	POLYACRYLAMIDE (PAM)	300 LB		
0156	6071030000-E	1640	COIR FIBER BAFFLE	720 LF		
0157	6084000000-E	1660	SEEDING & MULCHING	8 ACR		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
015E	6087000000-E	1660	MOWING	8	ACR	
015E	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	
016C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0161	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	300	LB	
0162	6108000000-E	1665	FERTILIZER TOPDRESSING	8.5	TON	
0163	6114500000-N	1667	SPECIALIZED HAND MOWING	50	MHR	
0164	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	100	EA	
016E	7048500000-E	1705	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)	8	EA	
016E	7060000000-E	1705	SIGNAL CABLE	4,095	LF	
0167	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	18	EA	
016E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4	EA	
016E	7264000000-E	1710	MESSENGER CABLE (3/8")	628	LF	
017C	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	30	LF	
0171	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	230	LF	
0172	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	30	LF	
0173	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	4	EA	
0174	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1	EA	
017E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,365	LF	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0176	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	6,870	LF	
0177	7636000000-N	1745	SIGN FOR SIGNALS	4	EA	
017E	7642100000-N	1743	TYPE I POST WITH FOUNDATION	7	EA	
0179	7642200000-N	1743	TYPE II PEDESTAL WITH FOUNDATION	1	EA	

WALL ITEMS

018C	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS	750	SF	
0181	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 1	600	SF	
0182	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 2	1,660	SF	
0183	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 3	190	SF	
0184	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 4	180	SF	

STRUCTURE ITEMS

018E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (25 + 55.00-L-)	Lump Sum	L.S.	
018E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (52 + 15.00-L-)	Lump Sum	L.S.	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0187	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25 + 55.00-L-)	Lump Sum	L.S.	
018E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (52 + 15.00-L-)	Lump Sum	L.S.	
018S	8070000000-E	410	FOUNDATION EXCAVATION	540 CY		
019C	8108000000-E	411	***'***" DIA DRILLED PIERS (6'-6")	1,284 LF		
0191	8111000000-E	411	PERMANENT STEEL CASING FOR ***'***" DIA DRILLED PIER (6'-6")	360 LF		
0192	8112730000-N	450	PDA TESTING	4 EA		
019E	8113000000-N	411	SID INSPECTIONS	12 EA		
0194	8114000000-N	411	SPT TESTING	12 EA		
019E	8115000000-N	411	CSL TESTING	12 EA		
0196	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (25 + 55.00-L-)	Lump Sum	L.S.	
0197	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (52 + 15.00-L-)	Lump Sum	L.S.	
019E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	118,862.8 SF		
019E	8161000000-E	420	GROOVING BRIDGE FLOORS	99,276 SF		
020C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	2,174.4 CY		
0201	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25 + 55.00-L-)	Lump Sum	L.S.	
020E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (52 + 15.00-L-)	Lump Sum	L.S.	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0203	8217000000-E	425	REINFORCING STEEL (BRIDGE)	648,719 LB		
0204	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	103,034 LB		
0205	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	3,914 LF		
0206	8364000000-E	450	HP12X53 STEEL PILES	4,730 LF		
0207	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24 x 0.50)	2,700 LF		
0208	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (30 x 0.50)	1,125 LF		
0209	8386000000-E	450	PP 18 X 0.50 STEEL PILES	3,325 LF		
021C	8393000000-N	450	PILE REDRIVES	55 EA		
0211	8482000000-E	460	THREE BAR METAL RAIL	2,585.5 LF		
0212	8510000000-E	460	CONCRETE MEDIAN BARRIER	1,028 LF		
0213	8531000000-E	462	4" SLOPE PROTECTION	929 SY		
0214	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	476 TON		
021E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	529 SY		
021E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0217	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
021E	8860000000-N	SP	GENERIC STRUCTURE ITEM 12" WATER LINE	Lump Sum	L.S.	
021E	8867000000-E	SP	GENERIC STRUCTURE ITEM 74" MODIFIED PRESTR CONC GDRS	11,681 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
022C	8881000000-E	SP	GENERIC STRUCTURE ITEM EXCAVATABLE FLOWABLE FILL	40 CY		

1058/Jul11/Q1211715.95/D1033109220000/E220

Total Amount Of Bid For Entire Project :

Contract No. **C202879**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General