

County : Pasquotank

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+98.50-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	400 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	400 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	19.95 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	69 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	20 LF		
0011	0335400000-E	305	24" DRAINAGE PIPE	24 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (24")	1 EA		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	64 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	120 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	310 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	305 TON		
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35 TON		

County : Pasquotank

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	29 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE	6 LF		
0025	2264000000-E	840	PIPE PLUGS	0.232 CY		
0026	2275000000-E	SP	FLOWABLE FILL	5 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	44 LF		
0030	3030000000-E	862	STEEL BM GUARDRAIL	37.5 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	1 EA		
0033	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0035	3435000000-N	SP	GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR UNIT, TYPE 350 TL-2	1 EA		
0036	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	465 SY		

County : Pasquotank

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	374	SF	
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	151	SF	
0040	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0041	5558000000-E	1515	12" VALVE	2	EA	
0042	5589200000-E	1515	2" AIR RELEASE VALVE	1	EA	
0043	5709600000-E	1520	12" FORCE MAIN SEWER	258	LF	
0044	5804000000-E	1530	ABANDON 12" UTILITY PIPE	255	LF	
0045	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	187	LF	
0046	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	19	LF	
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,650	LF	
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250	TON	
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	45	TON	
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	100	TON	
0051	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0055	6029000000-E	SP	SAFETY FENCE	1,000	LF	
0056	6030000000-E	1630	SILT EXCAVATION	100	CY	

County : Pasquotank

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500 SY		
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	325 LF		
0059	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	75 SY		
0060	6071010000-E	SP	WATTLE	200 LF		
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0062	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0063	6087000000-E	1660	MOWING	1 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

**STRUCTURE ITEMS**

0070	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+94.50-L-)	Lump Sum	L.S.	
0071	8112730000-N	450	PDA TESTING	1 EA		
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+94.50-L-)	Lump Sum	L.S.	
0073	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	37.6 CY		

County : Pasquotank

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+94.50-L-)	Lump Sum	L.S.	
0075	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	7,030 LB		
0076	8364000000-E	450	HP12X53 STEEL PILES	1,190 LF		
0077	8393000000-N	450	PILE REDRIVES	14 EA		
0078	8475000000-E	460	TWO BAR METAL RAIL	110.5 LF		
0079	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-9 3/4")	125.5 LF		
0080	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0081	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	690.25 LF		
0082	8892000000-E	SP	GENERIC STRUCTURE ITEM STEEL SHEET PILES	2,206 SF		

1159/Aug07/Q22463.432/D355801020000/E82

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202884**

**County (ies):**    **Pasquotank**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General