

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	3 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	170 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	3,400 SY		
0009	0255000000-E	SP	GENERIC GRADING ITEM HAULING AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	50 TON		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRUCTURES	3,050 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	13,530 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	2,702 LF		
0013	0335300000-E	305	18" DRAINAGE PIPE	184 LF		
0014	0335400000-E	305	24" DRAINAGE PIPE	28 LF		
0015	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	128 LF		
0016	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,220 LF		
0017	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,264 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	412 LF		
001E	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	72 LF		
002C	0453000000-E	310	*** PIPE END SECTION (24")	1 EA		
0021	0995000000-E	340	PIPE REMOVAL	3,058 LF		
0022	1099500000-E	505	SHALLOW UNDERCUT	1,200 CY		
0023	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	2,200 TON		
0024	1110000000-E	510	STABILIZER AGGREGATE	3,500 TON		
002E	1121000000-E	520	AGGREGATE BASE COURSE	263 TON		
002E	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0027	1275000000-E	600	PRIME COAT	249 GAL		
002E	1308000000-E	607	MILLING ASPHALT PAVEMENT, *** TO ***** (0" TO 3")	1,510 SY		
002E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	14,500 TON		
003C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	13,500 TON		
0031	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	15,550 TON		
0032	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,220 TON		
0033	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	250 TON		
0034	2000000000-N	806	RIGHT OF WAY MARKERS	139 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
003E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0037	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
003E	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
003E	2077000000-E	815	6" OUTLET PIPE	6 LF		
004C	2209000000-E	838	ENDWALLS	0.326 CY		
0041	2253000000-E	840	PIPE COLLARS	3.34 CY		
0042	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	65 EA		
004E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	20.1 LF		
0044	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	11 EA		
004E	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	1 EA		
004E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	6 EA		
0047	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	12 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	14 EA		
005C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	9 EA		
0051	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	5 EA		
0053	2535000000-E	846	***X*** CONCRETE CURB (8" X 18")	340 LF		
0054	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	2,790 LF		
005E	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	200 LF		
005E	2580000000-E	846	CONCRETE VALLEY GUTTER	520 LF		
0057	2605000000-N	848	CONCRETE CURB RAMP	5 EA		
005E	2612000000-E	848	6" CONCRETE DRIVEWAY	130 SY		
005E	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (3)	1,500 LF		
006C	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (47")	1,000 LF		
0061	3628000000-E	876	RIP RAP, CLASS I	20 TON		
0062	3649000000-E	876	RIP RAP, CLASS B	60 TON		
0063	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,105 SY		
0064	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,664 LF		
006E	4102000000-N	904	SIGN ERECTION, TYPE E	72 EA		
006E	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA		
0067	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
006E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	83 EA		
006E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	528 SF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144	SF	
0071	4430000000-N	1130	DRUMS	1,142	EA	
0072	4445000000-E	1145	BARRICADES (TYPE III)	16	LF	
0073	4455000000-N	1150	FLAGGER	780	DAY	
0074	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	221	EA	
007E	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	42	LF	
007E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	406	LF	
0077	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12	EA	
007E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	110	EA	
007E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	67,686	LF	
008C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	240	LF	
0081	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	24	EA	
0082	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	79,323	LF	
0083	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	18,758	LF	
0084	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	24	EA	
008E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	457	EA	
008E	5325200000-E	1510	2" WATER LINE	582	LF	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	5325600000-E	1510	6" WATER LINE	3,057 LF		
008E	5325800000-E	1510	8" WATER LINE	620 LF		
0089	5326000000-E	1510	10" WATER LINE	160 LF		
009C	5326600000-E	1510	16" WATER LINE	16,672 LF		
0091	5536000000-E	1515	2" VALVE	6 EA		
0092	5540000000-E	1515	6" VALVE	16 EA		
0093	5546000000-E	1515	8" VALVE	1 EA		
0094	5552000000-E	1515	10" VALVE	2 EA		
009E	5558600000-E	1515	16" VALVE	15 EA		
009E	5571000000-E	1515	*** TAPPING VALVE (2")	7 EA		
0097	5571600000-E	1515	6" TAPPING VALVE	14 EA		
009E	5571800000-E	1515	8" TAPPING VALVE	1 EA		
009E	5572000000-E	1515	10" TAPPING VALVE	2 EA		
010C	5648000000-N	1515	RELOCATE WATER METER	134 EA		
0101	5666000000-E	1515	FIRE HYDRANT	15 EA		
0102	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,987 LF		
0103	5801000000-E	1530	ABANDON 8" UTILITY PIPE	9,323 LF		
0104	5802000000-E	1530	ABANDON 10" UTILITY PIPE	7,397 LF		
010E	6000000000-E	1605	TEMPORARY SILT FENCE	37,150 LF		
010E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,930 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,615 TON		
010E	6012000000-E	1610	SEDIMENT CONTROL STONE	2,045 TON		
010S	6015000000-E	1615	TEMPORARY MULCHING	51 ACR		
011C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,400 LB		
0111	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5.75 TON		
0112	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,000 LF		
0113	6030000000-E	1630	SILT EXCAVATION	4,180 CY		
0114	6036000000-E	1631	MATTING FOR EROSION CONTROL	40,000 SY		
011E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	6,700 SY		
011E	6042000000-E	1632	1/4" HARDWARE CLOTH	4,200 LF		
0117	6071010000-E	SP	WATTLE	8,600 LF		
011E	6071012000-E	SP	COIR FIBER WATTLE	300 LF		
011S	6071020000-E	SP	POLYACRYLAMIDE (PAM)	4,050 LB		
012C	6071030000-E	1640	COIR FIBER BAFFLE	900 LF		
0121	6084000000-E	1660	SEEDING & MULCHING	42 ACR		
0122	6087000000-E	1660	MOWING	20 ACR		
0123	6090000000-E	1661	SEED FOR REPAIR SEEDING	550 LB		
0124	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.5 TON		
012E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,000 LB		
012E	6108000000-E	1665	FERTILIZER TOPDRESSING	29.75 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	6114500000-N	1667	SPECIALIZED HAND MOWING	120		
				MHR		
012E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	90		
				EA		
012E	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	846		
				SF		
013C	8839000000-E	SP	GENERIC RETAINING WALL ITEM PEDESTRIAN SAFETY RAIL	235		
				LF		
0131	8847000000-E	SP	GENERIC RETAINING WALL ITEM STONE VENEERED CMU RETAINING WALL	416		
				SF		
1346/Aug10/Q427848.966/D475424686000/E131				Total Amount Of Bid For Entire Project :		

Contract No. **C203078**

County (ies): **Wilkes**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)