

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM GEOTEXTILE FOR EMBANKMENT STABILIZATION	900 SY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+77)	Lump Sum	L.S.	
000E	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	700 CY		
000E	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	1,600 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	700 SY		
001C	0255000000-E	SP	GENERIC GRADING ITEM AGGREGATE SHOULDER BORROW	1,000 TON		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	23 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	242 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	76 LF		
0014	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	64 LF		
001E	1110000000-E	510	STABILIZER AGGREGATE	400 TON		
001E	1121000000-E	520	AGGREGATE BASE COURSE	309 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1245000000-E	SP	SHOULDER RECONSTRUCTION	6		SMI
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	480		TON
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	300		TON
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,000		TON
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	336		TON
0023	2022000000-E	815	SUBDRAIN EXCAVATION	22.4		CY
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8		CY
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100		LF
002E	2070000000-N	815	SUBDRAIN PIPE OUTLET	1		EA
0027	2077000000-E	815	6" OUTLET PIPE	6		LF
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4		EA
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4		EA
003C	2556000000-E	846	SHOULDER BERM GUTTER	268		LF
0031	2830000000-N	858	ADJUSTMENT OF MANHOLES	1		EA
0032	3030000000-E	862	STEEL BM GUARDRAIL	600		LF
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4		EA
003E	3628000000-E	876	RIP RAP, CLASS I	25		TON

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3649000000-E	876	RIP RAP, CLASS B	2 TON		
003E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	500 SY		
0039	3659000000-N	SP	PERFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	359 SF		
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0043	4435000000-N	1135	CONES	70 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
004E	4455000000-N	1150	FLAGGER	30 DAY		
004E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,390 LF		
0047	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,390 LF		
004E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	520 LF		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	126,720 LF		
005C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	215 EA		
0051	5326200000-E	1510	12" WATER LINE	48 LF		
0052	5558000000-E	1515	12" VALVE	1 EA		
0053	5804000000-E	1530	ABANDON 12" UTILITY PIPE	48 LF		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	2,300 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250 TON		
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	30 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	90 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
006C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0062	6029000000-E	SP	SAFETY FENCE	1,500 LF		
006E	6030000000-E	1630	SILT EXCAVATION	100 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,510 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	350 LF		
006E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	170 SY		
0067	6071010000-E	SP	WATTLE	210 LF		
006E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
006E	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
007C	6087000000-E	1660	MOWING	1 ACR		
0071	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0072	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0074	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007E	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	
0077	6123000000-E	1670	REFORESTATION	0.1	ACR	
<b>STRUCTURE ITEMS</b>						
007E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 77.00-L-)	Lump Sum	L.S.	
007E	8112730000-N	450	PDA TESTING	1	EA	
008C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15 + 77.00-L-)	Lump Sum	L.S.	
0081	8156000000-E	SP	CONCRETE WEARING SURFACE	4,194	SF	
0082	8161000000-E	420	GROOVING BRIDGE FLOORS	5,189	SF	
0083	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	52	CY	
0084	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 77.00-L-)	Lump Sum	L.S.	
008E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,810	LB	
008E	8364000000-E	450	HP12X53 STEEL PILES	720	LF	
0087	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	980	LF	
008E	8393000000-N	450	PILE REDRIVES	14	EA	
008E	8503000000-E	460	CONCRETE BARRIER RAIL	255.5	LF	
009C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	398	TON	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	442 SY		
0092	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0093	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0094	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,530 LF		

1506/Aug27/Q173468.55/D415262320000/E94

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202658**

**County (ies):**    **Beaufort**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

**Execution of Contract and Bonds  
Approved as to Form:**

---

**Attorney General**

Signature Sheet (Bid - Acceptance by Department)