

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|---------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0192000000-N | 260 | PROOF ROLLING | 20 HR | | |
| 0004 | 1011000000-N | 500 | FINE GRADING | Lump Sum | L.S. | |
| 0005 | 1110000000-M | 510 | STABILIZER AGGREGATE | 5,000 MTN | | |
| 0006 | 2549000000-M | 846 | 750MM CONCRETE CURB & GUTTER | 310 M | | |
| 0007 | 2556000000-M | 846 | SHOULDER BERM GUTTER | 1,100 M | | |
| 0008 | 2577000000-M | 846 | CONCRETE EXPRESSWAY GUTTER | 1,380 M | | |
| 0009 | 2655000000-M | 852 | 125MM MONOLITHIC CONCRETE ISLANDS (KEYED IN) | 250 M2 | | |
| 0010 | 2724000000-M | 857 | PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED | 177 M | | |
| 0011 | 2815000000-N | 858 | ADJUSTMENT OF DROP INLETS | 20 EA | | |
| 0012 | 3030000000-M | 862 | STEEL BM GUARDRAIL | 3,840.48 M | | |
| 0013 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 10 EA | | |
| 0014 | 3210000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE CAT-1 | 16 EA | | |
| 0015 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 17 EA | | |
| 0016 | 3285000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE M-350 | 3 EA | | |
| 0017 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 16 EA | | |
| 0018 | 3360000000-M | 863 | REMOVE EXISTING GUARDRAIL | 15.24 M | | |
| 0019 | 3656000000-M | 876 | FILTER FABRIC FOR DRAINAGE | 650 M2 | | |

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0020 | 4048000000-M | 902 | REINFORCED CONCRETE SIGN FOUNDATIONS | 11 M3 | | |
| 0021 | 4057000000-M | SP | OVERHEAD FOOTING | 138 M3 | | |
| 0022 | 4060000000-M | 903 | SUPPORTS, BREAKAWAY STEEL BEAM | 2,208 KG | | |
| 0023 | 4066000000-M | 903 | SUPPORTS, SIMPLE STEEL BEAM | 1,025 KG | | |
| 0024 | 4072000000-M | 903 | SUPPORTS, 4.5-KG STEEL U-CHANNEL | 377 M | | |
| 0025 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (12+50 -LP2B-) | Lump Sum | L.S. | |
| 0026 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (15+90 -Y2-) | Lump Sum | L.S. | |
| 0027 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (18+00 -Y2-) | Lump Sum | L.S. | |
| 0028 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (19+00 -FLYOVER-) | Lump Sum | L.S. | |
| 0029 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (19+70 -Y2-) | Lump Sum | L.S. | |
| 0030 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (23+50 -Y1-) | Lump Sum | L.S. | |
| 0031 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (28+60 -Y1-) | Lump Sum | L.S. | |
| 0032 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (32+00 -Y1-) | Lump Sum | L.S. | |
| 0033 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (41+02 -COL2-) | Lump Sum | L.S. | |
| 0034 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (51+53 -L-) | Lump Sum | L.S. | |

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|------------|-----------|--------|
| 0035 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (51+70 -CDR-) | Lump Sum | L.S. | |
| 0036 | 4082100000-N | SP | SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (55+48 -L-) | Lump Sum | L.S. | |
| 0037 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 1 EA | | |
| 0038 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 41 EA | | |
| 0039 | 4108000000-N | 904 | SIGN ERECTION, TYPE F | 5 EA | | |
| 0040 | 4109000000-N | 904 | SIGN ERECTION, TYPE *** (OVERHEAD) (A) | 1 EA | | |
| 0041 | 4110000000-N | 904 | SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A) | 11 EA | | |
| 0042 | 4400000000-M | 1110 | WORK ZONE SIGNS (STATIONARY) | 30 M2 | | |
| 0043 | 4405000000-M | 1110 | WORK ZONE SIGNS (PORTABLE) | 27 M2 | | |
| 0044 | 4410000000-M | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 9 M2 | | |
| 0045 | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 1 EA | | |
| 0046 | 4422000000-N | 1120 | CHANGEABLE MESSAGE SIGN (SHORT TERM) | 30 DAY | | |
| 0047 | 4430000000-N | 1130 | DRUMS | 128 EA | | |
| 0048 | 4435000000-N | 1135 | CONES | 75 EA | | |
| 0049 | 4445000000-M | 1145 | BARRICADES (TYPE III) | 110 M | | |
| 0050 | 4520000000-N | 1266 | TUBULAR MARKERS (FIXED) | 128 EA | | |
| 0051 | 4695000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM) | 1,101 M | | |
| 0052 | 4710000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM) | 146 M | | |

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 0053 | 4725000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM) | 45 | EA | |
| 0054 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 609 | EA | |
| 0055 | 5255000000-N | 1413 | PORTABLE LIGHTING | Lump Sum | L.S. | |
| 0056 | 6000000000-M | 1605 | TEMPORARY SILT FENCE | 1,150 | M | |
| 0057 | 6006000000-M | 1610 | STONE FOR EROSION CONTROL, CLASS A | 475 | MTN | |
| 0058 | 6009000000-M | 1610 | STONE FOR EROSION CONTROL, CLASS B | 465 | MTN | |
| 0059 | 6012000000-M | 1610 | SEDIMENT CONTROL STONE | 765 | MTN | |
| 0060 | 6024000000-M | 1622 | TEMPORARY SLOPE DRAINS | 300 | M | |
| 0061 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 12 | EA | |
| 0062 | 6030000000-M | 1630 | SILT EXCAVATION | 1,000 | M3 | |
| 0063 | 6036000000-M | 1631 | MATTING FOR EROSION CONTROL | 5,000 | M2 | |
| 0064 | 6038000000-M | SP | PERMANENT SOIL REINFORCEMENT MAT | 50 | M2 | |
| 0065 | 6042000000-M | 1632 | 6.4MM HARDWARE CLOTH | 925 | M | |
| 0066 | 6071010000-M | SP | WATTLE | 500 | M | |
| 0067 | 6071020000-M | SP | POLYACRYLAMIDE (PAM) | 100 | KG | |
| 0068 | 6071030000-M | SP | COIR FIBER BAFFLE | 200 | M | |
| 0069 | 6084000000-M | 1660 | SEEDING & MULCHING | 10 | HA | |
| 0070 | 6087000000-M | 1660 | MOWING | 2 | HA | |
| 0071 | 6090000000-M | 1661 | SEED FOR REPAIR SEEDING | 275 | KG | |

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0072 | 6093000000-M | 1661 | FERTILIZER FOR REPAIR SEEDING | 1 MTN | | |
| 0073 | 6096000000-M | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 450 KG | | |
| 0074 | 6108000000-M | 1665 | FERTILIZER TOPDRESSING | 25.75 MTN | | |
| 0075 | 6114500000-N | SP | SPECIALIZED HAND MOWING | 20 MHR | | |
| 0076 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 30 EA | | |
| 0077 | 6133000000-N | SP | GENERIC EROSION CONTROL ITEM REMOVAL OF EROSION CONTROL DEVICES | Lump Sum | L.S. | |
| 0078 | 7060000000-M | 1705 | SIGNAL CABLE | 1,087 M | | |
| 0079 | 7120000000-M | 1705 | VEHICLE SIGNAL HEAD (300MM, 3 SECTION) | 30 EA | | |
| 0080 | 7264000000-M | 1710 | MESSENGER CABLE (9.52MM) | 735 M | | |
| 0081 | 7288000000-M | 1715 | PAVED TRENCHING (***** (1,50MM) | 5 M | | |
| 0082 | 7300000000-M | 1715 | UNPAVED TRENCHING (***** (1,50MM) | 650 M | | |
| 0083 | 7301000000-M | 1715 | DIRECTIONAL DRILL (***** (1,50MM) | 50 M | | |
| 0084 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 28 EA | | |
| 0085 | 7420000000-M | 1722 | 50MM RISER WITH WEATHERHEAD | 6 EA | | |
| 0086 | 7444000000-M | 1725 | INDUCTIVE LOOP SAWCUT | 735 M | | |
| 0087 | 7456000000-M | 1726 | LEAD-IN CABLE (***** (14-2) | 3,730 M | | |
| 0088 | 7575142000-N | SP | 900MHZ WIRELESS RADIO SYSTEM | 6 EA | | |
| 0089 | 7576000000-N | SP | METAL STRAIN SIGNAL POLE | 15 EA | | |
| 0090 | 7613000000-N | SP | SOIL TEST | 15 EA | | |

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0091 | 7614100000-M | SP | DRILLED PIER FOUNDATION | 75 | | M3 |
| 0092 | 7636000000-N | 1745 | SIGN FOR SIGNALS | 7 | | EA |
| 0093 | 7684000000-N | 1750 | SIGNAL CABINET FOUNDATION | 4 | | EA |
| 0094 | 7756000000-N | 1751 | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) | 4 | | EA |
| 0095 | 7780000000-N | 1751 | DETECTOR CARD (TYPE 2070L) | 16 | | EA |
| 0096 | 7901000000-N | 1753 | CABINET BASE EXTENDER | 4 | | EA |

***** BEGIN SCHEDULE AA *****
 ***** (2 ALTERNATES) *****

| | | | | | | |
|------------|--------------|------|---|--------|--|-----|
| 0097 | 1121000000-M | 520 | AGGREGATE BASE COURSE | 44,600 | | MTN |
| AA1 | | | | | | |
| 0098 | 1231000000-M | 560 | SHOULDER BORROW | 13,900 | | M3 |
| AA1 | | | | | | |
| 0099 | 1491000000-M | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0C | 5,500 | | MTN |
| AA1 | | | | | | |
| 0100 | 1503000000-M | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C | 21,800 | | MTN |
| AA1 | | | | | | |
| 0101 | 1523000000-M | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5C | 17,100 | | MTN |
| AA1 | | | | | | |
| 0102 | 1575000000-M | SP | ASPHALT BINDER FOR PLANT MIX | 2,300 | | MTN |
| AA1 | | | | | | |
| 0103 | 1840000000-M | 665 | MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) | 13,410 | | M |
| AA1 | | | | | | |
| 0104 | 4685000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM) | 13,194 | | M |
| AA1 | | | | | | |
| 0105 | 4686000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM) | 2,419 | | M |
| AA1 | | | | | | |

*** OR ***

| | | | | | | |
|------------|--------------|-----|-----------------------|--------|--|-----|
| 0106 | 1121000000-M | 520 | AGGREGATE BASE COURSE | 16,100 | | MTN |
| AA2 | | | | | | |
| 0107 | 1231000000-M | 560 | SHOULDER BORROW | 12,100 | | M3 |
| AA2 | | | | | | |

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|-------------|--------------|-------|---|---------------|-----------|--------|
| 0108 AA2 | 1489000000-M | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 10,900 MTN | | |
| 0109 AA2 | 1503000000-M | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C | 7,400 MTN | | |
| 0110 AA2 | 1523000000-M | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5C | 5,800 MTN | | |
| 0111 AA2 | 1525000000-M | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 4,200 MTN | | |
| 0112 AA2 | 1575000000-M | SP | ASPHALT BINDER FOR PLANT MIX | 1,460 MTN | | |
| 0113 AA2 | 1847000000-M | 710 | ****MM PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (240MM) | 20,400 M2 | | |
| 0114 AA2 | 1847000000-M | 710 | ****MM PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (280MM) | 23,600 M2 | | |
| 0115 AA2 | 1869000000-M | 710 | ****MM PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (240MM) | 10,000 M2 | | |
| 0116 AA2 | 1869000000-M | 710 | ****MM PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (280MM) | 9,900 M2 | | |
| 0117 AA2 | 1881000000-M | SP | GENERIC PAVING ITEM MILLED RUMBLE STRIPS (CONC SHOULDER) | 13,410 M | | |
| 0118 AA2 | 1902000000-N | 710 | SURFACE TESTING CONCRETE PAVEMENT | Lump Sum | L.S. | |
| 0119 AA2 | 1913000000-M | 720 | CONCRETE SHOULDERS ADJACENT TO *****MM PAVEMENT (240MM) | 5,600 M2 | | |
| 0120 AA2 | 1913000000-M | 720 | CONCRETE SHOULDERS ADJACENT TO *****MM PAVEMENT (280MM) | 8,700 M2 | | |
| 0121 AA2 | 1924000000-N | 725 | FIELD LABORATORY RENTAL, PORT CEM CONC PAVEMENT | Lump Sum | L.S. | |
| 0122 AA2 | 4685000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM) | 3,550 M | | |

County : Cumberland

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|-------------|--------------|-------|---|-------------|-----------|--------|
| 0123 AA2 | 4686000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM) | 1,002 M | | |
| 0124 AA2 | 4847000000-M | 1205 | POLYUREA PAVEMENT MARKING LINES (100MM, *****) (HIGHLY REFLECTIVE ELEMENTS) | 11,011 M | | |

***** END SCHEDULE AA *****

1419/Sep04/Q337414.47/D534724502000/E124

Total Amount Of Bid For Entire Project :

Contract No **C202948**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General