

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (30 + 66.99)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	150 CY		
000E	0134000000-E	240	DRAINAGE DITCH EXCAVATION	42 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	200 SY		
000E	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	40 TON		
001C	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	120 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	104 LF		
0012	0335300000-E	305	18" DRAINAGE PIPE	96 LF		
0013	0335500000-E	305	30" DRAINAGE PIPE	88 LF		
0014	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	6 EA		
001E	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF		
001E	0995000000-E	340	PIPE REMOVAL	100 LF		
0017	1099500000-E	505	SHALLOW UNDERCUT	70 CY		
001E	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	125 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	1,446 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0021	1275000000-E	600	PRIME COAT	40.25 GAL		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	45 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	560 TON		
0024	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	440 TON		
0025	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	60 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	27 EA		
0028	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0029	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0031	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE	6 LF		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0034	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0035	2556000000-E	846	SHOULDER BERM GUTTER	480 LF		
0036	3030000000-E	862	STEEL BM GUARDRAIL	987.5 LF		
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
003E	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	1 EA		
004C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0041	3360000000-E	863	REMOVE EXISTING GUARDRAIL	114 LF		
0042	3628000000-E	876	RIP RAP, CLASS I	7 TON		
0043	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0044	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	875 SY		
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	14 LF		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0047	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	10 EA		
004E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
005C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	642 SF		
0051	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104 SF		
0052	4430000000-N	1130	DRUMS	38 EA		
0053	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,240 LF		
005E	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	88 LF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	44	LF	
0057	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	4	EA	
005E	6000000000-E	1605	TEMPORARY SILT FENCE	1,950	LF	
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	300	TON	
006C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	225	TON	
0061	6012000000-E	1610	SEDIMENT CONTROL STONE	160	TON	
0062	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0064	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	260	LF	
006E	6030000000-E	1630	SILT EXCAVATION	500	CY	
0067	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,000	SY	
006E	6037000000-E	SP	COIR FIBER MAT	10	SY	
006E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	305	SY	
007C	6042000000-E	1632	1/4" HARDWARE CLOTH	280	LF	
0071	6071010000-E	SP	WATTLE	230	LF	
0072	6071020000-E	SP	POLYACRYLAMIDE (PAM)	60	LB	
007E	6071030000-E	1640	COIR FIBER BAFFLE	350	LF	

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
007E	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
007E	6087000000-E	1660	MOWING	0.6 ACR		
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
008C	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0081	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

**STRUCTURE ITEMS**

008E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (30 + 66.99-L-)	Lump Sum	L.S.	
0084	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (30 + 66.99-L-)	Lump Sum	L.S.	
008E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,186 SF		
008E	8161000000-E	420	GROOVING BRIDGE FLOORS	5,520 SF		
0087	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	100.4 CY		
008E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (30 + 66.99-L-)	Lump Sum	L.S.	
008E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,119 LB		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	621.33	LF	
0091	8364000000-E	450	HP12X53 STEEL PILES	505	LF	
0092	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (30 x 0.50)	575	LF	
0093	8475000000-E	460	TWO BAR METAL RAIL	303.09	LF	
0094	8517000000-E	460	1'-**"X ***** CONCRETE PARAPET (1'-2" x 2'-6")	318.33	LF	
009E	8524000000-E	SP	**" CHAIN LINK FENCE (72")	314.33	LF	
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

0928/Aug24/Q49279.28/D392672060000/E96

Total Amount Of Bid For Entire Project :

**Contract No.**     **C203004**

**County (ies):**    **Rutherford**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General