

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (14 + 43.50-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	450 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	85 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	500 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	20 SY		
0012	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (15", V)	28 LF		
0013	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	28 LF		
0014	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
001E	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
001E	1330000000-E	607	INCIDENTAL MILLING	120 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	300 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	115 TON		
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	190 TON		
002C	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	32 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	4 EA		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	87.5 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3628000000-E	876	RIP RAP, CLASS I	55 TON		
003C	3635000000-E	876	RIP RAP, CLASS II	25 TON		
0031	3649000000-E	876	RIP RAP, CLASS B	1 TON		
003E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	865 SY		
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	71 LF		
0034	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
003E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	311 SF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,384 LF		
004C	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	130 TON		
0044	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
004E	6029000000-E	SP	SAFETY FENCE	800 LF		
004E	6030000000-E	1630	SILT EXCAVATION	100 CY		
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,000 SY		
0051	6037000000-E	SP	COIR FIBER MAT	200 SY		
0052	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	600 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0054	6070000000-N	1639	SPECIAL STILLING BASINS	6 EA		
005E	6071012000-E	SP	COIR FIBER WATTLE	25 LF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6071030000-E	1640	COIR FIBER BAFFLE	40 LF		
0057	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
005E	6087000000-E	1660	MOWING	1 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0064	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0067	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14 + 43.50-L-)	Lump Sum	L.S.	
006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 43.50-L-)	Lump Sum	L.S.	
006E	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	46.5 LF		
007C	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	18 LF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	36.9 LF		
0072	8115000000-N	411	CSL TESTING	1 EA		
0073	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14 + 43.50-L-)	Lump Sum	L.S.	
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	45.6 CY		
007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 43.50-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,697 LB		
0077	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,311 LB		
007E	8364000000-E	450	HP12X53 STEEL PILES	245 LF		
007E	8475000000-E	460	TWO BAR METAL RAIL	224.64 LF		
008C	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-10")	240.26 LF		
0081	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	380 TON		
0082	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	420 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	550 LF		
008E	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		

Contract No. **C202958**

County (ies): **Alamance**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)