

PROJECT NO.	SHEET NO.	TOTAL NO.
7CR.10011.36, 7CR.10681.36	3	3

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	FINAL SURFACE TESTING REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	INCIDENTAL MILLING SY	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A TONS	ASPHALT BINDER FOR PLANT MIX TONS	GENERIC PAVING ITEM - [ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE] SY	ADI. OF MANHOLES EA
7CR.10011.36	Alamance	1	NC 54	FROM JOINT 400' EAST OF SR 2142 (MOUNT WILLEN ROAD/SALEM CHURCH ROAD) - MP 12.32 TO ORANGE COUNTY LINE - MP 14.98	1	NO	0.691	32	231	267	1,094	73	12,972	
					1	NO	0.104	32-44			192	13	2,319	
					1	NO	0.038	44			101	7	981	
					1	NO	0.083	32-44			153	10	1,850	
					1	NO	1.74	32			2,825	189	32,666	
TOTAL FOR PROJ NO. 7CR.10011.36							2.656		231	267	4,365	292	50,788	
7CR.10681.36	Orange	2	NC 54	FROM SR 1207 (GREENFIELD ROAD) -MP 6.90 TO ALAMANCE COUNTY LINE -MP 0.00	1	NO	0.989	32	604		1,538	103	18,567	
					1	NO	0.019	56			72	5	624	1
					1	NO	0.063	56-68			189	13	2,292	
					1	NO	0.021	68			189	13	838	
					1	NO	0.032	56			87	6	1,051	
					1	NO	0.092	32-56			196	13	2,375	
					1	NO	0.342	32			532	36	6,421	
					1	NO	0.043	32-52			88	6	1,060	
					1	NO	0.027	52			88	6	824	1
					1	NO	0.05	45			109	7	1,320	
					1	NO	0.027	59			88	6	824	
					1	NO	0.07	32-59			156	10	1,889	
					1	NO	0.862	32			1,340	90	16,183	
					1	NO	0.063	32-44			116	8	1,405	
					1	NO	0.024	44			71	5	620	
					1	NO	0.774	32			1,203	81	14,531	
					1	NO	0.037	44			99	7	955	
					1	NO	0.034	32-44			63	4	758	
					1	NO	1.067	32			1,659	111	20,031	
					1	NO	0.035	44			95	6	904	
					1	NO	0.045	32-44			83	6	1,003	
					1	NO	0.089	32			138	9	1,671	
					1	NO	0.045	32-44			83	6	1,003	
					1	NO	0.033	44			90	6	852	
					1	NO	0.416	32			647	43	7,810	
					1	NO	0.029	44			62	4	749	
					1	NO	0.903	32			1,404	94	16,952	
1	NO	0.044	32-44			81	5	981						
1	NO	0.009	44			19	1	232						
1	NO	0.02	56			94	6	657						
1	NO	0.012	44			26	2	310						
1	NO	0.041	32-44			76	5	914						
1	NO	0.545	32			847	57	10,232						
TOTAL FOR PROJ NO. 7CR.10681.36							6.902		604	267	11,628	780	136,838	2
GRAND TOTAL							9.558		835	534	15,993	1,072	187,626	2

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	LENGTH	WIDTH	4685000000-E	4686000000-E			4690000000-E	4695000000-E			4710000000-E	4725000000-E			4905000000-N
							4" X 90 M WHITE THERMO	4" X 120 M WHITE THERMO	4" X 120 M YELLOW THERMO	6" X 120 M WHITE THERMO	8" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	24" X 120 M WHITE THERMO	THERMO LT ARROW 90 M	THERMO STR ARROW 90 M	THERMO RT ARROW 90 M	SNOWPLOWABLE PAVEMENT MARKERS		
NO		NO					LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA		
7CR.10011.36	Alamance	1	NC 54	FROM JOINT 400' EAST OF SR 2142 (MOUNT WILLEN ROAD/SALEM CHURCH ROAD) - MP 12.32 TO ORANGE COUNTY LINE - MP 14.98	0.691	32	28,050	100	20,951	76	130	50	2				250		
					0.691		28,050	100	20,951	76	130	50	2		250				
TOTAL FOR PROJ NO. 7CR.10011.36								21,051		130		2		2					
7CR.10681.36	Orange	2	NC 54	FROM SR 1207 (GREENFIELD ROAD) - MP 6.90 TO ALAMANCE COUNTY LINE -MP 0.00	0.989	32	72,872	1,734	54,491	206	178	515	4	4	6	550			
					0.989		72,872	1,734	54,491	206	178	515	4	4	6	550			
TOTAL FOR PROJ NO. 7CR.10681.36								56,225		693		14							
GRAND TOTAL					1.68		100,922	1,834	75,442	282	308	515	6	4	6	800			
								77,276		823		16							