

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 72.00-L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	1,050 CY		
0008	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	700 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	700 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	20 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	36 LF		
0013	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0014	1220000000-E	545	INCIDENTAL STONE BASE	43 TON		
0015	1245000000-E	SP	SHOULDER RECONSTRUCTION	1.92 SMI		
0016	1330000000-E	607	INCIDENTAL MILLING	120 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	920 TON		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	220 TON		
001S	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	500 TON		
002C	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	1,140 TON		
0021	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	160 TON		
0022	1704000000-E	SP	PATCHING EXISTING PAVEMENT	29 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002E	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002S	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
003C	2556000000-E	846	SHOULDER BERM GUTTER	220 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	725 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	2 TON		
003E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	460 SY		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400	SF	
003E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144	SF	
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	140	SF	
004C	4435000000-N	1135	CONES	50	EA	
0041	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
0042	4455000000-N	1150	FLAGGER	20	DAY	
0043	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	11,638	LF	
0044	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	11,638	LF	
004E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	72	EA	
004E	6000000000-E	1605	TEMPORARY SILT FENCE	3,200	LF	
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	190	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	140	TON	
005C	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200	LB	
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75	TON	
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0054	6029000000-E	SP	SAFETY FENCE	700	LF	

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6030000000-E	1630	SILT EXCAVATION	250 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,500 SY		
0057	6037000000-E	SP	COIR FIBER MAT	450 SY		
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	600 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	440 LF		
006C	6071010000-E	SP	WATTLE	60 LF		
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
006Z	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
006E	6087000000-E	1660	MOWING	3 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	3.25 TON		
006E	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

STRUCTURE ITEMS

007C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+72.00-L-)	Lump Sum	L.S.	
0071	8112730000-N	450	PDA TESTING	1 EA		

County : Bladen

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16 + 72.00-L-)	Lump Sum	L.S.	
0073	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	42.1 CY		
0074	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 72.00-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,883 LB		
007E	8364000000-E	450	HP12X53 STEEL PILES	700 LF		
0077	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	560 LF		
007E	8393000000-N	450	PILE REDRIVES	22 EA		
007E	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	240.5 LF		
008C	8594000000-E	876	RIP RAP, CLASS B	78 TON		
0081	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	298 TON		
0082	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	332 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,440 LF		

1615/Oct02/Q53944.17/D364372010000/E84

Total Amount Of Bid For Entire Project :

Contract No. **C202955**

County (ies): **Bladen**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General