

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1330000000-E	607	INCIDENTAL MILLING	436 SY		
0003	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	30 TON		
0004	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2 TON		
000E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
000E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	116 SF		
0007	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
000E	4435000000-N	1135	CONES	60 EA		
000E	4450000000-N	1150	FLAGGER	640 HR		
001C	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	2,925 LF		
0011	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	16 EA		
0012	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	1,117 SF		
0013	8161000000-E	420	GROOVING BRIDGE FLOORS	32,191 SF		
0014	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	4,491 LB		
001E	8296000000-N	442	POLLUTION CONTROL	Lump Sum	L.S.	
001E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0017	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
001E	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING AT BENT 1, 2 AND 7	Lump Sum	L.S.	

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	8860000000-N	SP	GENERIC STRUCTURE ITEM CLEANING & PAINTING STRUCTURAL STEEL	Lump Sum	L.S.	
002C	8860000000-N	SP	GENERIC STRUCTURE ITEM CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS	Lump Sum	L.S.	
0021	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE	Lump Sum	L.S.	
0022	8860000000-N	SP	GENERIC STRUCTURE ITEM SYNTHETIC RUBBER EXPANSION JOINT SEAL	Lump Sum	L.S.	
0023	8860000000-N	SP	GENERIC STRUCTURE ITEM TEMP STEEL COVER FOR EXP JOINT SEAL REPAIR	Lump Sum	L.S.	
0024	8881000000-E	SP	GENERIC STRUCTURE ITEM LATEX MOD CONCRETE OVERLAY - VERY EARLY STRENGTH	221.1 CY		
002E	8889000000-E	SP	GENERIC STRUCTURE ITEM DIAPHRAGM MODIFICATION SPANS A, B AND H	8,582 LB		
002E	8889000000-E	SP	GENERIC STRUCTURE ITEM DIAPHRAGM MODIFICATION SPANS C AND G	3,310 LB		
0027	8889000000-E	SP	GENERIC STRUCTURE ITEM PLATE GIRDER REPAIR	1,230 LB		
002E	8889000000-E	SP	GENERIC STRUCTURE ITEM REPLACE STEEL DIAPHRAGM	1,085 LB		
0029	8889000000-E	SP	GENERIC STRUCTURE ITEM REPLACE STEEL STIFFENER PLATES	232 LB		
003C	8889000000-E	SP	GENERIC STRUCTURE ITEM ROLLED BEAM REPAIR	4,300 LB		
0031	8893000000-E	SP	GENERIC STRUCTURE ITEM HYDRO-DEMOLITION OF BRIDGE DECK	3,505.8 SY		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0032	8893000000-E	SP	GENERIC STRUCTURE ITEM PLACING & FINISHING LATEX MOD CONC OVERLAY - VERY EARLY STRENGTH	3,614.3	SY	
0033	8893000000-E	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	3,614.3	SY	
0034	8897000000-N	SP	GENERIC STRUCTURE ITEM BOLT REMOVAL AND REPLACEMENT	100	EA	

0906/Oct10/Q71878.5/D237418100000/E34

Total Amount Of Bid For Entire Project :

Contract No. **C203075**

County (ies): **Catawba**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General