

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
000E	0063000000-N	SP	GRADING	Lump Sum	L.S.	
000E	0106000000-E	230	BORROW EXCAVATION	40,000 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	580 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	200 SY		
000E	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRUCTURES	135 TON		
001C	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	380 SY		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	92 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0013	0345000000-E	310	24" SIDE DRAIN PIPE	92 LF		
0014	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	2 EA		
001E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	52 LF		
001E	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	232 LF		
0017	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	500 LF		
001E	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	96 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	40 LF		
002C	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0021	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (84", 1")	320 LF		
0022	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (84", 1")	160 LF		
0023	0986000000-E	SP	GENERIC PIPE ITEM 84" STEEL PIPE (OPEN TRENCH)	100 LF		
0024	0995000000-E	340	PIPE REMOVAL	395 LF		
002E	1077000000-E	SP	#57 STONE	5 TON		
0026	1099500000-E	505	SHALLOW UNDERCUT	300 CY		
0027	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	570 TON		
002E	1121000000-E	520	AGGREGATE BASE COURSE	55 TON		
0029	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
003C	1275000000-E	600	PRIME COAT	48 GAL		
0031	1330000000-E	607	INCIDENTAL MILLING	2,620 SY		
0032	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	120 TON		
0033	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,650 TON		
0034	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	100 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	3,510 TON		
003E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	3,660 TON		
0037	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	10 TON		
003E	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	645 TON		
003E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	26 TON		
004C	2220000000-E	838	REINFORCED ENDWALLS	16 CY		
0041	2275000000-E	SP	FLOWABLE FILL	426 CY		
0042	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	21 EA		
004E	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	9.5 CY		
0044	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	21 LF		
004E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
004E	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	5 EA		
0047	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	4 EA		
004E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
004E	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
005C	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	1 EA		
0051	2556000000-E	846	SHOULDER BERM GUTTER	1,210 LF		
0052	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	90 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	160 SY		
0054	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (T1)	770 LF		
005E	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	2 EA		
005E	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	506 LF		
0057	2759000000-N	SP	GENERIC PAVING ITEM MEDIAN HAZARD PROTECTION	1 EA		
005E	3030000000-E	862	STEEL BM GUARDRAIL	2,500 LF		
005E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
006C	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (NJ-25)	1 EA		
0061	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0062	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0063	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	6 EA		
0064	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,725 LF		
006E	3628000000-E	876	RIP RAP, CLASS I	245 TON		
006E	3642000000-E	876	RIP RAP, CLASS A	5 TON		
0067	3649000000-E	876	RIP RAP, CLASS B	65 TON		
006E	3651000000-E	SP	BOULDERS	15 TON		
006E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,515 SY		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	4 CY		
0071	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 CY		
0072	4057000000-E	SP	OVERHEAD FOOTING	6 CY		
0073	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,268 LB		
0074	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	2,020 LB		
007E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,030 LF		
007E	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (10 + 50 -L-)	Lump Sum	L.S.	
0077	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
007E	4102000000-N	904	SIGN ERECTION, TYPE E	48 EA		
007E	4108000000-N	904	SIGN ERECTION, TYPE F	6 EA		
008C	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	2 EA		
0081	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	6 EA		
0082	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	4 EA		
0083	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	52 EA		
0084	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,673 SF		
008E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	630 SF		
008E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	185 SF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	4415000000-N	1115	FLASHING ARROW BOARD	3 EA		
008E	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	3 EA		
008E	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	5 DAY		
009C	4430000000-N	1130	DRUMS	532 EA		
0091	4445000000-E	1145	BARRICADES (TYPE III)	180 LF		
0092	4455000000-N	1150	FLAGGER	120 DAY		
009E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	5 EA		
0094	4480000000-N	1165	TMA	6 EA		
009E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	2,890 LF		
009E	4510000000-N	SP	LAW ENFORCEMENT	320 HR		
0097	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	35 EA		
009E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	205 LF		
009E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
010C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	29 EA		
0101	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,279 LF		
0102	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	50,865 LF		
010E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	3,609 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	31,800	LF	
010E	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	2,700	LF	
010E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	13,200	LF	
0107	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	2,460	LF	
010E	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	340	LF	
010E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	26	EA	
011C	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	150	EA	
0111	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	36	EA	
0112	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	16	EA	
011E	5691500000-E	1520	12" SANITARY GRAVITY SEWER	300	LF	
0114	5775000000-E	1525	4' DIA UTILITY MANHOLE	3	EA	
011E	5798000000-E	1530	ABANDON *** UTILITY PIPE (42")	184	LF	
011E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	24	LF	
0117	5816000000-N	1530	ABANDON UTILITY MANHOLE	1	EA	
011E	5836000000-E	1540	24" ENCASEMENT PIPE	190	LF	
011E	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	90	LF	
012C	5872210000-E	1550	TRENCHLESS INSTALLATION OF 24" NOT IN SOIL	90	LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	6000000000-E	1605	TEMPORARY SILT FENCE	3,525 LF		
0122	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,060 TON		
0123	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,000 TON		
0124	6012000000-E	1610	SEDIMENT CONTROL STONE	860 TON		
012E	6015000000-E	1615	TEMPORARY MULCHING	15.5 ACR		
0126	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500 LB		
0127	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
012E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	800 LF		
012E	6029000000-E	SP	SAFETY FENCE	100 LF		
013C	6030000000-E	1630	SILT EXCAVATION	1,640 CY		
0131	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,400 SY		
0132	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,350 SY		
0133	6042000000-E	1632	1/4" HARDWARE CLOTH	1,250 LF		
0134	6045000000-E	SP	*** TEMPORARY PIPE (15")	60 LF		
013E	6070000000-N	1639	SPECIAL STILLING BASINS	5 EA		
013E	6071010000-E	SP	WATTLE	650 LF		
0137	6071020000-E	SP	POLYACRYLAMIDE (PAM)	350 LB		
013E	6071030000-E	1640	COIR FIBER BAFFLE	655 LF		
013E	6084000000-E	1660	SEEDING & MULCHING	12 ACR		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014C	6087000000-E	1660	MOWING	9	ACR	
0141	6090000000-E	1661	SEED FOR REPAIR SEEDING	200	LB	
0142	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0143	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	400	LB	
0144	6108000000-E	1665	FERTILIZER TOPDRESSING	12	TON	
014E	6111000000-E	SP	IMPERVIOUS DIKE	90	LF	
0146	6114500000-N	1667	SPECIALIZED HAND MOWING	20	MHR	
0147	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	
014E	6123000000-E	1670	REFORESTATION	0.25	ACR	
014E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	300	LF	
015C	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2	EA	
0151	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	225	LF	
0152	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	1,150	LF	

WALL ITEMS

0153	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL @ EB1	2,353	SF	
0154	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL @ EB2	2,408	SF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
015E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+90.11-L-)	Lump Sum	L.S.	
015E	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 20+90.11-L-)	Lump Sum	L.S.	
0157	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,873 SF		
015E	8161000000-E	420	GROOVING BRIDGE FLOORS	9,550 SF		
015E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	213.4 CY		
016C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+90.11-L-)	Lump Sum	L.S.	
0161	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,217 LB		
0162	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,821 LB		
016E	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	1,102.02 LF		
0164	8364000000-E	450	HP12X53 STEEL PILES	440 LF		
016E	8384000000-E	450	HP14X73 STEEL PILES	1,555 LF		
016E	8503000000-E	460	CONCRETE BARRIER RAIL	418.75 LF		
0167	8531000000-E	462	4" SLOPE PROTECTION	44 SY		
016E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
016E	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	

Contract No. **C202951**

County (ies): **Davidson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General