

8/17/99

REVISIONS

CROSS SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATION L	UNCL. EXC. (CU. YD.)	EMBT. (CU. YD.)
13+70.00	-	-
14+20.00	4	14
14+50.00	3	19
15+00.00	11	48
15+50.00	13	107
16+00.00	8	175
16+50.00	5	220
16+80.00	0	154
17+23.75	0	220
18+66.25	-	-
19+00.00	18	62
19+50.00	4	86
20+00.00	6	53
20+20.00	1	14
20+70.00	1	16

CROSS SECTION INDEX

SHEET	BEGIN STATION	END STATION
X-2	13+70.00	17+23.75
X-3	17+50.00	20+70.00

Note:
 Approximate quantities only. Unclassified Excavation, Fine Grading, Clearing and Grubbing, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."
 Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.



