

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	180 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	20 CY		
0007	0106000000-E	230	BORROW EXCAVATION	90 CY		
0008	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	550 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	95 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	300 SY		
0011	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	604 LF		
0012	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (48", 0.109")	188 LF		
0013	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	80 LF		
0014	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0015	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (48", 0.064")	2 EA		
0016	0995000000-E	340	PIPE REMOVAL	50 LF		
0017	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0018	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	230 TON		
0020	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	62 TON		
0021	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	26 TON		
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	15 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	12 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	5 EA		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0028	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE	6 LF		
0030	2264000000-E	840	PIPE PLUGS	1 CY		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0032	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5.12 LF		
0033	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	5 EA		
0034	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	2 EA		
0035	2556000000-E	846	SHOULDER BERM GUTTER	985 LF		
0036	3345000000-E	864	REMOVE & RESET EXISTING GUARD-RAIL	1,000 LF		
0037	3500000000-E	866	WOVEN WIRE FENCE, *** FABRIC (48")	160 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	10 EA		
0039	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	5 EA		
0040	3557000000-E	866	ADDITIONAL BARBED WIRE	20 LF		
0041	3566000000-E	867	WOVEN WIRE FENCE RESET	155 LF		
0042	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	225 SY		
0043	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	93 SF		
0045	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	385 SF		
0046	4415000000-N	1115	FLASHING ARROW BOARD	3 EA		
0047	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0048	4430000000-N	1130	DRUMS	86 EA		
0049	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0050	4480000000-N	1165	TMA	2 EA		
0051	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,500 LF		
0052	4510000000-N	SP	LAW ENFORCEMENT	200 HR		
0053	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM REMOVE AND REPLACE SNOWPLOW-ABLE PAVEMENT MARKER REFLECTOR	32 EA		
0054	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	220 EA		
0055	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	5,000 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	625 LF		
0057	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0058	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	11,250 LF		
0059	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	8,750 LF		
0060	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2 EA		
0061	6000000000-E	1605	TEMPORARY SILT FENCE	1,600 LF		
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	210 TON		
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10 TON		
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0065	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0066	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0068	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0069	6029000000-E	SP	SAFETY FENCE	100 LF		
0070	6030000000-E	1630	SILT EXCAVATION	80 CY		
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0073	6071012000-E	SP	COIR FIBER WATTLE	1,450 LF		
0074	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6087000000-E	1660	MOWING	0.25	ACR	
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	
0080	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	

1603/Sep26/Q39669.39/D274574412000/E81

Total Amount Of Bid For Entire Project :

Contract No. **C202959**

County (ies): **Haywood**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General