

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+47.50 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	6 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	500 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	69.96 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	1,200 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	228 LF		
001E	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	32 LF		
001E	0995000000-E	340	PIPE REMOVAL	140 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
001E	1330000000-E	607	INCIDENTAL MILLING	100 SY		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,120	TON	
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	510	TON	
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	610	TON	
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	115	TON	
0023	2022000000-E	815	SUBDRAIN EXCAVATION	25	CY	
0024	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100	SY	
002E	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	20	CY	
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
0027	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
002E	2077000000-E	815	6" OUTLET PIPE	6	LF	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
003C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0031	2556000000-E	846	SHOULDER BERM GUTTER	25	LF	
0032	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	8	EA	
003E	3030000000-E	862	STEEL BM GUARDRAIL	50	LF	
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3572000000-E	867	CHAIN LINK FENCE RESET	270 LF		
003E	3628000000-E	876	RIP RAP, CLASS I	83 TON		
003E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	751 SY		
004C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	195 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	15 EA		
0042	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	15 EA		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	276 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104 SF		
004E	4430000000-N	1130	DRUMS	20 EA		
0047	4435000000-N	1135	CONES	20 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	104 LF		
004E	4450000000-N	1150	FLAGGER	240 HR		
005C	5325600000-E	1510	6" WATER LINE	517 LF		
0051	5571600000-E	1515	6" TAPPING VALVE	2 EA		
0052	5648000000-N	1515	RELOCATE WATER METER	6 EA		
0053	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	338 LF		
0054	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	37 LF		
005E	5912000000-N	SP	GENERIC UTILITY ITEM INSTALL 4" & 8" MDPE GAS MAIN	Lump Sum	L.S.	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6000000000-E	1605	TEMPORARY SILT FENCE	1,500	LF	
0057	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	285	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	245	TON	
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	75	TON	
006C	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0061	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0062	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0064	6029000000-E	SP	SAFETY FENCE	600	LF	
006E	6030000000-E	1630	SILT EXCAVATION	380	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000	SY	
0067	6037000000-E	SP	COIR FIBER MAT	700	SY	
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	60	LF	
006E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	90	SY	
007C	6071010000-E	SP	WATTLE	210	LF	
0071	6071020000-E	SP	POLYACRYLAMIDE (PAM)	60	LB	
0072	6071030000-E	1640	COIR FIBER BAFFLE	110	LF	
007E	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
0074	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007E	6087000000-E	1660	MOWING	1	ACR	
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
008C	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0082	6123000000-E	1670	REFORESTATION	0.1	ACR	

STRUCTURE ITEMS

008E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 47.50-L-)	Lump Sum	L.S.	
0084	8112730000-N	450	PDA TESTING	1	EA	
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18 + 47.50-L-)	Lump Sum	L.S.	
008E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,631	SF	
0087	8161000000-E	420	GROOVING BRIDGE FLOORS	4,393	SF	
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	54.8	CY	
008E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 47.50-L-)	Lump Sum	L.S.	
009C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,848	LB	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8259000000-E	430	36" PRESTRESSED CONCRETE GIRDERS	508.54 LF		
0092	8364000000-E	450	HP12X53 STEEL PILES	870 LF		
0093	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	450 LF		
0094	8393000000-N	450	PILE REDRIVES	9 EA		
009E	8475000000-E	460	TWO BAR METAL RAIL	190.92 LF		
009E	8517000000-E	460	1'***X ***** CONCRETE PARAPET (1'-2" X 2'-6")	206.55 LF		
0097	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	300 TON		
009E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	332 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

1405/Oct02/Q34522.37/D440784450000/E99

Total Amount Of Bid For Entire Project :

Contract No. **C202957**

County (ies): **Pitt**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)