

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (21 + 94)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	175 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	160 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	6 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	16 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	48 LF		
0012	0995000000-E	340	PIPE REMOVAL	22 LF		
0013	1099500000-E	505	SHALLOW UNDERCUT	25 CY		
0014	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	50 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	130 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	170 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	140 TON		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	200 TON		
002C	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	27 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	125 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	4 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3628000000-E	876	RIP RAP, CLASS I	8 TON		
003C	3635000000-E	876	RIP RAP, CLASS II	71 TON		
0031	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,342 SY		
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	366 SF		
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	88 LF		
003E	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10 TON		
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	305 TON		
004C	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0044	6029000000-E	SP	SAFETY FENCE	100 LF		
004E	6030000000-E	1630	SILT EXCAVATION	100 CY		
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0047	6037000000-E	SP	COIR FIBER MAT	480 SY		
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
004E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	50 SY		
005C	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0051	6071010000-E	SP	WATTLE	45 LF		
0052	6071012000-E	SP	COIR FIBER WATTLE	120 LF		
005E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15 LB		
0054	6071030000-E	1640	COIR FIBER BAFFLE	75 LF		
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6084000000-E	1660	SEEDING & MULCHING	1	ACR	
0057	6087000000-E	1660	MOWING	0.5	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
006C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75	TON	
0062	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0063	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0064	6126000000-E	SP	STREAMBANK REFORESTATION	0.07	ACR	

STRUCTURE ITEMS

006E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21 +94.00-L-)	Lump Sum	L.S.	
006E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 +94.00-L-)	Lump Sum	L.S.	
0067	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	105.5	LF	
006E	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	65	LF	
006E	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	51	LF	
007C	8113000000-N	411	SID INSPECTIONS	1	EA	
0071	8114000000-N	411	SPT TESTING	1	EA	

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8115000000-N	411	CSL TESTING	1 EA		
0073	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (21 + 94.00-L-)	Lump Sum	L.S.	
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	61.6 CY		
007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 94.00-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	22,297 LB		
0077	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,344 LB		
007E	8364000000-E	450	HP12X53 STEEL PILES	320 LF		
007E	8475000000-E	460	TWO BAR METAL RAIL	314.9 LF		
008C	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-10 3/4")	330.52 LF		
0081	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	400 TON		
0082	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	440 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,045 LF		
008E	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		
			Total Amount Of Bid For Entire Project :			

Contract No. **C203018**

County (ies): **Cabarrus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General