

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	11 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	2,700 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (115+52.74 -L-)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	2,360 CY		
0009	0106000000-E	230	BORROW EXCAVATION	211,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	240 CY		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	7,770 SY		
0012	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	2,630 SY		
0013	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	2,400 CY		
0014	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	4,100 SY		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	1,825 TON		
0016	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	3,710 SY		
0017	0335200000-E	305	15" DRAINAGE PIPE	856 LF		
0018	0335300000-E	305	18" DRAINAGE PIPE	128 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0335500000-E	305	30" DRAINAGE PIPE	772 LF		
002C	0335600000-E	305	36" DRAINAGE PIPE	176 LF		
0021	0335700000-E	305	42" DRAINAGE PIPE	44 LF		
0022	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	5,736 LF		
0023	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	1,300 LF		
0024	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	848 LF		
002E	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	420 LF		
002E	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	404 LF		
0027	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	220 LF		
002E	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	72 LF		
002E	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	68 LF		
003C	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	76 LF		
0031	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0032	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (24", 0.064")	2 EA		
0033	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (36", 0.079")	2 EA		
0034	0995000000-E	340	PIPE REMOVAL	400 LF		
003E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1099500000-E	505	SHALLOW UNDERCUT	500 CY		
0037	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	1,000 TON		
003E	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0039	1220000000-E	545	INCIDENTAL STONE BASE	400 TON		
004C	1330000000-E	607	INCIDENTAL MILLING	1,730 SY		
0041	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	11,990 TON		
0042	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	9,030 TON		
0043	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	9,400 TON		
0044	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,525 TON		
004E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	184 TON		
0046	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0047	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0048	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0049	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
005C	2077000000-E	815	6" OUTLET PIPE	6 LF		
0051	2209000000-E	838	ENDWALLS	5 CY		
0052	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	135 EA		
0053	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	43 LF		
0054	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	35 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
005E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0057	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	9 EA		
005E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	24 EA		
005E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	55 EA		
006C	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0061	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	10 EA		
0062	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	19 EA		
006E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	3,085 LF		
0064	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	11,630 LF		
006E	2591000000-E	848	4" CONCRETE SIDEWALK	20 SY		
006E	2605000000-N	848	CONCRETE CURB RAMP	1 EA		
0067	2612000000-E	848	6" CONCRETE DRIVEWAY	360 SY		
006E	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	3,000 SY		
006E	3030000000-E	862	STEEL BM GUARDRAIL	2,225 LF		
007C	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	350 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	10 EA		
0072	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0073	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0074	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
007E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
007E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0077	3628000000-E	876	RIP RAP, CLASS I	120 TON		
007E	3649000000-E	876	RIP RAP, CLASS B	50 TON		
007E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,955 SY		
008C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0081	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	999 LF		
0082	4102000000-N	904	SIGN ERECTION, TYPE E	58 EA		
0083	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	33 EA		
0084	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	576 SF		
008E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	224 SF		
008E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	175 SF		
0087	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
008E	4430000000-N	1130	DRUMS	351 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	4445000000-E	1145	BARRICADES (TYPE III)	448	LF	
009C	4455000000-N	1150	FLAGGER	82	DAY	
0091	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	370	EA	
0092	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	12,242	LF	
0093	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	15,381	LF	
0094	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,317	LF	
009E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	202	LF	
009E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	71	EA	
0097	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	515	LF	
009E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	85,027	LF	
009E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	254	LF	
010C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	754	LF	
0101	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	74	EA	
0102	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	16,060	LF	
0103	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	16	EA	
0104	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	580	EA	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4915000000-E	1264	7' U-CHANNEL POSTS	15 EA		
010E	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	15 EA		
0107	5325200000-E	1510	2" WATER LINE	300 LF		
010E	5325800000-E	1510	8" WATER LINE	3,844 LF		
010E	5326200000-E	1510	12" WATER LINE	7,464 LF		
011C	5536000000-E	1515	2" VALVE	1 EA		
0111	5546000000-E	1515	8" VALVE	12 EA		
0112	5558000000-E	1515	12" VALVE	17 EA		
0113	5606000000-E	1515	2" BLOW OFF	4 EA		
0114	5643000000-E	1515	*** WATER METER (5/8")	42 EA		
011E	5648000000-N	1515	RELOCATE WATER METER	1 EA		
011E	5666000000-E	1515	FIRE HYDRANT	26 EA		
0117	5835700000-E	1540	16" ENCASEMENT PIPE	84 LF		
011E	5836000000-E	1540	24" ENCASEMENT PIPE	266 LF		
011E	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	66 LF		
012C	5888000000-E	SP	GENERIC UTILITY ITEM 12" RJ DI WATER LINE	836 LF		
0121	5888000000-E	SP	GENERIC UTILITY ITEM 8" RJ DI WATER LINE	94 LF		
0122	6000000000-E	1605	TEMPORARY SILT FENCE	17,200 LF		
0123	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,110 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	3,980 TON		
012E	6012000000-E	1610	SEDIMENT CONTROL STONE	2,910 TON		
012E	6015000000-E	1615	TEMPORARY MULCHING	24.5 ACR		
0127	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	750 LB		
012E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.75 TON		
012E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	3,000 LF		
013C	6029000000-E	SP	SAFETY FENCE	400 LF		
0131	6030000000-E	1630	SILT EXCAVATION	7,550 CY		
0132	6036000000-E	1631	MATTING FOR EROSION CONTROL	40,000 SY		
013E	6037000000-E	SP	COIR FIBER MAT	120 SY		
0134	6042000000-E	1632	1/4" HARDWARE CLOTH	6,000 LF		
013E	6071010000-E	SP	WATTLE	300 LF		
013E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	170 LB		
0137	6071030000-E	1640	COIR FIBER BAFFLE	1,750 LF		
013E	6071050000-E	SP	*** SKIMMER (1-1/2")	8 EA		
013E	6071050000-E	SP	*** SKIMMER (2")	1 EA		
014C	6084000000-E	1660	SEEDING & MULCHING	20 ACR		
0141	6087000000-E	1660	MOWING	10 ACR		
0142	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0143	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25	TON	
0144	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	800	LB	
014E	6108000000-E	1665	FERTILIZER TOPDRESSING	23.5	TON	
014E	6114500000-N	1667	SPECIALIZED HAND MOWING	40	MHR	
0147	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75	EA	
014E	7060000000-E	1705	SIGNAL CABLE	1,530	LF	
014E	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	7	EA	
015C	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	1	EA	
0151	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2	EA	
0152	7264000000-E	1710	MESSENGER CABLE (3/8")	470	LF	
0153	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	700	LF	
0154	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	680	LF	
015E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	7	EA	
015E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,650	LF	
0157	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	5,640	LF	
015E	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4	EA	
015E	7613000000-N	SP	SOIL TEST	4	EA	
016C	7614100000-E	SP	DRILLED PIER FOUNDATION	36	CY	
0161	7636000000-N	1745	SIGN FOR SIGNALS	4	EA	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0162	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0163	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0164	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	5 EA		
016E	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
STRUCTURE ITEMS						
016E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (115+52.74 -L-)	Lump Sum	L.S.	
0167	8112730000-N	450	PDA TESTING	1 EA		
016E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (115+52.74 -L-)	Lump Sum	L.S.	
016E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	15,882 SF		
017C	8161000000-E	420	GROOVING BRIDGE FLOORS	12,971 SF		
0171	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	392.9 CY		
0172	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (115+52.74 -L-)	Lump Sum	L.S.	
0173	8217000000-E	425	REINFORCING STEEL (BRIDGE)	34,096 LB		
0174	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	882,500 LS		
017E	8364000000-E	450	HP12X53 STEEL PILES	5,100 LF		
017E	8393000000-N	450	PILE REDRIVES	30 EA		
0177	8482000000-E	460	THREE BAR METAL RAIL	372.88 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
017E	8524000000-E	SP	*** CHAIN LINK FENCE (121")	377 LF		
017E	8531000000-E	462	4" SLOPE PROTECTION	860 SY		
018C	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0181	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
1121/Nov13/Q1511227.78/D748441890000/E181			Total Amount Of Bid For Entire Project :			

Contract No. **C202243**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General