

County : Harnett, Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	2,722 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	434 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	42.6 SMI		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	38,544 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	2,361 SY		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	24,159 TON		
0008	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	8,242 TON		
0009	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,003 TON		
001C	1704000000-E	SP	PATCHING EXISTING PAVEMENT	4,750 TON		
0011	2600000000-N	SP	RETROFIT EXISTING CURB RAMP	66 EA		
0012	2605000000-N	848	CONCRETE CURB RAMP	4 EA		
0013	2830000000-N	858	ADJUSTMENT OF MANHOLES	120 EA		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	104 EA		
001E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	117,600 LF		
001E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	180,985 LF		
0017	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	4,340 LF		
001E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	720 LF		

County : Harnett, Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,030 LF		
002C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	71 EA		
0021	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	238 EA		
0022	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	307,250 LF		
0023	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	525 LF		
0024	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2,635 EA		
002E	6000000000-E	1605	TEMPORARY SILT FENCE	1,814 LF		
0026	6036000000-E	1631	MATTING FOR EROSION CONTROL	150 SY		
0027	6071010000-E	SP	WATTLE	300 LF		
002E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	12 LB		
0029	6084000000-E	1660	SEEDING & MULCHING	35.08 ACR		
003C	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	120 LF		
0031	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,200 LF		
0032	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	12 EA		
0033	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	12 EA		
0034	7420000000-E	1722	2" RISER WITH WEATHERHEAD	12 EA		
003E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,625 LF		

County : Harnett, Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	1,200 LF		
			<hr/>			
1558/Nov07/Q708438.68/D151703130000/E36			Total Amount Of Bid For Entire Project :			

Contract No. **C203215**

County (ies): **Harnett, Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)