

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+47.50 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	169 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
001C	0199000000-E	SP	TEMPORARY SHORING	400 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	5 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	15 SY		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	44 LF		
0014	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	2 EA		
001E	0995000000-E	340	PIPE REMOVAL	200 LF		
001E	1121000000-E	520	AGGREGATE BASE COURSE	760 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	300 SY		
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	110 TON		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,670 TON		
002C	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	770 TON		
0021	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	820 TON		
0022	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	100 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	175 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	50 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	700 LF		
003C	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0031	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	4 EA		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0034	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	2 EA		
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	3 EA		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3360000000-E	863	REMOVE EXISTING GUARDRAIL	720 LF		
0037	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	250 LF		
003E	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)	3 EA		
003E	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
004C	3628000000-E	876	RIP RAP, CLASS I	156 TON		
0041	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	860 SY		
0042	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	282 LF		
0044	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	14 EA		
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	17 EA		
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	432 SF		
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	236 SF		
005C	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0051	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	1 EA		
0052	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	20 DAY		
005E	4430000000-N	1130	DRUMS	180 EA		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4445000000-E	1145	BARRICADES (TYPE III)	176	LF	
005E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1	EA	
005E	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	2	EA	
0057	4480000000-N	1165	TMA	2	EA	
005E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,480	LF	
005E	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	2,960	LF	
006C	4510000000-N	SP	LAW ENFORCEMENT	50	HR	
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	27	EA	
0062	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,864	LF	
0063	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	233	LF	
0064	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	423	LF	
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,226	LF	
006E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	15	EA	
0067	6000000000-E	1605	TEMPORARY SILT FENCE	2,250	LF	
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	390	TON	
007C	6012000000-E	1610	SEDIMENT CONTROL STONE	190	TON	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0072	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0074	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
007E	6029000000-E	SP	SAFETY FENCE	1,000 LF		
007E	6030000000-E	1630	SILT EXCAVATION	330 CY		
0077	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,400 SY		
007E	6037000000-E	SP	COIR FIBER MAT	900 SY		
007E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	770 SY		
008C	6042000000-E	1632	1/4" HARDWARE CLOTH	440 LF		
0081	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
0082	6071010000-E	SP	WATTLE	300 LF		
0083	6071020000-E	SP	POLYACRYLAMIDE (PAM)	160 LB		
0084	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
008E	6087000000-E	1660	MOWING	1.5 ACR		
008E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
008E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
008E	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
009C	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
STRUCTURE ITEMS						
0092	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (18+47.50 -L-)	Lump Sum	L.S.	
0093	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+47.50 -L-)	Lump Sum	L.S.	
0094	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+47.50 -L-)	Lump Sum	L.S.	
0095	8112730000-N	450	PDA TESTING	1 EA		
0096	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+47.50 -L-)	Lump Sum	L.S.	
0097	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,031 SF		
0098	8161000000-E	420	GROOVING BRIDGE FLOORS	7,067 SF		
0099	8196000000-E	420	CLASS A CONCRETE (CULVERT)	108.6 CY		
0100	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+47.50 -L-)	Lump Sum	L.S.	
0101	8217000000-E	425	REINFORCING STEEL (BRIDGE)	16,028 LB		
0102	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	645.38 LF		
0103	8364000000-E	450	HP12X53 STEEL PILES	900 LF		
0104	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24 X 0.50)	518 LF		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	8392000000-N	450	PIPE PILE PLATES	14 EA		
010E	8393000000-N	450	PILE REDRIVES	26 EA		
0107	8503000000-E	460	CONCRETE BARRIER RAIL	266.54 LF		
010E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	421 TON		
010E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	468 SY		
011C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

0804/Nov07/Q74282.77/D488907060000/E110

Total Amount Of Bid For Entire Project :

Contract No. **C203022**

County (ies): **Scotland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General