

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (19 + 65.00-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	400 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	20 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	60 SY		
001C	0344000000-E	310	18" SIDE DRAIN PIPE	72 LF		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	28 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	12 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0014	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	28 LF		
001E	0995000000-E	340	PIPE REMOVAL	88 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	760 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
001E	1275000000-E	600	PRIME COAT	515 GAL		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	800 TON		
002C	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	550 TON		
0021	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	75 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	4 EA		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	175 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		
003C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	500 LF		
0033	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (III)	4 EA		
0034	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003E	3635000000-E	876	RIP RAP, CLASS II	12 TON		
003E	3649000000-E	876	RIP RAP, CLASS B	207 TON		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,191		
				SY		
003E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1		
				EA		
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	101		
				LF		
004C	4096000000-N	904	SIGN ERECTION, TYPE D	2		
				EA		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	2		
				EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4		
				EA		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	403		
				SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192		
				SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57		
				SF		
004E	4430000000-N	1130	DRUMS	40		
				EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	96		
				LF		
004E	4450000000-N	1150	FLAGGER	480		
				HR		
004E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30		
				EA		
005C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,800		
				LF		
0051	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,800		
				LF		
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,640		
				LF		
005E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	11		
				EA		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	2,025		
				LF		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	385 TON		
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	400 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	650 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
006C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	550 LF		
0062	6029000000-E	SP	SAFETY FENCE	300 LF		
0063	6030000000-E	1630	SILT EXCAVATION	880 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,100 SY		
006E	6037000000-E	SP	COIR FIBER MAT	500 SY		
006E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	325 SY		
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	1,150 LF		
006E	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
006E	6071010000-E	SP	WATTLE	500 LF		
007C	6071020000-E	SP	POLYACRYLAMIDE (PAM)	200 LB		
0071	6071030000-E	1640	COIR FIBER BAFFLE	275 LF		
0072	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0073	6084000000-E	1660	SEEDING & MULCHING	4 ACR		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6087000000-E	1660	MOWING	2	ACR	
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0077	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100	LB	
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	3	TON	
007E	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
008C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
<b>STRUCTURE ITEMS</b>						
0081	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (19+65.00-L-)	Lump Sum	L.S.	
0082	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+65.00-L-)	Lump Sum	L.S.	
008E	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	142.4	LF	
0084	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	33	LF	
008E	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	27.4	LF	
008E	8113000000-N	411	SID INSPECTIONS	2	EA	
0087	8114000000-N	411	SPT TESTING	5	EA	
008E	8115000000-N	411	CSL TESTING	2	EA	

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (19 + 65.00-L-)	Lump Sum	L.S.	
009C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	68.6 CY		
0091	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19 + 65.00-L-)	Lump Sum	L.S.	
0092	8217000000-E	425	REINFORCING STEEL (BRIDGE)	28,357 LB		
0093	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,076 LB		
0094	8364000000-E	450	HP12X53 STEEL PILES	275 LF		
009E	8392500000-E	450	PREDRILLING FOR PILES	30 LF		
009E	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	420 LF		
0097	8594000000-E	876	RIP RAP, CLASS B	75 TON		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	550 TON		
009E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	610 SY		
010C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0101	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	2,100 LF		

1456/Nov29/Q72241.15/D467583950000/E101

Total Amount Of Bid For Entire Project :

**Contract No.**     **C203079**

**County (ies):**    **Caswell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General