

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (20+74.50)	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (21+69.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	220 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	4,300 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	70 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	150 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	270 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	52 LF		
0014	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0016	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	120 LF		
0017	0995000000-E	340	PIPE REMOVAL	84 LF		
0018	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	100 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	45 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0021	1330000000-E	607	INCIDENTAL MILLING	340 SY		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	730 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	395 TON		
0024	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	590 TON		
0025	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	95 TON		
0026	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0029	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0030	2077000000-E	815	6" OUTLET PIPE	6 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0034	2556000000-E	846	SHOULDER BERM GUTTER	150 LF		
0035	2619000000-E	850	4" CONCRETE PAVED DITCH	20 SY		
0036	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0037	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	315000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0039	316500000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	3 EA		
0040	319500000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0041	321500000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0042	362800000-E	876	RIP RAP, CLASS I	12 TON		
0043	364900000-E	876	RIP RAP, CLASS B	16 TON		
0044	365600000-E	876	GEOTEXTILE FOR DRAINAGE	976 SY		
0045	407200000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	25 LF		
0046	410200000-N	904	SIGN ERECTION, TYPE E	2 EA		
0047	411610000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0048	415500000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	12 EA		
0049	440000000-E	1110	WORK ZONE SIGNS (STATIONARY)	568 SF		
0050	440500000-E	1110	WORK ZONE SIGNS (PORTABLE)	112 SF		
0051	441000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	145 SF		
0052	443000000-N	1130	DRUMS	51 EA		
0053	443500000-N	1135	CONES	19 EA		
0054	444500000-E	1145	BARRICADES (TYPE III)	100 LF		
0055	445000000-N	1150	FLAGGER	400 HR		
0056	451600000-N	1180	SKINNY DRUM	19 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30 EA		
0058	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,758 LF		
0059	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	25 EA		
0060	5325800000-E	1510	8" WATER LINE	1,120 LF		
0061	5546000000-E	1515	8" VALVE	2 EA		
0062	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
0063	5801000000-E	1530	ABANDON 8" UTILITY PIPE	1,080 LF		
0064	5835700000-E	1540	16" ENCASEMENT PIPE	105 LF		
0065	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	35 LF		
0066	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	35 LF		
0067	6000000000-E	1605	TEMPORARY SILT FENCE	2,150 LF		
0068	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	330 TON		
0069	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	270 TON		
0070	6012000000-E	1610	SEDIMENT CONTROL STONE	190 TON		
0071	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0072	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0074	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0075	6029000000-E	SP	SAFETY FENCE	400 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6030000000-E	1630	SILT EXCAVATION	410 CY		
0077	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0078	6037000000-E	SP	COIR FIBER MAT	50 SY		
0079	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	120 SY		
0080	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0081	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA		
0082	6071010000-E	SP	WATTLE	100 LF		
0083	6071020000-E	SP	POLYACRYLAMIDE (PAM)	35 LB		
0084	6071030000-E	1640	COIR FIBER BAFFLE	200 LF		
0085	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0086	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0087	6087000000-E	1660	MOWING	1 ACR		
0088	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0089	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0090	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0091	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0092	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0093	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
WALL ITEMS						
0094	843000000-E	452	SHEET PILE RETAINING WALLS	325		
				SF		
STRUCTURE ITEMS						
0095	802100000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+74.50-L-)	Lump Sum	L.S.	
0096	803500000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+69.50-L-)	Lump Sum	L.S.	
0097	812100000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+74.50-L-)	Lump Sum	L.S.	
0098	812100000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21+69.50-L-)	Lump Sum	L.S.	
0099	818200000-E	420	CLASS A CONCRETE (BRIDGE)	64		
				CY		
0100	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+74.50-L-)	Lump Sum	L.S.	
0101	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+22.01-L-)	Lump Sum	L.S.	
0102	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+69.50-L-)	Lump Sum	L.S.	
0103	821700000-E	425	REINFORCING STEEL (BRIDGE)	9,694		
				LB		
0104	836400000-E	450	HP12X53 STEEL PILES	1,040		
				LF		
0105	847500000-E	460	TWO BAR METAL RAIL	268.71		
				LF		
0106	851700000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" x 2'-10 1/2")	290		
				LF		
0107	860800000-E	876	RIP RAP CLASS II (2'-0" THICK)	290		
				TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	322 SY		
0109	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0110	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,430 LF		
0111	8892000000-E	SP	GENERIC STRUCTURE ITEM (18" STEEL SHEET PILES)	2,755 SF		

0813/Dec07/Q62752.21/D487257070000/E111

Total Amount Of Bid For Entire Project :

Contract No. **C202842**

County (ies): **Henderson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)