

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (19+72.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	71 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	222 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	24 LF		
0011	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (15", V)	648 LF		
0012	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0013	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	190 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	222 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	280 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	118 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	210 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	30 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8 EA		
0023	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	586 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	900 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0029	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,091 LF		
0030	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,275 SY		
0032	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	61 LF		
0033	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0034	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8 EA		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	297 SF		
0036	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0037	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,150 LF		
0039	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,150 LF		
0040	5325800000-E	1510	8" WATER LINE	524 LF		
0041	5546000000-E	1515	8" VALVE	2 EA		
0042	5801000000-E	1530	ABANDON 8" UTILITY PIPE	520 LF		
0043	5882000000-N	SP	GENERIC UTILITY ITEM STEEL PIPE CAP FOR WATER LINE	13 EA		
0044	5888000000-E	SP	GENERIC UTILITY ITEM HP 12 X 53 GALVANIZED STEEL PILES FOR WATER LINE	301.5 LF		
0045	5888000000-E	SP	GENERIC UTILITY ITEM PERM ST CASING FOR 2'-6" MIN DIA HOLE	97.5 LF		
0046	5888000000-E	SP	GENERIC UTILITY ITEM PILE EXCAVATION IN SOIL FOR WATER LINE	70.5 LF		
0047	5888000000-E	SP	GENERIC UTILITY ITEM PILE EXCAVATION NOT IN SOIL FOR WATER LINE	42 LF		
0048	5888000000-E	SP	GENERIC UTILITY ITEM PIPE INSULATION	500 LF		
0049	6000000000-E	1605	TEMPORARY SILT FENCE	1,525 LF		
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	385 TON		
0053	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0056	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0057	6029000000-E	SP	SAFETY FENCE	100 LF		
0058	6030000000-E	1630	SILT EXCAVATION	100 CY		
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	570 LF		
0061	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	350 SY		
0062	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0063	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0064	6087000000-E	1660	MOWING	0.25 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0069	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

---

**WALL ITEMS**


---

0071	8430000000-E	452	SHEET PILE RETAINING WALLS	2,105 SF		
------	--------------	-----	----------------------------	-------------	--	--

---

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (19+72.50-L-)	Lump Sum	L.S.	
0073	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+72.50-L-)	Lump Sum	L.S.	
0074	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	117.6 LF		
0075	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	62 LF		
0076	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	116.6 LF		
0077	8113000000-N	411	SID INSPECTIONS	6 EA		
0078	8114000000-N	411	SPT TESTING	1 EA		
0079	8115000000-N	411	CSL TESTING	1 EA		
0080	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19+72.50-L-)	Lump Sum	L.S.	
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	75.6 CY		
0082	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+72.50-L-)	Lump Sum	L.S.	
0083	8217000000-E	425	REINFORCING STEEL (BRIDGE)	23,257 LB		
0084	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,208 LB		
0085	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
0086	8475000000-E	460	TWO BAR METAL RAIL	345.5 LF		
0087	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" x 2'-11")	360.5 LF		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,320 LF		
0090	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	840 LF		
1339/Dec03/Q47550.3/D432893540000/E90			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C203031**

**County (ies):**   **Rowan**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General