

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	8,500 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0004	1243000000-E	SP	SHOULDER CONSTRUCTION	0.4 SMI		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	17.3 SMI		
0006	1264000000-E	SP	DITCHING	2,200 LF		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	742 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 4")	650 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	8,500 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,350 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,450 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,051 TON		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	600 TON		
0015	2612000000-E	848	6" CONCRETE DRIVEWAY	165 SY		
0016	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	4 EA		
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	43,200 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	44,467 LF		
0020	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	100 LF		
0021	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	50 LF		
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	195 LF		
0023	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	2 EA		
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6 EA		
0025	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	287,804 LF		
0026	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100 LF		
0027	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	12 EA		
0028	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	657 EA		
0029	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF		
0030	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
0031	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0032	6071010000-E	SP	WATTLE	500 LF		
0033	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2 LB		

1605/Jan03/Q411812.7/D107599130000/E33

Total Amount Of Bid For Entire Project :

Contract No. **C203266**

County (ies): **Stanly**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General