

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0015000000-N	205	SEALING ABANDONED WELLS	17 EA		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+00-L-)	Lump Sum	L.S.	
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (87+00-L-)	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	1,700 CY		
0008	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0009	0106000000-E	230	BORROW EXCAVATION	419,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	9,085 CY		
0011	0192000000-N	260	PROOF ROLLING	22 HR		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
0013	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	20,850 SY		
0014	0199000000-E	SP	TEMPORARY SHORING	2,880 SF		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	1,860 TON		
0016	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	4,070 SY		
0017	0342000000-E	310	*** SIDE DRAIN PIPE (30")	1,960 LF		
0018	0342000000-E	310	*** SIDE DRAIN PIPE (36")	2,144 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0342000000-E	310	*** SIDE DRAIN PIPE (42")	316 LF		
0020	0342000000-E	310	*** SIDE DRAIN PIPE (48")	132 LF		
0021	0343000000-E	310	15" SIDE DRAIN PIPE	3,840 LF		
0022	0344000000-E	310	18" SIDE DRAIN PIPE	1,752 LF		
0023	0345000000-E	310	24" SIDE DRAIN PIPE	1,400 LF		
0024	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	312 LF		
0025	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	56 LF		
0026	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	112 LF		
0027	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	264 LF		
0028	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	140 LF		
0029	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	14 EA		
0030	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")	4 EA		
0031	0995000000-E	340	PIPE REMOVAL	5,154 LF		
0032	1099500000-E	505	SHALLOW UNDERCUT	4,330 CY		
0033	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	7,900 TON		
0034	1110000000-E	510	STABILIZER AGGREGATE	16,000 TON		
0035	1121000000-E	520	AGGREGATE BASE COURSE	27,225 TON		
0036	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	1275000000-E	600	PRIME COAT	21,105 GAL		
0038	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	150 SY		
0039	1330000000-E	607	INCIDENTAL MILLING	1,300 SY		
0040	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	12,470 TON		
0041	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	4,910 TON		
0042	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	12,701 TON		
0043	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,810 TON		
0044	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	21,012 TON		
0045	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	6,510 TON		
0046	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	3,110 TON		
0047	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	590 TON		
0048	2022000000-E	815	SUBDRAIN EXCAVATION	268.8 CY		
0049	2033000000-E	815	SUBDRAIN FINE AGGREGATE	201.6 CY		
0050	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,200 LF		
0051	2070000000-N	815	SUBDRAIN PIPE OUTLET	3 EA		
0052	2077000000-E	815	6" OUTLET PIPE	18 LF		
0053	2209000000-E	838	ENDWALLS	54 CY		
0054	2220000000-E	838	REINFORCED ENDWALLS	16 CY		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2253000000-E	840	PIPE COLLARS	1 CY		
0056	2275000000-E	SP	FLOWABLE FILL	65 CY		
0057	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	108 EA		
0058	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	22 LF		
0059	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	31 EA		
0060	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0061	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	13 EA		
0062	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	11 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	9 EA		
0065	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	19 EA		
0066	2396000000-N	840	FRAME WITH COVER, STD 840.54	20 EA		
0067	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	20 EA		
0068	2538000000-E	846	***.*** CONCRETE CURB & GUTTER (9" X 12")	300 LF		
0069	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	5,600 LF		
0070	2556000000-E	846	SHOULDER BERM GUTTER	2,210 LF		
0071	2612000000-E	848	6" CONCRETE DRIVEWAY	150 SY		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	2,875 SY		
0073	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0074	3030000000-E	862	STEEL BM GUARDRAIL	2,400 LF		
0075	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0076	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0077	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	18 EA		
0078	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0079	3360000000-E	863	REMOVE EXISTING GUARDRAIL	4,725 LF		
0080	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	150 LF		
0081	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0082	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	29,550 LF		
0083	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	1,870 EA		
0084	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	470 EA		
0085	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	4,550 LF		
0086	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	390 EA		
0087	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	50 EA		
0088	3557000000-E	866	ADDITIONAL BARBED WIRE	1,500 LF		
0089	3565000000-E	866	DOUBLE GATES, *** HIGH, ** WIDE, *** OPENING (48", 12', 24')	2 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	3628000000-E	876	RIP RAP, CLASS I	300 TON		
0091	3635000000-E	876	RIP RAP, CLASS II	450 TON		
0092	3649000000-E	876	RIP RAP, CLASS B	125 TON		
0093	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	4,735 SY		
0094	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	7 CY		
0095	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 CY		
0096	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	6,845 LB		
0097	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	3,294 LF		
0098	4096000000-N	904	SIGN ERECTION, TYPE D	13 EA		
0099	4102000000-N	904	SIGN ERECTION, TYPE E	106 EA		
0100	4108000000-N	904	SIGN ERECTION, TYPE F	45 EA		
0101	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	8 EA		
0102	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	2 EA		
0103	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	3 EA		
0104	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	1 EA		
0105	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	70 EA		
0106	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2 EA		
0107	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	812 SF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	676 SF		
0109	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	389 SF		
0110	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0111	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	5 EA		
0112	4430000000-N	1130	DRUMS	639 EA		
0113	4435000000-N	1135	CONES	169 EA		
0114	4445000000-E	1145	BARRICADES (TYPE III)	640 LF		
0115	4450000000-N	1150	FLAGGER	8,800 HR		
0116	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0117	4480000000-N	1165	TMA	2 EA		
0118	4485000000-E	1170	PORTABLE CONCRETE BARRIER	375 LF		
0119	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	670 LF		
0120	4507000000-E	1170	WATER FILLED BARRIER	710 LF		
0121	4510000000-N	SP	LAW ENFORCEMENT	320 HR		
0122	4516000000-N	1180	SKINNY DRUM	213 EA		
0123	4520000000-N	1266	TUBULAR MARKERS (FIXED)	95 EA		
0124	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,858 EA		
0125	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	53,923 LF		
0126	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	89,405 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	3,010 LF		
0128	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	510 LF		
0129	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	962 LF		
0130	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
0131	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	181 EA		
0132	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,378 LF		
0133	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	2,381 LF		
0134	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)	89 LF		
0135	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (IV)	4 EA		
0136	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (III)	2 EA		
0137	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	2 EA		
0138	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	291,876 LF		
0139	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	7,092 LF		
0140	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,152 LF		
0141	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	88 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	420 EA		
0143	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,750 LF		
0144	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	149 LF		
0145	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	4 EA		
0146	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,781 EA		
0147	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0148	5325200000-E	1510	2" WATER LINE	1,034 LF		
0149	5325600000-E	1510	6" WATER LINE	2,709 LF		
0150	5325800000-E	1510	8" WATER LINE	259 LF		
0151	5326200000-E	1510	12" WATER LINE	83 LF		
0152	5327400000-E	1510	24" WATER LINE	2,987 LF		
0153	5536000000-E	1515	2" VALVE	1 EA		
0154	5540000000-E	1515	6" VALVE	8 EA		
0155	5546000000-E	1515	8" VALVE	6 EA		
0156	5559400000-E	1515	24" VALVE	2 EA		
0157	5571600000-E	1515	6" TAPPING VALVE	5 EA		
0158	5571800000-E	1515	8" TAPPING VALVE	3 EA		
0159	5572200000-E	1515	12" TAPPING VALVE	3 EA		
0160	5572600000-E	1515	16" TAPPING VALVE	1 EA		
0161	5573400000-E	1515	24" TAPPING VALVE	1 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0162	5589100000-E	1515	1" AIR RELEASE VALVE	2 EA		
0163	5648000000-N	1515	RELOCATE WATER METER	35 EA		
0164	5649000000-N	1515	RECONNECT WATER METER	20 EA		
0165	5672000000-N	1515	RELOCATE FIRE HYDRANT	6 EA		
0166	5691300000-E	1520	8" SANITARY GRAVITY SEWER	1,216 LF		
0167	5709300000-E	1520	6" FORCE MAIN SEWER	2,382 LF		
0168	5709400000-E	1520	8" FORCE MAIN SEWER	946 LF		
0169	5709600000-E	1520	12" FORCE MAIN SEWER	168 LF		
0170	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	5 EA		
0171	5775000000-E	1525	4' DIA UTILITY MANHOLE	6 EA		
0172	5800000000-E	1530	ABANDON 6" UTILITY PIPE	2,485 LF		
0173	5801000000-E	1530	ABANDON 8" UTILITY PIPE	5,397 LF		
0174	5804000000-E	1530	ABANDON 12" UTILITY PIPE	2,790 LF		
0175	5810000000-E	1530	ABANDON 16" UTILITY PIPE	2,725 LF		
0176	5816000000-N	1530	ABANDON UTILITY MANHOLE	4 EA		
0177	5828000000-N	1530	REMOVE UTILITY MANHOLE	1 EA		
0179	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	84 LF		
0180	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	84 LF		
0181	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	50 LF		
0182	5872210000-E	1550	TRENCHLESS INSTALLATION OF 24" NOT IN SOIL	50 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0183	5875000000-N	SP	CONCRETE PIERS	2 EA		
0184	5882000000-N	SP	GENERIC UTILITY ITEM RECONNECT SEWER FORCE MAIN SERVICE	5 EA		
0185	6000000000-E	1605	TEMPORARY SILT FENCE	60,000 LF		
0186	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	4,350 TON		
0187	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	11,200 TON		
0188	6012000000-E	1610	SEDIMENT CONTROL STONE	7,660 TON		
0189	6015000000-E	1615	TEMPORARY MULCHING	180 ACR		
0190	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,450 LB		
0191	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	14.5 TON		
0192	6024000000-E	1622	TEMPORARY SLOPE DRAINS	10,000 LF		
0193	6029000000-E	SP	SAFETY FENCE	16,000 LF		
0194	6030000000-E	1630	SILT EXCAVATION	17,380 CY		
0195	6036000000-E	1631	MATTING FOR EROSION CONTROL	50,000 SY		
0196	6037000000-E	SP	COIR FIBER MAT	2,500 SY		
0197	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	3,050 SY		
0198	6042000000-E	1632	1/4" HARDWARE CLOTH	9,000 LF		
0199	6045000000-E	SP	*** TEMPORARY PIPE (18")	115 LF		
0200	6045000000-E	SP	*** TEMPORARY PIPE (30")	200 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0201	6046000000-E	1636	TEMPORARY PIPE FOR STREAM CROSSING	80 LF		
0202	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	50 SY		
0203	6070000000-N	1639	SPECIAL STILLING BASINS	15 EA		
0204	6071012000-E	SP	COIR FIBER WATTLE	5,500 LF		
0205	6071020000-E	SP	POLYACRYLAMIDE (PAM)	4,500 LB		
0206	6071030000-E	1640	COIR FIBER BAFFLE	2,500 LF		
0207	6071050000-E	SP	*** SKIMMER (1-1/2")	10 EA		
0208	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0209	6071050000-E	SP	*** SKIMMER (3")	1 EA		
0210	6084000000-E	1660	SEEDING & MULCHING	120 ACR		
0211	6087000000-E	1660	MOWING	90 ACR		
0212	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,800 LB		
0213	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	6 TON		
0214	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,950 LB		
0215	6108000000-E	1665	FERTILIZER TOPDRESSING	88.5 TON		
0216	6111000000-E	SP	IMPERVIOUS DIKE	525 LF		
0217	6114500000-N	1667	SPECIALIZED HAND MOWING	25 MHR		
0218	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	150 EA		
0219	6120000000-E	SP	CULVERT DIVERSION CHANNEL	250 CY		
0220	6123000000-E	1670	REFORESTATION	5 ACR		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0221	6126000000-E	SP	STREAMBANK REFORESTATION	0.55 ACR		
0222	6135000000-E	SP	GENERIC EROSION CONTROL ITEM COMPOST BLANKET	40 ACR		
0223	7060000000-E	1705	SIGNAL CABLE	13,080 LF		
0224	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	72 EA		
0225	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	17 EA		
0226	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	10 EA		
0227	7252000000-E	1710	MESSENGER CABLE (1/4")	891 LF		
0228	7264000000-E	1710	MESSENGER CABLE (3/8")	1,260 LF		
0229	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	6,077 LF		
0230	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2"))	195 LF		
0231	7301000000-E	1715	DIRECTIONAL DRILL (***** (3, 2"))	1,607 LF		
0232	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	40 EA		
0233	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	21 EA		
0234	7360000000-N	1720	WOOD POLE	9 EA		
0235	7372000000-N	1721	GUY ASSEMBLY	18 EA		
0236	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		
0237	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0238	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,800 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0239	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	25,700 LF		
0240	7481000000-N	SP	SITE SURVEY	1 EA		
0241	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	2 EA		
0242	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	4 EA		
0243	7481260000-N	SP	EXTERNAL LOOP EMULATOR PRO- CESSING UNIT	1 EA		
0244	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	2 EA		
0245	7575142000-N	1736	900MHZ RADIO	6 EA		
0246	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	11 EA		
0247	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	5 EA		
0248	7613000000-N	SP	SOIL TEST	16 EA		
0249	7614100000-E	SP	DRILLED PIER FOUNDATION	112 CY		
0250	7636000000-N	1745	SIGN FOR SIGNALS	10 EA		
0251	7684000000-N	1750	SIGNAL CABINET FOUNDATION	5 EA		
0252	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	5 EA		
0253	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	40 EA		
0254	7901000000-N	1753	CABINET BASE EXTENDER	5 EA		
0284	5679000000-E	1515	12" LINE STOP	3 EA		
0285	5679200000-E	1515	16" LINE STOP	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0286	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	29 EA		
CULVERT ITEMS						
0255	8126000000-N	414	CULVERT EXCAVATION, STA ***** (112+82.50-L-)	Lump Sum	L.S.	
0256	8126000000-N	414	CULVERT EXCAVATION, STA ***** (127+46.00-L-)	Lump Sum	L.S.	
0257	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	261 TON		
0258	8196000000-E	420	CLASS A CONCRETE (CULVERT)	344.6 CY		
0259	8248000000-E	425	EPOXY COATED REINFORCING STEEL (CULVERT)	38,457 LB		
0260	8594000000-E	876	RIP RAP, CLASS B	125 TON		
WALL ITEMS						
0261	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO. 1	1,350 SF		
STRUCTURE ITEMS						
0262	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+02.90-L-)	Lump Sum	L.S.	
0263	8112730000-N	450	PDA TESTING	3 EA		
0264	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (22+02.90-L-)	Lump Sum	L.S.	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0265	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (87+04.50-L-)	Lump Sum	L.S.	
0266	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	14,417 SF		
0267	8161000000-E	420	GROOVING BRIDGE FLOORS	16,639 SF		
0268	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	245 CY		
0269	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+02.90-L-)	Lump Sum	L.S.	
0270	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (87+04.50-L-)	Lump Sum	L.S.	
0271	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	36,463 LB		
0272	8259000000-E	430	36" PRESTRESSED CONCRETE GIRDERS	2,009.84 LF		
0273	8329000000-E	450	12" PRESTRESSED CONCRETE PILES	180 LF		
0274	8333000000-E	450	16" PRESTRESSED CONCRETE PILES	2,700 LF		
0275	8364000000-E	450	HP12X53 STEEL PILES	1,100 LF		
0276	8393000000-N	450	PILE REDRIVES	34 EA		
0277	8475000000-E	460	TWO BAR METAL RAIL	255.49 LF		
0278	8503000000-E	460	CONCRETE BARRIER RAIL	372.92 LF		
0279	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-6")	287.16 LF		
0280	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,142 TON		
0281	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	1,269 SY		
0282	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

0283	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
------	--------------	----	-----------------------	----------	------	--

0935/Mar08/Q1591278.96/D1332592704000/E285

Total Amount Of Bid For Entire Project :

Contract No. **C202155**

County (ies): **Brunswick**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General