

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+08.71-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	300 SY		
0007	0223000000-E	275	ROCK PLATING	600 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	5 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	10 SY		
0010	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	20 LF		
0011	1099500000-E	505	SHALLOW UNDERCUT	300 CY		
0012	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	570 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	900 TON		
0015	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	525 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	140 TON		
0017	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	500 TON		
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	104 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2264000000-E	840	PIPE PLUGS	1 CY		
0020	2275000000-E	SP	FLOWABLE FILL	5 CY		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0023	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0025	2950000000-N	859	CONVERT EXISTING JUNCTION BOX TO DROP INLET	1 EA		
0026	3030000000-E	862	STEEL BM GUARDRAIL	700 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0028	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0030	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0031	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,055 LF		
0032	3595000000-E	869	RELAPPING GUARDRAIL	314 LF		
0033	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,000 SY		
0034	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	82 LF		
0035	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0036	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	5 EA		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	810 SF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	384	SF	
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36	SF	
0040	4415000000-N	1115	FLASHING ARROW BOARD	4	EA	
0041	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2	EA	
0042	4430000000-N	1130	DRUMS	200	EA	
0043	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
0044	4480000000-N	1165	TMA	2	EA	
0045	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,770	LF	
0046	4510000000-N	SP	LAW ENFORCEMENT	16	HR	
0047	4595000000-E	SP	GENERIC TRAFFIC CONTROL ITEM OVERSIZED VEHICLES DETOUR ROUTE SIGNING	1,132	SF	
0048	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,328	EA	
0049	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	11,090	LF	
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,386	LF	
0051	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	1,024	LF	
0052	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,411	LF	
0053	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	6	EA	
0054	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	69	EA	
0055	6000000000-E	1605	TEMPORARY SILT FENCE	450	LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	45 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	335 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0063	6029000000-E	SP	SAFETY FENCE	400 LF		
0064	6030000000-E	1630	SILT EXCAVATION	200 CY		
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0066	6037000000-E	SP	COIR FIBER MAT	475 SY		
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	725 LF		
0068	6070000000-N	1639	SPECIAL STILLING BASINS	8 EA		
0069	6071010000-E	SP	WATTLE	325 LF		
0070	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100 LB		
0071	6071030000-E	1640	COIR FIBER BAFFLE	100 LF		
0072	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0073	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0074	6087000000-E	1660	MOWING	1 ACR		
0075	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0077	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0078	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0079	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0080	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
STRUCTURE ITEMS						
0081	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+08.71-L-)	Lump Sum	L.S.	
0082	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+08.71-L-)	Lump Sum	L.S.	
0083	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	64 LF		
0084	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	82 LF		
0085	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	74 LF		
0086	8113000000-N	411	SID INSPECTIONS	1 EA		
0087	8114000000-N	411	SPT TESTING	1 EA		
0088	8115000000-N	411	CSL TESTING	1 EA		
0089	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+08.71-L-)	Lump Sum	L.S.	
0090	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,888 SF		
0091	8161000000-E	420	GROOVING BRIDGE FLOORS	8,992 SF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	139.1 CY		
0093	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+08.71-L-)	Lump Sum	L.S.	
0094	8217000000-E	425	REINFORCING STEEL (BRIDGE)	32,223 LB		
0095	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,872 LB		
0096	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	890 LF		
0097	8364000000-E	450	HP12X53 STEEL PILES	490 LF		
0098	8503000000-E	460	CONCRETE BARRIER RAIL	494.51 LF		
0099	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	734 TON		
0100	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	814 SY		
0101	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0102	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0820/Feb01/Q97100.36/D490309690000/E102				Total Amount Of Bid For Entire Project :		

Contract No. **C203085**

County (ies): **Davidson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General