

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (25+67.96)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	10,500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	78,900 CY		
0008	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	4 EA		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,660 CY		
0010	0192000000-N	260	PROOF ROLLING	1.1 HR		
0011	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	10,500 CY		
0012	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	10,680 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	70 TON		
0014	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	190 SY		
0015	0335200000-E	305	15" DRAINAGE PIPE	280 LF		
0016	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0017	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	156 LF		
0018	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	128 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0973100000-E	330	*** WELDED STEEL PIPE, **** THICK, GRADE B IN SOIL (48", 0.688")	48 LF		
0020	0973300000-E	330	*** WELDED STEEL PIPE, **** THICK, GRADE B NOT IN SOIL (48", 0.688")	48 LF		
0021	0986000000-E	SP	GENERIC PIPE ITEM 48" WELDED STEEL PIPE, 0.688" THICK, GRADE B, OPEN CUT	20 LF		
0022	0995000000-E	340	PIPE REMOVAL	149 LF		
0023	1121000000-E	520	AGGREGATE BASE COURSE	73 TON		
0024	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0025	1330000000-E	607	INCIDENTAL MILLING	175 SY		
0026	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	130 TON		
0027	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,910 TON		
0028	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,100 TON		
0029	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,100 TON		
0030	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	50 TON		
0031	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	260 TON		
0032	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0033	2000000000-N	806	RIGHT OF WAY MARKERS	27 EA		
0034	2209000000-E	838	ENDWALLS	10 CY		
0035	2253000000-E	840	PIPE COLLARS	1 CY		
0036	2275000000-E	SP	FLOWABLE FILL	25 CY		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0038	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0039	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0040	2556000000-E	846	SHOULDER BERM GUTTER	360 LF		
0041	3030000000-E	862	STEEL BM GUARDRAIL	1,912.5 LF		
0042	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	4 EA		
0043	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0045	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0046	3578000000-N	SP	GENERIC FENCING ITEM RIGHT OF WAY GATE	1 EA		
0047	3628000000-E	876	RIP RAP, CLASS I	370 TON		
0048	3649000000-E	876	RIP RAP, CLASS B	550 TON		
0049	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	3,645 SY		
0050	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	90 SF		
0051	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	344 LF		
0052	4102000000-N	904	SIGN ERECTION, TYPE E	15 EA		
0053	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		
0054	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	8 EA		
0055	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	500 SF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100 SF		
0057	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	120 SF		
0058	4430000000-N	1130	DRUMS	30 EA		
0059	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0060	4450000000-N	1150	FLAGGER	40 HR		
0061	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,200 LF		
0062	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,540 LF		
0063	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	1,952 LF		
0064	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,500 LF		
0065	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2 EA		
0066	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	6 EA		
0067	5325600000-E	1510	6" WATER LINE	215 LF		
0068	5606600000-E	1515	6" BLOW OFF	1 EA		
0069	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0070	6000000000-E	1605	TEMPORARY SILT FENCE	7,000 LF		
0071	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0072	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,200 TON		
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	750 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6015000000-E	1615	TEMPORARY MULCHING	15	ACR	
0075	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500	LB	
0076	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3	TON	
0077	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,000	LF	
0078	6029000000-E	SP	SAFETY FENCE	200	LF	
0079	6030000000-E	1630	SILT EXCAVATION	1,000	CY	
0080	6036000000-E	1631	MATTING FOR EROSION CONTROL	20,940	SY	
0081	6037000000-E	SP	COIR FIBER MAT	100	SY	
0082	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	220	SY	
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	600	LF	
0084	6070000000-N	1639	SPECIAL STILLING BASINS	16	EA	
0085	6071010000-E	SP	WATTLE	1,650	LF	
0086	6071020000-E	SP	POLYACRYLAMIDE (PAM)	300	LB	
0087	6071030000-E	1640	COIR FIBER BAFFLE	300	LF	
0088	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
0089	6084000000-E	1660	SEEDING & MULCHING	15	ACR	
0090	6087000000-E	1660	MOWING	8	ACR	
0091	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	
0092	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0093	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	300	LB	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	6108000000-E	1665	FERTILIZER TOPDRESSING	9 TON		
0095	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0096	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0097	7985000000-N	SP	GENERIC SIGNAL ITEM REMOVAL & DISPOSAL OF RAILROAD WARNING BEACON & EQUIPMENT	Lump Sum	L.S.	
STRUCTURE ITEMS						
0098	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26+52.19-L-)	Lump Sum	L.S.	
0099	8105500000-E	411	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	120.5 LF		
0100	8105600000-E	411	***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	103 LF		
0101	8111000000-E	411	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	24.6 LF		
0102	8113000000-N	411	SID INSPECTIONS	1 EA		
0103	8114000000-N	411	SPT TESTING	1 EA		
0104	8115000000-N	411	CSL TESTING	1 EA		
0105	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	17,421 SF		
0106	8161000000-E	420	GROOVING BRIDGE FLOORS	16,333 SF		
0107	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	389.7 CY		
0108	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26+52.19-L-)	Lump Sum	L.S.	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8217000000-E	425	REINFORCING STEEL (BRIDGE)	82,829 LB		
0110	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	12,355 LB		
0111	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	1,500.83 LF		
0112	8364000000-E	450	HP12X53 STEEL PILES	1,246 LF		
0113	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	960.75 LF		
0114	8524000000-E	SP	*** CHAIN LINK FENCE (72")	248 LF		
0115	8531000000-E	462	4" SLOPE PROTECTION	343 SY		
0116	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	530 TON		
0117	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	590 SY		
0118	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0119	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
1154/Feb08/Q317378.23/D517075060000/E119			Total Amount Of Bid For Entire Project :			

1-17-12
Z-140

Contract No. **C203141**

County (ies): **Davidson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)