

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (20+70 -L-)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	400 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	400 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	15 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	55 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0011	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (15", V)	28 LF		
0012	1330000000-E	607	INCIDENTAL MILLING	190 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	220 TON		
0014	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	170 TON		
0015	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	20 TON		
0016	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0018	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0020	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	110 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	137.5 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0029	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0030	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	455 SY		
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	16 LF		
0032	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4 EA		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	215 SF		
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		
0036	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	860 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	860	LF	
0039	5326200000-E	1510	12" WATER LINE	420	LF	
0040	5558000000-E	1515	12" VALVE	1	EA	
0041	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
0042	5804000000-E	1530	ABANDON 12" UTILITY PIPE	420	LF	
0043	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	170	LF	
0044	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	170	LF	
0045	6000000000-E	1605	TEMPORARY SILT FENCE	965	LF	
0046	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	30	TON	
0048	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100	LF	
0052	6029000000-E	SP	SAFETY FENCE	500	LF	
0053	6030000000-E	1630	SILT EXCAVATION	50	CY	
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	750	SY	
0055	6037000000-E	SP	COIR FIBER MAT	375	SY	
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	130	LF	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
0058	6069000000-E	1638	STILLING BASINS	2 CY		
0059	6071012000-E	SP	COIR FIBER WATTLE	330 LF		
0060	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0061	6087000000-E	1660	MOWING	0.15 ACR		
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0063	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0064	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0065	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0066	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0067	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		
0068	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0069	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+70.00-L-)	Lump Sum	L.S.	
0070	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+70.00-L-)	Lump Sum	L.S.	
0071	8156000000-E	SP	CONCRETE WEARING SURFACE	2,779 SF		
0072	8161000000-E	420	GROOVING BRIDGE FLOORS	3,128 SF		
0073	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	41.9 CY		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+70.00-L-)	Lump Sum	L.S.	
0075	821700000-E	425	REINFORCING STEEL (BRIDGE)	6,666 LB		
0076	836400000-E	450	HP12X53 STEEL PILES	630 LF		
0077	838420000-E	450	HP14X73 GALVANIZED STEEL PILES	400 LF		
0078	850500000-E	460	VERTICAL CONCRETE BARRIER RAIL	180.25 LF		
0079	860800000-E	876	RIP RAP CLASS II (2'-0" THICK)	155 TON		
0080	862200000-E	876	GEOTEXTILE FOR DRAINAGE	175 SY		
0081	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0082	876200000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	990 LF		
1213/Feb05/Q25099.65/D378628622000/E82			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C203082**

**County (ies):**   **Johnston**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General