

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16+20.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0199000000-E	SP	TEMPORARY SHORING	225 SF		
0007	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0008	0600000000-E	310	30" CS PIPE CULVERTS, 0.079" THICK	60 LF		
0009	0995000000-E	340	PIPE REMOVAL	51 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0011	1330000000-E	607	INCIDENTAL MILLING	200 SY		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	250 TON		
0013	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	200 TON		
0014	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	350 TON		
0015	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	42 TON		
0016	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0018	2354200000-N	840	FRAME WITH GRATE, STD 840.24	1 EA		
0019	3030000000-E	862	STEEL BM GUARDRAIL	37.5 LF		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0021	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0022	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-83SC)	1 EA		
0023	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0025	3319000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-83	3 EA		
0026	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	232 LF		
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	650 SY		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	156 SF		
0029	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	38 SF		
0030	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0031	4430000000-N	1130	DRUMS	64 EA		
0032	4445000000-E	1145	BARRICADES (TYPE III)	16 LF		
0033	4450000000-N	1150	FLAGGER	650 HR		
0034	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0035	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	2 EA		
0036	4485000000-E	1170	PORTABLE CONCRETE BARRIER	110 LF		
0037	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	60 LF		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	61 EA		
0039	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,200 LF		
0040	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,200 LF		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,330 LF		
0042	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	60 LF		
0043	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	15 EA		
0044	4960000000-N	SP	GENERIC TRAFFIC CONTROL ITEM PORTABLE TRAFFIC SIGNAL SYSTEM (PRE-TIMED)	1 EA		
0045	4960000000-N	SP	GENERIC TRAFFIC CONTROL ITEM PORTABLE TRAFFIC SIGNAL SYSTEM (ACTUATED)	1 EA		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF		
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	80 TON		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	20 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	175 TON		
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0051	6029000000-E	SP	SAFETY FENCE	500 LF		
0052	6030000000-E	1630	SILT EXCAVATION	90 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	300 SY		
0054	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	10 SY		
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6070000000-N	1639	SPECIAL STILLING BASINS	8 EA		
0057	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0058	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	10 EA		
0059	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0060	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+20.00-L-)	Lump Sum	L.S.	
0061	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	234 LF		
0062	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	48 LF		
0063	8113000000-N	411	SID INSPECTIONS	2 EA		
0064	8114000000-N	411	SPT TESTING	8 EA		
0065	8115000000-N	411	CSL TESTING	2 EA		
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+20.00-L-)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	53.2 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+20.00-L-)	Lump Sum	L.S.	
0069	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,800 LB		
0070	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,224 LB		
0071	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	264 TON		

County : Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	293 SY		
0073	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0074	8860000000-N	SP	GENERIC STRUCTURE ITEM 3'-0" X 1'-9" PS CONC CORED SLABS (TRANSPORT & INSTALL ONLY)	Lump Sum	L.S.	
0075	8860000000-N	SP	GENERIC STRUCTURE ITEM CONC BARRIER RAIL (TRANSPORT & INSTALL ONLY)	Lump Sum	L.S.	
1615/Feb01/Q37885.3/D347669840000/E75			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C203225**

**County (ies):**   **Yancey**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General