

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+03-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	10 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	20 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	1099500000-E	505	SHALLOW UNDERCUT	50 CY		
0014	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	95 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	95 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	130 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	225 TON		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	21 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	9 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0025	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0030	3030000000-E	862	STEEL BM GUARDRAIL	137.5 LF		
0031	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	87.5 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	4 EA		
0034	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0035	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0036	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,005 SY		
0037	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	129 LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0039	4102000000-N	904	SIGN ERECTION, TYPE E	7 EA		
0040	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8 EA		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	161 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	109 SF		
0043	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0044	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,156 LF		
0045	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	56 LF		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	950 LF		
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	285 TON		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	15 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	175 TON		
0050	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0054	6029000000-E	SP	SAFETY FENCE	300 LF		
0055	6030000000-E	1630	SILT EXCAVATION	75 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6037000000-E	SP	COIR FIBER MAT	450 SY		
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	175 LF		
0059	6070000000-N	1639	SPECIAL STILLING BASINS	6 EA		
0060	6071020000-E	SP	COIR FIBER WATTLE	45 LF		
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15 LB		
0062	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0063	6087000000-E	1660	MOWING	0.5 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0070	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0071	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+03.00-L-)	Lump Sum	L.S.	
0072	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+03.00-L-)	Lump Sum	L.S.	
0073	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	19.5 LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	34 LF		
0075	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	7.4 LF		
0076	8113000000-N	411	SID INSPECTIONS	3 EA		
0077	8114000000-N	411	SPT TESTING	6 EA		
0078	8115000000-N	411	CSL TESTING	1 EA		
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+03.00-L-)	Lump Sum	L.S.	
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	48 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+03.00-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	10,574 LB		
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,214 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	130 LF		
0085	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	240.5 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	249 TON		
0087	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	277 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	960 LF		

Contract No. **C203089**

County (ies): **Buncombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General