

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 1 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	3,050 CY		
0006	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	2 EA		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	210 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	1,300 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	6,200 SY		
0010	0255000000-E	SP	GENERIC GRADING ITEM HAULING & DISPOSAL OF PETROLEUM CONTAMINATED SOIL	10 TON		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	300 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	940 SY		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	400 LF		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	32 LF		
0015	0345000000-E	310	24" SIDE DRAIN PIPE	496 LF		
0016	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	380 LF		
0017	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	788 LF		
0018	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	594 LF		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 2 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	16 LF		
0020	0453000000-E	310	*** PIPE END SECTION (18")	6 EA		
0021	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	100 LF		
0022	0995000000-E	340	PIPE REMOVAL	1,049 LF		
0023	1099500000-E	505	SHALLOW UNDERCUT	1,300 CY		
0024	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	2,470 TON		
0025	1121000000-E	520	AGGREGATE BASE COURSE	4,381 TON		
0026	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0027	1330000000-E	607	INCIDENTAL MILLING	2,000 SY		
0028	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,770 TON		
0029	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,950 TON		
0030	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,780 TON		
0031	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,440 TON		
0032	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,290 TON		
0033	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,930 TON		
0034	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	875 TON		
0035	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0036	2000000000-N	806	RIGHT OF WAY MARKERS	59 EA		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 3 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0038	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0039	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0040	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0041	2077000000-E	815	6" OUTLET PIPE	6 LF		
0042	2209000000-E	838	ENDWALLS	2.5 CY		
0043	2253000000-E	840	PIPE COLLARS	1.55 CY		
0044	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	15 EA		
0045	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.5 LF		
0046	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	5 EA		
0047	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0048	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0049	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0050	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,950 LF		
0051	2556000000-E	846	SHOULDER BERM GUTTER	861 LF		
0052	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	240 LF		
0053	2739000000-E	852	GENERIC PAVING ITEM 6" MONOLITHIC CONCRETE ISLAND (SURFACE MOUNTED)	100 SY		
0054	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 4 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2	EA	
0056	3030000000-E	862	STEEL BM GUARDRAIL	1,262.5	LF	
0057	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75	LF	
0058	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2	EA	
0059	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10	EA	
0060	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2	EA	
0061	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1	EA	
0062	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0063	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5	EA	
0064	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	6	EA	
0065	3566000000-E	867	WOVEN WIRE FENCE RESET	610	LF	
0066	3569000000-E	867	BARBED WIRE FENCE RESET	205	LF	
0067	3578000000-N	SP	GENERIC FENCING ITEM RESET EXISTING GATE	1	EA	
0068	3578000000-N	SP	GENERIC FENCING ITEM STEEL PIPE GATE	1	EA	
0069	3649000000-E	876	RIP RAP, CLASS B	180	TON	
0070	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,270	SY	
0071	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	334.75	SF	

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 5 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	56.625 SF		
0073	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	900 LF		
0074	4102000000-N	904	SIGN ERECTION, TYPE E	60 EA		
0075	4108000000-N	904	SIGN ERECTION, TYPE F	9 EA		
0076	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	7 EA		
0077	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	40 EA		
0078	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	422 SF		
0079	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	608 SF		
0080	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	167 SF		
0081	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0082	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0083	4430000000-N	1130	DRUMS	300 EA		
0084	4435000000-N	1135	CONES	100 EA		
0085	4445000000-E	1145	BARRICADES (TYPE III)	176 LF		
0086	4450000000-N	1150	FLAGGER	2,400 HR		
0087	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0088	4480000000-N	1165	TMA	2 EA		
0089	4485000000-E	1170	PORTABLE CONCRETE BARRIER	546 LF		
0090	4510000000-N	SP	LAW ENFORCEMENT	32 HR		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 6 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	4516000000-N	1180	SKINNY DRUM	100 EA		
0092	4520000000-N	1266	TUBULAR MARKERS (FIXED)	34 EA		
0093	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	479 EA		
0094	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	21,360 LF		
0095	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	20,788 LF		
0096	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,350 LF		
0097	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	130 LF		
0098	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	456 LF		
0099	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	3 EA		
0100	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	41 EA		
0101	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,396 LF		
0102	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	25,004 LF		
0103	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,681 LF		
0104	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	217 LF		
0105	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	22 EA		
0106	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,350 LF		
0107	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	80 LF		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 7 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	5 EA		
0109	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	470 EA		
0110	5325600000-E	1510	6" WATER LINE	45 LF		
0111	5325800000-E	1510	8" WATER LINE	340 LF		
0112	5326200000-E	1510	12" WATER LINE	230 LF		
0113	5558000000-E	1515	12" VALVE	1 EA		
0114	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0115	6000000000-E	1605	TEMPORARY SILT FENCE	7,000 LF		
0116	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	700 TON		
0117	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	900 TON		
0118	6012000000-E	1610	SEDIMENT CONTROL STONE	700 TON		
0119	6015000000-E	1615	TEMPORARY MULCHING	40 ACR		
0120	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,250 LB		
0121	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	6 TON		
0122	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400 LF		
0123	6029000000-E	SP	SAFETY FENCE	100 LF		
0124	6030000000-E	1630	SILT EXCAVATION	2,800 CY		
0125	6036000000-E	1631	MATTING FOR EROSION CONTROL	16,500 SY		
0126	6037000000-E	SP	COIR FIBER MAT	100 SY		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 8 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	500 SY		
0128	6042000000-E	1632	1/4" HARDWARE CLOTH	900 LF		
0129	6071010000-E	SP	WATTLE	600 LF		
0130	6071020000-E	SP	POLYACRYLAMIDE (PAM)	200 LB		
0131	6071030000-E	1640	COIR FIBER BAFFLE	600 LF		
0132	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0133	6084000000-E	1660	SEEDING & MULCHING	25 ACR		
0134	6087000000-E	1660	MOWING	21 ACR		
0135	6090000000-E	1661	SEED FOR REPAIR SEEDING	350 LB		
0136	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
0137	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	825 LB		
0138	6108000000-E	1665	FERTILIZER TOPDRESSING	25 TON		
0139	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0140	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0141	7060000000-E	1705	SIGNAL CABLE	1,370 LF		
0142	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	5 EA		
0143	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	1 EA		
0144	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0145	7264000000-E	1710	MESSENGER CABLE (3/8")	620 LF		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 9 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	870 LF		
0147	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	9 EA		
0148	7360000000-N	1720	WOOD POLE	4 EA		
0149	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0150	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0151	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0152	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	970 LF		
0153	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	3,530 LF		
0154	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		
0155	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0156	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0157	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	6 EA		
0158	7948000000-N	1757	TRAFFIC SIGNAL REMOVAL	1 EA		
0180	0106000000-E	230	BORROW EXCAVATION	76,800 CY		

STRUCTURE ITEMS

0159	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	67.5 LF		
0160	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	79 LF		
0161	8112730000-N	450	PDA TESTING	2 EA		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 10 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0162	8113000000-N	411	SID INSPECTIONS	3 EA		
0163	8115000000-N	411	CSL TESTING	3 EA		
0164	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (25+41.22-L-)	Lump Sum	L.S.	
0165	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	12,011 SF		
0166	8161000000-E	420	GROOVING BRIDGE FLOORS	11,483 SF		
0167	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	243.1 CY		
0168	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25+41.22-L-)	Lump Sum	L.S.	
0169	8217000000-E	425	REINFORCING STEEL (BRIDGE)	38,837 LB		
0170	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	7,788 LB		
0171	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	1,378.5 LF		
0172	8364000000-E	450	HP12X53 STEEL PILES	595 LF		
0173	8391000000-N	450	STEEL PILE POINTS	14 EA		
0174	8475000000-E	460	TWO BAR METAL RAIL	694.6 LF		
0175	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-6")	694.6 LF		
0176	8531000000-E	462	4" SLOPE PROTECTION	26.4 SY		
0177	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0178	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL # 1	2,458 SF		

Mar 27, 2013 10:08 am

ITEMIZED PROPOSAL FOR CONTRACT NO. C203145

Page 11 of 11

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0179	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL # 2	2,151 SF		

1008/Mar27/Q332962.125/D791428120000/E180**Total Amount Of Bid For Entire Project :**

1-17-12
Z-140

Contract No. **C203145**

County (ies): **Cabarrus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General