

August 10, 2012



Project: R-2241A
 County: Person

PROJECT SPECIAL PROVISIONS
 Utility Construction

Specifications:

The proposed utility construction shall meet the applicable requirements of the NC Department of Transportation's "Standard Specifications for Roads and Structures" dated January 2006, and the following provisions.

Revise the 2006 Standard Specifications as follows:

Utility Owner's Contact Information:

Page 15-1; Sub-article 1500-2 Cooperation with the Utility Owner, paragraph 2, add the following sentences:

The utility owner is the City of Roxboro. The contact person is Mr. Andrew Oakley and he can be reached by phone at (336) 599-5658.

Page 15-6; Subarticle 1510-3 (B) Testing and Sterilization, change the allowable leakage formula to:

$$W=LD (P)^{1/2}/148,000$$

Page 15-6; Subarticle 1510-3 (B) Testing and Sterilization; seventh paragraph delete the words (concurrently or) in the following sentence.

Testing, cleaning and sterilization may be performed ~~concurrently or~~ consecutively.

PROJECT SPECIAL PROVISIONS

Utility

UTILITIES BY OTHERS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Progress Energy - Power (Transmission)
- B) Progress Energy - Power (Distribution)
- C) Piedmont EMC - Power (Distribution)
- D) CenturyLink - Telephone
- E) Charter Communications – CATV
- F) PSNC Energy - Gas

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A) Progress Energy - Power (Transmission)
 - 1) Progress Energy will remove its existing poles and overhead lines and install new poles and lines within the project limits at the locations shown on the Utilities by Others Plans prior to the date of availability.
 - 2) Contact person for Progress Energy (Transmission) is Mr. Jamie Loy at 919-546-6034.
- B) Progress Energy - Power (Distribution)
 - 1) Progress Energy will remove its existing poles and overhead lines and install new poles and lines within the project limits at the locations shown on the Utilities by Others Plans by July 31, 2013.
 - 2) Contact person for Progress Energy (Distribution) is Mr. Tom Edwards at 919-882-5046.
- C) Piedmont EMC - Power (Distribution)
 - 1) Piedmont EMC will remove its existing poles and overhead lines and install new poles and lines within the project limits at the locations shown on the Utilities by Others Plans by July 31, 2013.

2) Contact person for Piedmont EMC is Mr. Barry Bradsher at 336-503-2808.

D) CenturyLink - Telephone

- 1) CenturyLink will abandon its existing cables and install new underground conduits within the project limits at the locations shown on the Utilities by Others Plans by July 1, 2013.
- 2) Contact person for CenturyLink is Mr. Kevin Godwin at 910-366-2142.

E) Charter Communications - CATV

- 1) Charter Communications will remove its existing poles and cables and install new cables attached to Progress Energy's new poles within the project limits to the locations shown on the Utilities by Others Plans by August 30, 2013.
- 2) Contact person for Charter Communications is Mr. Rex Gray at 919-353-2712.

F) PSNC Energy - Gas

- 1) PSNC will abandon its existing facilities and relocate them to new locations within the project limits at the locations shown on the Utilities by Others Plans prior to date of availability except as noted below.
- 2) Contractor shall provide a two (2) week notice to PSNC Energy prior to the completion of rough grading from -L- station 30+58 to -Y9- station 15+40. PSNC Energy shall complete its work within two (2) weeks in this area.
- 3) Contractor shall provide a two (2) week notice to PSNC Energy when the work of installing the water and sewer lines crossing the stream at -L- station 13+40 will begin. Contractor and PSNC Energy shall coordinate installations of the lines in the stream to minimize impacts. PSNC Energy shall complete all their work associated with this line within two (2) weeks.
- 4) Contact person for PSNC Energy is Mrs. Nakima Bogan at 919-367-2720.