

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (12+76.00 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	30 SY		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	16 LF		
0011	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	56 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	352 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	231 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	187 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	90 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0026	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	460 SY		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	277 SF		
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0030	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,800 LF		
0032	6000000000-E	1605	TEMPORARY SILT FENCE	800 LF		
0033	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	35 TON		
0035	6012000000-E	1610	SEDIMENT CONTROL STONE	120 TON		
0036	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0037	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0039	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0040	6029000000-E	SP	SAFETY FENCE	300 LF		
0041	6030000000-E	1630	SILT EXCAVATION	100 CY		
0042	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,900 SY		
0043	6037000000-E	SP	COIR FIBER MAT	285 SY		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	560 LF		
0045	6071010000-E	SP	WATTLE	50 LF		
0046	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
0047	6071030000-E	1640	COIR FIBER BAFFLE	80 LF		
0048	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0049	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0050	6087000000-E	1660	MOWING	0.6 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0055	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0056	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+76.00-L-)	Lump Sum	L.S.	
0059	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+76.00-L-)	Lump Sum	L.S.	
0060	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38 CY		
0061	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+76.00-L-)	Lump Sum	L.S.	
0062	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,880 LB		
0063	8364000000-E	450	HP12X53 STEEL PILES	385 LF		
0064	8475000000-E	460	TWO BAR METAL RAIL	144.33 LF		
0065	8517000000-E	460	1'-**"X *****" CONCRETE PARA- PET (1'-2" X 3'-1 3/4")	160 LF		
0066	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	285 TON		
0067	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	315 SY		
0068	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0069	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	880 LF		

Contract No. **C203090**

County (ies): **Rockingham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General