

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	464 SY		
0008	0199000000-E	SP	TEMPORARY SHORING	547 SF		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	30 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	90 SY		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	52 LF		
0012	0345000000-E	310	24" SIDE DRAIN PIPE	96 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	128 LF		
0014	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 0.168")	64 LF		
0015	0995000000-E	340	PIPE REMOVAL	235 LF		
0016	1099500000-E	505	SHALLOW UNDERCUT	82 CY		
0017	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	155 TON		
0018	1121000000-E	520	AGGREGATE BASE COURSE	856 TON		
0019	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1275000000-E	600	PRIME COAT	477 GAL		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	300 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	220 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	560 TON		
0024	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	60 TON		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0028	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE	6 LF		
0030	2199000000-E	SP	SANDBAG HEADWALLS	262 SF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0032	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0034	2619000000-E	850	4" CONCRETE PAVED DITCH	110 SY		
0035	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	215 LF		
0036	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0037	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	80 LF		
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	1 EA		
0040	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77 SHOP CURVED)	1 EA		
0041	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0043	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	1 EA		
0044	3360000000-E	863	REMOVE EXISTING GUARDRAIL	390 LF		
0045	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	50 LF		
0046	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	77 LF		
0047	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (AT-1)	1 EA		
0048	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)	1 EA		
0049	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0050	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	215 LF		
0051	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	21 EA		
0052	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	17 EA		
0053	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0054	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	485 SY		
0055	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	51 LF		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0057	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8 EA		
0058	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	154 SF		
0059	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	149 SF		
0060	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0061	4430000000-N	1130	DRUMS	25 EA		
0062	4435000000-N	1135	CONES	25 EA		
0063	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0064	4450000000-N	1150	FLAGGER	1,920 HR		
0065	4480000000-N	1165	TMA	2 EA		
0066	4516000000-N	1180	SKINNY DRUM	37 EA		
0067	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	65 EA		
0068	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	490 LF		
0069	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,961 LF		
0070	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,400 LF		
0071	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,200 LF		
0072	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	6 EA		
0073	6000000000-E	1605	TEMPORARY SILT FENCE	8,030 LF		
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	295 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	215 TON		
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	285 TON		
0077	6015000000-E	1615	TEMPORARY MULCHING	1.25 ACR		
0078	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0080	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0081	6029000000-E	SP	SAFETY FENCE	300 LF		
0082	6030000000-E	1630	SILT EXCAVATION	380 CY		
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,500 SY		
0084	6037000000-E	SP	COIR FIBER MAT	100 SY		
0085	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150 SY		
0086	6042000000-E	1632	1/4" HARDWARE CLOTH	460 LF		
0087	6045000000-E	SP	*** TEMPORARY PIPE (18")	235 LF		
0088	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	240 SY		
0089	6070000000-N	1639	SPECIAL STILLING BASINS	6 EA		
0090	6071012000-E	SP	COIR FIBER WATTLE	660 LF		
0091	6071020000-E	SP	POLYACRYLAMIDE (PAM)	45 LB		
0092	6071030000-E	1640	COIR FIBER BAFFLE	100 LF		
0093	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0095	6087000000-E	1660	MOWING	0.75 ACR		
0096	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0097	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0098	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0099	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0100	6111000000-E	SP	IMPERVIOUS DIKE	200 LF		
0101	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0102	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0103	6126000000-E	SP	STREAMBANK REFORESTATION	0.17 ACR		

---

**CULVERT ITEMS**


---

0104	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+89.00-L-)	Lump Sum	L.S.	
0105	8126000000-N	414	CULVERT EXCAVATION, STA ***** (14+89.00-L-)	Lump Sum	L.S.	
0106	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	72 TON		
0107	8196000000-E	420	CLASS A CONCRETE (CULVERT)	126.9 CY		
0108	8245000000-E	425	REINFORCING STEEL (CULVERT)	17,252 LB		
0109	8590000000-E	876	RIP RAP, CLASS ** (I)	9 TON		

County : Transylvania

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>WALL ITEMS</b>						
0110	8802010000-E	SP	SOIL NAIL RETAINING WALLS	1,260 SF		
0111	8802015100-N	SP	SOIL NAIL VERIFICATION TESTS	1 EA		
0112	8802015110-N	SP	SOIL NAIL PROOF TESTS	5 EA		
0848/Mar04/Q59576.82/D448762652210/E112			<b>Total Amount Of Bid For Entire Project :</b>			

**Contract No.**     **C203092**

**County (ies):**   **Transylvania**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General