

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16+47.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	30 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	80 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	48 LF		
0011	0335300000-E	305	18" DRAINAGE PIPE	116 LF		
0012	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	64 LF		
0013	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")	4 EA		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	450 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	328 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	266 TON		
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	54 TON		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	17 EA		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	34 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	26 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	150 LF		
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0026	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3 LF		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0028	2556000000-E	846	SHOULDER BERM GUTTER	210 LF		
0029	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0033	3360000000-E	863	REMOVE EXISTING GUARDRAIL	625 LF		
0034	3635000000-E	876	RIP RAP, CLASS II	44 TON		
0035	3649000000-E	876	RIP RAP, CLASS B	165 TON		
0036	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,895 SY		
0037	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	69 LF		
0038	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
0040	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	366 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		
0042	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0043	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,318 LF		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,725 LF		
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	270 TON		
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65 TON		
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	355 TON		
0048	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0052	6029000000-E	SP	SAFETY FENCE	300 LF		
0053	6030000000-E	1630	SILT EXCAVATION	440 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,100 SY		
0055	6037000000-E	SP	COIR FIBER MAT	900 SY		
0056	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	425 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	265 LF		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6070000000-N	1639	SPECIAL STILLING BASINS	12	EA	
0059	6071012000-E	SP	COIR FIBER WATTLE	330	LF	
0060	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100	LB	
0061	6071030000-E	1640	COIR FIBER BAFFLE	210	LF	
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
0063	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	
0064	6087000000-E	1660	MOWING	0.6	ACR	
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
0069	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	
0071	6123000000-E	1670	REFORESTATION	0.1	ACR	

STRUCTURE ITEMS

0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+47.50-L-)	Lump Sum	L.S.	
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+47.50-L-)	Lump Sum	L.S.	

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	65.5 LF		
0075	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	44 LF		
0076	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	55.65 LF		
0077	8113000000-N	411	SID INSPECTIONS	1 EA		
0078	8115000000-N	411	CSL TESTING	1 EA		
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+47.50-L-)	Lump Sum	L.S.	
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	73.5 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+47.50-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	23,772 LB		
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,149 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	250 LF		
0085	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	330.5 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	720 TON		
0087	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	799 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,100 LF		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	715 LF		

1434/Apr01/Q52603.35/D416951652000/E90

Total Amount Of Bid For Entire Project :

Contract No. **C203149**

County (ies): **Granville**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General