

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM PEDESTRIAN SAFETY RAIL	270 LF		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (51+40.50)	Lump Sum	L.S.	
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (71+24.00)	Lump Sum	L.S.	
0006	0043000000-N	226	GRADING	Lump Sum	L.S.	
0007	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0008	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	70 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0011	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	598 SF		
0013	0223000000-E	275	ROCK PLATING	500 SY		
0014	0225000000-E	SP	REINFORCED SOIL SLOPES	500 SY		
0015	0241000000-E	SP	GENERIC GRADING ITEM SOIL NAIL SLOPE STABILIZATION	2,500 SY		
0016	0262000000-N	SP	GENERIC GRADING ITEM SOIL NAIL PROOF TESTS	12 EA		
0017	0262000000-N	SP	GENERIC GRADING ITEM SOIL NAIL VERIFICATION TESTS	3 EA		
0018	0262000000-N	SP	GENERIC GRADING ITEM SUPPLEMENTAL SOIL NAILS	15 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	800 TON		
0020	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	2,520 SY		
0021	0335200000-E	305	15" DRAINAGE PIPE	1,612 LF		
0022	0335300000-E	305	18" DRAINAGE PIPE	892 LF		
0023	0335400000-E	305	24" DRAINAGE PIPE	348 LF		
0024	0335500000-E	305	30" DRAINAGE PIPE	408 LF		
0025	0335600000-E	305	36" DRAINAGE PIPE	72 LF		
0026	0335850000-E	305	***" DRAINAGE PIPE ELBOWS (24")	1 EA		
0027	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	272 LF		
0028	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	428 LF		
0029	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	504 LF		
0030	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	48 LF		
0031	0576000000-E	310	***" CS PIPE CULVERTS, *****" THICK (36", 0.079")	92 LF		
0032	0576000000-E	310	***" CS PIPE CULVERTS, *****" THICK (42", 0.109")	60 LF		
0033	0576000000-E	310	***" CS PIPE CULVERTS, *****" THICK (48", 0.109")	68 LF		
0034	0576000000-E	310	***" CS PIPE CULVERTS, *****" THICK (54", 0.138")	140 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (60", 0.138")	120 LF		
0036	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	352 LF		
0037	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	404 LF		
0038	0600000000-E	310	30" CS PIPE CULVERTS, 0.079" THICK	80 LF		
0039	0995000000-E	340	PIPE REMOVAL	2,929 LF		
0040	1099500000-E	505	SHALLOW UNDERCUT	150 CY		
0041	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0042	1121000000-E	520	AGGREGATE BASE COURSE	2,952 TON		
0043	1220000000-E	545	INCIDENTAL STONE BASE	3,100 TON		
0044	1275000000-E	600	PRIME COAT	26 GAL		
0045	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***** DEPTH (2")	800 SY		
0046	1330000000-E	607	INCIDENTAL MILLING	800 SY		
0047	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	9,800 TON		
0048	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	400 TON		
0049	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	14,400 TON		
0050	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	350 TON		
0051	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	8,700 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	210 TON		
0053	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,695 TON		
0054	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		
0055	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	30,500 LF		
0056	2000000000-N	806	RIGHT OF WAY MARKERS	156 EA		
0057	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		
0058	2033000000-E	815	SUBDRAIN FINE AGGREGATE	50.4 CY		
0059	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0060	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0061	2077000000-E	815	6" OUTLET PIPE	6 LF		
0062	2209000000-E	838	ENDWALLS	14.9 CY		
0063	2220000000-E	838	REINFORCED ENDWALLS	8.9 CY		
0064	2275000000-E	SP	FLOWABLE FILL	43.39 CY		
0065	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	29 EA		
0066	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.36 LF		
0067	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	5 EA		
0068	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7 EA		
0069	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0070	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	6 EA		
0072	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	3 EA		
0073	2486000000-E	SP	GENERIC DRAINAGE ITEM SANDBAG HEADWALLS	335 SF		
0074	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	2,030 LF		
0075	2556000000-E	846	SHOULDER BERM GUTTER	200 LF		
0076	2591000000-E	848	4" CONCRETE SIDEWALK	10 SY		
0077	2612000000-E	848	6" CONCRETE DRIVEWAY	470 SY		
0078	2619000000-E	850	4" CONCRETE PAVED DITCH	60 SY		
0079	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0080	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	12 EA		
0081	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	7 EA		
0082	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	7 EA		
0083	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0084	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (AT-1)	1 EA		
0085	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0086	3420000000-E	SP	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL WITH 8' POSTS	1,275 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	3420000000-E	SP	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL, SHOP CURVED WITH 8' POSTS	425 LF		
0088	3420000000-E	SP	GENERIC GUARDRAIL ITEM TEMPORARY STEEL BM GUARDRAIL WITH 8' POSTS	225 LF		
0089	3420000000-E	SP	GENERIC GUARDRAIL ITEM TEMPORARY STEEL BM GUARDRAIL WITH 8' POSTS (SHOP CURVED)	62.5 LF		
0090	3435000000-N	SP	GENERIC GUARDRAIL ITEM ADDITIONAL GUARDRAIL POSTS (8')	20 EA		
0091	3436000000-N	862	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE III SHOP CURVED	1 EA		
0092	3628000000-E	876	RIP RAP, CLASS I	126 TON		
0093	3635000000-E	876	RIP RAP, CLASS II	73 TON		
0094	3642000000-E	876	RIP RAP, CLASS A	532 TON		
0095	3649000000-E	876	RIP RAP, CLASS B	1,026 TON		
0096	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	7,693 SY		
0097	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,266 LF		
0098	4102000000-N	904	SIGN ERECTION, TYPE E	70 EA		
0099	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0100	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	4 EA		
0101	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	63 EA		
0102	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	288 SF		
0103	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	946 SF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	260	SF	
0105	4415000000-N	1115	FLASHING ARROW BOARD	2	EA	
0106	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2	EA	
0107	4430000000-N	1130	DRUMS	872	EA	
0108	4435000000-N	1135	CONES	60	EA	
0109	4445000000-E	1145	BARRICADES (TYPE III)	160	LF	
0110	4450000000-N	1150	FLAGGER	10,800	HR	
0111	4480000000-N	1165	TMA	2	EA	
0112	4516000000-N	1180	SKINNY DRUM	900	EA	
0113	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	400	EA	
0114	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	29,387	LF	
0115	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	36,534	LF	
0116	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	419	LF	
0117	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	275	LF	
0118	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	291	LF	
0119	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	24	EA	
0120	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	68,008	LF	
0121	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	371	LF	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	263 LF		
0123	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	24 EA		
0124	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,400 LF		
0125	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	493 EA		
0126	5319000000-E	1505	CLASS B CONCRETE FOR ENCASING UTILITY LINES	1 CY		
0127	5325600000-E	1510	6" WATER LINE	100 LF		
0128	5326200000-E	1510	12" WATER LINE	938 LF		
0129	5326600000-E	1510	16" WATER LINE	178 LF		
0130	5546000000-E	1515	8" VALVE	3 EA		
0131	5558000000-E	1515	12" VALVE	3 EA		
0132	5558600000-E	1515	16" VALVE	3 EA		
0133	5648000000-N	1515	RELOCATE WATER METER	7 EA		
0134	5672000000-N	1515	RELOCATE FIRE HYDRANT	3 EA		
0135	5709200000-E	1520	4" FORCE MAIN SEWER	415 LF		
0136	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2 EA		
0137	5798000000-E	1530	ABANDON *** UTILITY PIPE (4")	436 LF		
0138	5800000000-E	1530	ABANDON 6" UTILITY PIPE	100 LF		
0139	5804000000-E	1530	ABANDON 12" UTILITY PIPE	913 LF		
0140	5810000000-E	1530	ABANDON 16" UTILITY PIPE	160 LF		
0141	5836400000-E	1540	36" ENCASEMENT PIPE	84 LF		



County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	6000000000-E	1605	TEMPORARY SILT FENCE	21,710 LF		
0143	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,800 TON		
0144	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	3,150 TON		
0145	6012000000-E	1610	SEDIMENT CONTROL STONE	1,010 TON		
0146	6015000000-E	1615	TEMPORARY MULCHING	18 ACR		
0147	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	450 LB		
0148	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0149	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0150	6029000000-E	SP	SAFETY FENCE	900 LF		
0151	6030000000-E	1630	SILT EXCAVATION	4,510 CY		
0152	6036000000-E	1631	MATTING FOR EROSION CONTROL	9,500 SY		
0153	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	500 SY		
0154	6042000000-E	1632	1/4" HARDWARE CLOTH	440 LF		
0155	6071010000-E	SP	WATTLE	60 LF		
0156	6071020000-E	SP	POLYACRYLAMIDE (PAM)	85 LB		
0157	6071030000-E	1640	COIR FIBER BAFFLE	180 LF		
0158	6084000000-E	1660	SEEDING & MULCHING	12 ACR		
0159	6087000000-E	1660	MOWING	12 ACR		
0160	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0161	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0162	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	300 LB		
0163	6108000000-E	1665	FERTILIZER TOPDRESSING	8.5 TON		
0164	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0165	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	100 EA		
0166	7048500000-E	1705	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)	4 EA		
0167	7060000000-E	1705	SIGNAL CABLE	2,520 LF		
0168	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	20 EA		
0169	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2 EA		
0170	7264000000-E	1710	MESSENGER CABLE (3/8")	1,250 LF		
0171	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	100 LF		
0172	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,530 LF		
0173	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	15 EA		
0174	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,000 LF		
0175	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	5,720 LF		
0176	7576000000-N	SP	METAL STRAIN SIGNAL POLE	12 EA		
0177	7613000000-N	SP	SOIL TEST	12 EA		
0178	7614100000-E	SP	DRILLED PIER FOUNDATION	180 CY		
0179	7636000000-N	1745	SIGN FOR SIGNALS	4 EA		
0180	7642200000-N	1743	TYPE II PEDESTAL WITH FOUNDATION	1 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0181	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0182	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0183	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	15 EA		
0184	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
<b>WALL ITEMS</b>						
0185	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	1,255 SF		
<b>STRUCTURE ITEMS</b>						
0186	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (51+40.50-L-)	Lump Sum	L.S.	
0187	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (71+24.00-L-)	Lump Sum	L.S.	
0188	8096000000-E	450	PILE EXCAVATION IN SOIL	69 LF		
0189	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	71 LF		
0190	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (51+40.50-L-)	Lump Sum	L.S.	
0191	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (71+24.00-L-)	Lump Sum	L.S.	
0192	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	112 CY		
0193	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (51+40.50-L-)	Lump Sum	L.S.	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0194	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (71+24.00-L-)	Lump Sum	L.S.	
0195	8217000000-E	425	REINFORCING STEEL (BRIDGE)	16,656 LB		
0196	8364000000-E	450	HP12X53 STEEL PILES	980 LF		
0197	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	880 LF		
0198	8391000000-N	450	STEEL PILE POINTS	44 EA		
0199	8475000000-E	460	TWO BAR METAL RAIL	288.1 LF		
0200	8517000000-E	460	1'-***"X *****" CONCRETE PARA- PET (1'-2" X 2'-9")	210.6 LF		
0201	8517000000-E	460	1'-***"X *****" CONCRETE PARA- PET (1'-2" X 2'-10 1/2")	110 LF		
0202	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	468 TON		
0203	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	520 SY		
0204	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0205	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,080 LF		

0922/Apr09/Q346998.85/D832267654000/E205

Total Amount Of Bid For Entire Project :

**Contract No.**     **C203138**

**County (ies):**   **Henderson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General