

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	10,800 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	294,200 CY		
0007	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	2 EA		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,080 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	12,300 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	8,000 SY		
0011	0223000000-E	275	ROCK PLATING	1,320 SY		
0012	0255000000-E	SP	GENERIC GRADING ITEM HAULING AND DISPOSAL OF PETRO- LEUM CONTAMINATED SOIL	180 TON		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	1,526 TON		
0014	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	1,440 SY		
0015	0335200000-E	305	15" DRAINAGE PIPE	3,098 LF		
0016	0335300000-E	305	18" DRAINAGE PIPE	116 LF		
0017	0335400000-E	305	24" DRAINAGE PIPE	68 LF		
0018	0335500000-E	305	30" DRAINAGE PIPE	32 LF		
0019	0335600000-E	305	36" DRAINAGE PIPE	220 LF		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	24 LF		
0021	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	84 LF		
0022	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	172 LF		
0023	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	52 LF		
0024	0986000000-E	SP	GENERIC PIPE ITEM 18" WELDED STEEL PIPE, 0.5" THICK, GRADE B (OPEN CUT)	34 LF		
0025	0986000000-E	SP	GENERIC PIPE ITEM 36" WELDED STEEL PIPE, 0.5" THICK, GRADE B IN SOIL	42 LF		
0026	0986000000-E	SP	GENERIC PIPE ITEM 36" WELDED STEEL PIPE, 0.5" THICK, GRADE B NOT IN SOIL	41 LF		
0027	0986000000-E	SP	GENERIC PIPE ITEM 42" WELDED STEEL PIPE, 0.625" THICK, GRADE B (OPEN CUT)	83 LF		
0028	0986000000-E	SP	GENERIC PIPE ITEM 42" WELDED STEEL PIPE, 0.625" THICK, GRADE B IN SOIL	50 LF		
0029	0986000000-E	SP	GENERIC PIPE ITEM 42" WELDED STEEL PIPE, 0.625" THICK, GRADE B NOT IN SOIL	50 LF		
0030	0986000000-E	SP	GENERIC PIPE ITEM 54" WELDED STEEL PIPE 0.75" THICK, GRADE B (OPEN CUT)	286 LF		
0031	0986000000-E	SP	GENERIC PIPE ITEM 54" WELDED STEEL PIPE, 0.75" THICK, GRADE B IN SOIL	42 LF		
0032	0986000000-E	SP	GENERIC PIPE ITEM 54" WELDED STEEL PIPE, 0.75" THICK, GRADE B NOT IN SOIL	42 LF		
0033	0995000000-E	340	PIPE REMOVAL	285 LF		
0034	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	1,000 SY		

May 02, 2013 2:16 pm  
 County : Mecklenburg

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	1066000000-E	501	LIME FOR LIME TREATED SOIL	100 TON		
0036	1099500000-E	505	SHALLOW UNDERCUT	1,500 CY		
0037	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	3,000 TON		
0038	1110000000-E	510	STABILIZER AGGREGATE	100 TON		
0039	1121000000-E	520	AGGREGATE BASE COURSE	1,282 TON		
0040	1176000000-E	542	SOIL CEMENT BASE	1,000 SY		
0041	1187000000-E	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	100 TON		
0042	1198000000-E	542	AGGREGATE FOR SOIL CEMENT BASE	100 TON		
0043	1209000000-E	543	ASPHALT CURING SEAL	500 GAL		
0044	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0045	1275000000-E	600	PRIME COAT	1,215 GAL		
0046	1330000000-E	607	INCIDENTAL MILLING	1,230 SY		
0047	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,000 TON		
0048	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,930 TON		
0049	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,220 TON		
0050	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	3,190 TON		
0051	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,830 TON		
0052	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,340 TON		
0053	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	925 TON		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	85 TON		
0055	2000000000-N	806	RIGHT OF WAY MARKERS	45 EA		
0056	2070000000-N	815	SUBDRAIN PIPE OUTLET	6 EA		
0057	2077000000-E	815	6" OUTLET PIPE	228 LF		
0058	2143000000-E	818	BLOTTING SAND	100 TON		
0059	2209000000-E	838	ENDWALLS	24.2 CY		
0060	2220000000-E	838	REINFORCED ENDWALLS	12.1 CY		
0061	2275000000-E	SP	FLOWABLE FILL	145 CY		
0062	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	39 EA		
0063	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	4 CY		
0064	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	29.2 LF		
0065	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	5 EA		
0066	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0067	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0068	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	15 EA		
0069	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	13 EA		
0070	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0071	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	2484000000-E	SP	GENERIC DRAINAGE ITEM SUBSURFACE DRAIN	2,470 LF		
0073	2535000000-E	846	***X *** CONCRETE CURB (9" X 12")	240 LF		
0074	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	10,340 LF		
0075	2591000000-E	848	4" CONCRETE SIDEWALK	2,490 SY		
0076	2605000000-N	848	CONCRETE CURB RAMP	25 EA		
0077	2612000000-E	848	6" CONCRETE DRIVEWAY	970 SY		
0078	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	60 SY		
0079	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0080	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0081	3030000000-E	862	STEEL BM GUARDRAIL	5,162.5 LF		
0082	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	250 LF		
0083	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0084	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0085	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0086	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0087	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0088	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,087.5 LF		
0089	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	62.5 LF		

May 02, 2013 2:16 pm  
 County : Mecklenburg

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (AT-1)	1 EA		
0091	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0092	3420000000-E	SP	GENERIC GUARDRAIL ITEM BLACK VINYL COATED GLARE SCREEN (GUARDRAIL MOUNTED)	1,560 LF		
0093	3435000000-N	SP	GENERIC GUARDRAIL ITEM EXTRA LENGTH GUARDRAIL POSTS, 8'	160 EA		
0094	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	530 LF		
0095	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	40 EA		
0096	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	20 EA		
0097	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (60")	1,350 LF		
0098	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (60")	115 EA		
0099	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (60")	5 EA		
0100	3578000000-N	SP	GENERIC FENCING ITEM RIGHT OF WAY GATE	1 EA		
0101	3628000000-E	876	RIP RAP, CLASS I	30 TON		
0102	3649000000-E	876	RIP RAP, CLASS B	1,410 TON		
0103	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	4,985 SY		
0104	3885000000-E	SP	GENERIC TRACKWORK ITEM SUB-BALLAST	21,500 TON		
0105	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	252 SF		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	577 LF		
0107	4102000000-N	904	SIGN ERECTION, TYPE E	45 EA		
0108	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0109	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	26 EA		
0110	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2 EA		
0111	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	3 EA		
0112	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	958 SF		
0113	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0114	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	155 SF		
0115	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	1 EA		
0116	4430000000-N	1130	DRUMS	54 EA		
0117	4435000000-N	1135	CONES	83 EA		
0118	4445000000-E	1145	BARRICADES (TYPE III)	164 LF		
0119	4455000000-N	1150	FLAGGER	600 DAY		
0120	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0121	4485000000-E	1170	PORTABLE CONCRETE BARRIER	770 LF		
0122	4516000000-N	1180	SKINNY DRUM	83 EA		
0123	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	240 EA		
0124	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	825 LF		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	12,589	LF	
0126	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	2,582	LF	
0127	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	706	LF	
0128	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	81	LF	
0129	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	784	LF	
0130	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	277	LF	
0131	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	264	LF	
0132	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	65	EA	
0133	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	825	LF	
0134	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	660	LF	
0135	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	155	LF	
0136	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (III)	94	LF	
0137	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (IV)	94	LF	
0138	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (III)	8	EA	
0139	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** (IV)	8	EA	



May 02, 2013 2:16 pm  
 County : Mecklenburg

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (III)	3	EA	
0141	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	2	EA	
0142	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	68,481	LF	
0143	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,816	LF	
0144	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,136	LF	
0145	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	128	EA	
0146	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	227	EA	
0147	5325600000-E	1510	6" WATER LINE	47	LF	
0148	5325800000-E	1510	8" WATER LINE	1,134	LF	
0149	5326200000-E	1510	12" WATER LINE	2,650	LF	
0150	5326600000-E	1510	16" WATER LINE	312	LF	
0151	5540000000-E	1515	6" VALVE	1	EA	
0152	5546000000-E	1515	8" VALVE	6	EA	
0153	5558000000-E	1515	12" VALVE	5	EA	
0154	5558600000-E	1515	16" VALVE	3	EA	
0155	5589100000-E	1515	1" AIR RELEASE VALVE	2	EA	
0156	5606000000-E	1515	2" BLOW OFF	1	EA	
0157	5648000000-N	1515	RELOCATE WATER METER	8	EA	
0158	5649000000-N	1515	RECONNECT WATER METER	1	EA	

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0159	5666000000-E	1515	FIRE HYDRANT	3 EA		
0160	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
0161	5678400000-E	1515	6" LINE STOP	2 EA		
0162	5678600000-E	1515	8" LINE STOP	8 EA		
0163	5679000000-E	1515	12" LINE STOP	3 EA		
0164	5679200000-E	1515	16" LINE STOP	3 EA		
0165	5691300000-E	1520	8" SANITARY GRAVITY SEWER	884 LF		
0166	5775000000-E	1525	4' DIA UTILITY MANHOLE	3 EA		
0167	5776000000-E	1525	5' DIA UTILITY MANHOLE	2 EA		
0168	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	7 LF		
0169	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	29 LF		
0170	5800000000-E	1530	ABANDON 6" UTILITY PIPE	54 LF		
0171	5801000000-E	1530	ABANDON 8" UTILITY PIPE	2,995 LF		
0172	5804000000-E	1530	ABANDON 12" UTILITY PIPE	2,784 LF		
0173	5810000000-E	1530	ABANDON 16" UTILITY PIPE	110 LF		
0174	5815500000-N	1530	REMOVE FIRE HYDRANT	3 EA		
0175	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
0176	5828000000-N	1530	REMOVE UTILITY MANHOLE	5 EA		
0177	5835800000-E	1540	18" ENCASEMENT PIPE	12 LF		
0178	5836000000-E	1540	24" ENCASEMENT PIPE	188 LF		
0179	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	94 LF		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0180	5872210000-E	1550	TRENCHLESS INSTALLATION OF 24" NOT IN SOIL	94 LF		
0181	6000000000-E	1605	TEMPORARY SILT FENCE	26,735 LF		
0182	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	900 TON		
0183	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5,035 TON		
0184	6012000000-E	1610	SEDIMENT CONTROL STONE	2,800 TON		
0185	6015000000-E	1615	TEMPORARY MULCHING	40.5 ACR		
0186	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,200 LB		
0187	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6 TON		
0188	6024000000-E	1622	TEMPORARY SLOPE DRAINS	4,155 LF		
0189	6029000000-E	SP	SAFETY FENCE	200 LF		
0190	6030000000-E	1630	SILT EXCAVATION	7,000 CY		
0191	6036000000-E	1631	MATTING FOR EROSION CONTROL	60,430 SY		
0192	6037000000-E	SP	COIR FIBER MAT	425 SY		
0193	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	315 SY		
0194	6042000000-E	1632	1/4" HARDWARE CLOTH	1,500 LF		
0195	6045000000-E	SP	*** TEMPORARY PIPE (15")	35 LF		
0196	6071012000-E	SP	COIR FIBER WATTLE	9,405 LF		
0197	6071020000-E	SP	POLYACRYLAMIDE (PAM)	970 LB		
0198	6071030000-E	1640	COIR FIBER BAFFLE	2,930 LF		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0199	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0200	6084000000-E	1660	SEEDING & MULCHING	57 ACR		
0201	6087000000-E	1660	MOWING	45 ACR		
0202	6090000000-E	1661	SEED FOR REPAIR SEEDING	450 LB		
0203	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	3 TON		
0204	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,400 LB		
0205	6108000000-E	1665	FERTILIZER TOPDRESSING	41.5 TON		
0206	6111000000-E	SP	IMPERVIOUS DIKE	30 LF		
0207	6114500000-N	1667	SPECIALIZED HAND MOWING	20 MHR		
0208	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	100 EA		
0209	6132000000-N	SP	GENERIC EROSION CONTROL ITEM SUPPLEMENTAL RESPONSE FOR ERO- SION CONTROL	10 EA		
<b>WALL ITEMS</b>						
0210	8847000000-E	SP	GENERIC RETAINING WALL ITEM CONTRACTOR DESIGN WALL	14,840 SF		
0211	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 1	5,000 SF		
<b>STRUCTURE ITEMS</b>						
0212	8105560000-E	411	4'-0" DIA DRILLED PIERS IN SO IL	96.5 LF		

May 02, 2013 2:16 pm  
County : Mecklenburg

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0213	8105660000-E	411	4'-0" DIA DRILLED PIERS NOT IN SOIL	43 LF		
0214	8113000000-N	411	SID INSPECTIONS	1 EA		
0215	8114000000-N	411	SPT TESTING	1 EA		
0216	8115000000-N	411	CSL TESTING	1 EA		
0217	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	10,821 SF		
0218	8161000000-E	420	GROOVING BRIDGE FLOORS	9,605 SF		
0219	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	153.1 CY		
0220	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11+76.26-L-)	Lump Sum	L.S.	
0221	8217000000-E	425	REINFORCING STEEL (BRIDGE)	45,559 LB		
0222	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,508 LB		
0223	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,769 LB		
0224	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	1,136.33 LF		
0225	8364000000-E	450	HP12X53 STEEL PILES	1,165 LF		
0226	8475000000-E	460	TWO BAR METAL RAIL	311.67 LF		
0227	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 3'-4")	326.67 LF		
0228	8524000000-E	SP	*** CHAIN LINK FENCE (72")	323 LF		
0229	8531000000-E	462	4" SLOPE PROTECTION	345 SY		

May 02, 2013 2:16 pm

ITEMIZED PROPOSAL FOR CONTRACT NO. C203148

County : Mecklenburg

---

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

---

0230	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
------	--------------	-----	----------------------	----------	------	--

---

---

1416/May02/Q752618.27/D922509942000/E230

Total Amount Of Bid For Entire Project :

---

1-17-12  
Z-140

**Contract No.**     **C203148**

**County (ies):**    **Mecklenburg**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)