

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+05.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	11,800 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	350 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	350 SY		
0011	0223000000-E	275	ROCK PLATING	850 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	180 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	340 SY		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	236 LF		
0015	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	4 EA		
0016	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	112 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	90 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	12 TON		
0019	1330000000-E	607	INCIDENTAL MILLING	250 SY		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	580 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	300 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	610 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	80 TON		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0025	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100 SY		
0026	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	16.8 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0028	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	1,585 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	1,650 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0037	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,820 LF		
0038	3649000000-E	876	RIP RAP, CLASS B	6 TON		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	475 SY		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	30 LF		
0041	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0042	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	156 SF		
0046	4435000000-N	1135	CONES	40 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
0048	4450000000-N	1150	FLAGGER	160 HR		
0049	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,300 LF		
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,300 LF		
0051	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	900 LF		
0052	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	17 EA		
0053	5325800000-E	1510	8" WATER LINE	1,123 LF		
0054	5546000000-E	1515	8" VALVE	2 EA		
0055	5709300000-E	1520	6" FORCE MAIN SEWER	1,202 LF		
0056	5709400000-E	1520	8" FORCE MAIN SEWER	1,178 LF		
0057	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,178 LF		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	5801000000-E	1530	ABANDON 8" UTILITY PIPE	2,257 LF		
0059	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	878 LF		
0060	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	98 LF		
0061	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	1,854 LF		
0062	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	206 LF		
0063	5882000000-N	SP	GENERIC UTILITY ITEM 6" INSERT GATE VALVE	2 EA		
0064	5882000000-N	SP	GENERIC UTILITY ITEM 8" INSERT GATE VALVE	2 EA		
0065	6000000000-E	1605	TEMPORARY SILT FENCE	3,800 LF		
0066	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0067	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	245 TON		
0068	6012000000-E	1610	SEDIMENT CONTROL STONE	180 TON		
0069	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0070	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0071	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0072	6024000000-E	1622	TEMPORARY SLOPE DRAINS	750 LF		
0073	6029000000-E	SP	SAFETY FENCE	2,000 LF		
0074	6030000000-E	1630	SILT EXCAVATION	360 CY		
0075	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,000 SY		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6037000000-E	SP	COIR FIBER MAT	600	SY	
0077	6042000000-E	1632	1/4" HARDWARE CLOTH	375	LF	
0078	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	425	SY	
0079	6071012000-E	SP	COIR FIBER WATTLE	350	LF	
0080	6071020000-E	SP	POLYACRYLAMIDE (PAM)	55	LB	
0081	6071030000-E	1640	COIR FIBER BAFFLE	80	LF	
0082	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0083	6087000000-E	1660	MOWING	2.5	ACR	
0084	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0085	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0086	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125	LB	
0087	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75	TON	
0088	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0089	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	

STRUCTURE ITEMS

0090	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+05.00-L-)	Lump Sum	L.S.	
0091	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+05.00-L-)	Lump Sum	L.S.	
0092	8112730000-N	450	PDA TESTING	1	EA	

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+05.00-L-)	Lump Sum	L.S.	
0094	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,379 SF		
0095	8161000000-E	420	GROOVING BRIDGE FLOORS	7,766 SF		
0096	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	78.8 CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+05.00-L-)	Lump Sum	L.S.	
0098	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,552 LB		
0099	8259000000-E	430	36" PRESTRESSED CONCRETE GIRDERS	922.08 LF		
0100	8333000000-E	450	16" PRESTRESSED CONCRETE PILES	1,015 LF		
0101	8336000000-E	450	20" PRESTRESSED CONCRETE PILES	840 LF		
0102	8393000000-N	450	PILE REDRIVES	14 EA		
0103	8503000000-E	460	CONCRETE BARRIER RAIL	372.67 LF		
0104	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	168 TON		
0105	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	187 SY		
0106	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

1122/May03/Q89938.0/D474795312000/E106

Total Amount Of Bid For Entire Project :

Contract No. **C203025**

County (ies): **Bertie**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General