

CONTRACT: 49010.1.SR03T1B ID: C-4901AD

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	49010.1.SR03T1B	1	10
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
C-4901 AD	N/A		

CONTENTS

TITLE	SHEET
LEGEND	2
ROADWAY TITLE SHEET	2A
GEOTECHNICAL REPORT	3A-3B

LINE	STATION	PLAN	PROFILE	X-SECT
-M1-	7591+00 to 7598+90	4	4	5-8
-M1-	7663+50 to 7679+00	9-10	9-10	n/a

ROADWAY SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. C-4901 AD F.A. PROJ. N/A
 COUNTY DAVIDSON
 PROJECT DESCRIPTION CP "BOWERS" (MP 309.8) TO CP "LAKE" (MP 314.0) ON THE NCRR /NSRR MAINLINE (Revised)

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF PREPARING THE SCOPE OF WORK TO BE INCLUDED IN THE REQUEST FOR PROPOSAL. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS, FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.


SOIL AND ROCK BOUNDARIES WITHIN A BOREHOLE ARE BASED ON GEOTECHNICAL INTERPRETATION UNLESS ENCOUNTERED IN A SAMPLE. INTERPRETED BOUNDARIES MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN SAMPLED STRATA. AND BOREHOLE INFORMATION MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS, INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, OR THE OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IS IT CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.


INVENTORY



PERSONNEL

B. WORLEY, PG
B. SMITH
L. GONZALEZ-CASTILLO
C. HUSKETH

DRAWN BY B. WORLEY, PG
 DRAWN BY M. BRANDON
 INVESTIGATED BY B. WORLEY, PG
 CHECKED BY D. DEWEY, PE
 SUBMITTED BY Summit Design and Engineering
 DATE JANUARY, 2013



Bradley D. Worley

EARTHWORK BALANCE SHEET

Volumes in Cubic Yards

PROJECT TIP # C-4901A

COUNTY Davidson

DATE 5/13/2013

SHEET 1 OF 1 SHEETS

LINE	STATION	STATION	TOTAL				TOTAL				BORROW	SUITABLE			
			EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT EXCAV.	UNSUIT. EXCAV.	SUITABLE EXCAV.	EMB.	ROCK EMB.	EARTH EMB.		EMBANK. 20%	WASTE	UNSUIT. WASTE	TOTAL WASTE
-M1-	7572+00.00	7602+00.00	27,985		1,071		27,985	15,577		15,577	18,692	0	9,293	1,071	10,364
		SUBTOTAL	27,985		1,071		27,985	15,577		15,577	18,692	0	9,293	1,071	10,364
-M1-	7602+00.00	7632+00.00	57,017		0		57,017	13,784		13,784	16,541	0	40,476	0	40,476
		SUBTOTAL	57,017		0		57,017	13,784		13,784	16,541	0	40,476	0	40,476
-M1-	7632+00.00	7661+66.40	21,271		0		21,271	12,200		12,200	14,640	0	6,631	0	6,631
		SUBTOTAL	21,271		0		21,271	12,200		12,200	14,640	0	6,631	0	6,631
-M1-	7663+16.37	7692+00.00	25,747		0		25,747	22,030		22,030	26,436	689	0	0	0
		SUBTOTAL	25,747		0		25,747	22,030		22,030	26,436	689	0	0	0
-M1-	7692+00.00	7722+00.00	4,902		0		4,902	2,038		2,038	2,446	0	2,456	0	2,456
		SUBTOTAL	4,902		0		4,902	2,038		2,038	2,446	0	2,456	0	2,456
-M1-	7722+00.00	7740+37.14	16,001		0		16,001	662		662	794	0	15,207	0	15,207
		SUBTOTAL	16,001		0		16,001	662		662	794	0	15,207	0	15,207
-M1-	7741+55.53	7760+06.51	14,871		0		14,871	6,227		6,227	7,472	0	7,399	0	7,399
		SUBTOTAL	14,871		0		14,871	6,227		6,227	7,472	0	7,399	0	7,399
-M1-	7762+21.65	7792+00.00	24,130		0		24,130	18,617		18,617	22,340	0	1,790	0	1,790
		SUBTOTAL	24,130		0		24,130	18,617		18,617	22,340	0	1,790	0	1,790
-M1-	7792+00.00	7796+63.00	6,437		0		6,437	14		14	17	0	6,420	0	6,420
		SUBTOTAL	6,437		0		6,437	14		14	17	0	6,420	0	6,420
PROJECT SUBTOTAL			198,361	0	1,071	0	198,361	91,148	0	91,148	109,378	689	89,672	1,071	90,743
ADDITIONAL UNDERCUT					0										
**EST. LOSS DUE TO CLEARING & GRUBBING			-350				-350						-350		-350
WASTE TO REPLACE BORROW												-689	-689		-689
PROJECT TOTAL			198,011	0	1,071	0	198,011	91,148	0	91,148	109,378	0	88,633	1,071	89,704
GRAND TOTAL			198,011		1,071										
SAY			198,100		1,080										

EST. DDE = 9010 CY

EST. 250 CY OF SHALLOW UNDERCUT.

EST. 1080 CY OF SELECT GRANULAR MATERIAL

EST. 3200 CY OF CLASS III SELECT MATERIAL

EST. 510 TONS OF CLASS IV SUBGRADE STABILIZATION

* THESE EARTHWORK QUANTITIES ARE BASED IN PART ON SUBSURFACE DATA PROVIDED BY THE GEOTECHNICAL ENGINEER.

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION		GRADATION		ROCK DESCRIPTION		TERMS AND DEFINITIONS																																																																																																																																																																																																																													
<p>SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (ASHTO T208, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE:</p> <p style="text-align: center;"><i>VERY STIFF, GRAY, SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LAYERS, HEAVY PLASTIC, A-7-6</i></p>		<p>WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.</p> <p style="text-align: center;">ANGULARITY OF GRAINS</p> <p>THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.</p>		<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>		<p>ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL, DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOD.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SCREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>																																																																																																																																																																																																																													
<p style="text-align: center;">SOIL LEGEND AND AASHTO CLASSIFICATION</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>GENERAL CLASS.</th> <th colspan="7">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="7">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="3">ORGANIC MATERIALS</th> </tr> <tr> <th>GROUP CLASS.</th> <th colspan="2">A-1</th> <th colspan="2">A-3</th> <th colspan="3">A-2</th> <th colspan="2">A-4</th> <th colspan="2">A-5</th> <th colspan="3">A-6</th> <th colspan="2">A-7</th> <th colspan="2">A-1, A-2</th> <th colspan="2">A-4, A-5</th> <th colspan="2">A-6, A-7</th> </tr> <tr> <th>SYMBOL</th> <td colspan="2">[Symbol]</td> <td colspan="2">[Symbol]</td> <td colspan="3">[Symbol]</td> <td colspan="2">[Symbol]</td> <td colspan="2">[Symbol]</td> <td colspan="3">[Symbol]</td> <td colspan="2">[Symbol]</td> <td colspan="2">[Symbol]</td> <td colspan="2">[Symbol]</td> <td colspan="2">[Symbol]</td> </tr> <tr> <th>% PASSING</th> <td colspan="2">50 MX</td> <td colspan="2">30 MX</td> <td colspan="3">10 MX</td> <td colspan="2">5 MX</td> <td colspan="2">2.5 MX</td> <td colspan="3">1.25 MX</td> <td colspan="2">0.625 MX</td> <td colspan="2">0.315 MX</td> <td colspan="2">0.15 MX</td> <td colspan="2">0.075 MX</td> </tr> <tr> <th>LIQUID LIMIT</th> <td colspan="2">5 MX</td> <td colspan="2">NP</td> <td colspan="3">40 MX</td> <td colspan="2">41 MX</td> <td colspan="3">40 MX</td> <td colspan="2">41 MX</td> <td colspan="3">40 MX</td> <td colspan="2">41 MX</td> <td colspan="2">40 MX</td> <td colspan="2">41 MX</td> </tr> <tr> <th>PLASTIC INDEX</th> <td colspan="2">0</td> <td colspan="2">0</td> <td colspan="3">0</td> <td colspan="2">4 MX</td> <td colspan="2">8 MX</td> <td colspan="3">12 MX</td> <td colspan="2">16 MX</td> <td colspan="2">No MX</td> <td colspan="2">No MX</td> <td colspan="2">No MX</td> </tr> <tr> <th>GROUP INDEX</th> <td colspan="2">0</td> <td colspan="2">0</td> <td colspan="3">0</td> <td colspan="2">4 MX</td> <td colspan="2">8 MX</td> <td colspan="3">12 MX</td> <td colspan="2">16 MX</td> <td colspan="2">No MX</td> <td colspan="2">No MX</td> <td colspan="2">No MX</td> </tr> <tr> <th>USUAL TYPES OF MAJOR MATERIALS</th> <td colspan="2">STONE FRAGS, GRAVEL, AND SAND</td> <td colspan="2">FINE SAND</td> <td colspan="3">SILTY OR CLAYEY GRAVEL AND SAND</td> <td colspan="2">SILTY SOILS</td> <td colspan="3">CLAYEY SOILS</td> <td colspan="3">SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td> <td colspan="2">HIGHLY ORGANIC SOILS</td> <td colspan="2">MUCK, PEAT</td> <td colspan="2">HIGHLY ORGANIC SOILS</td> </tr> <tr> <th>GEN. RATING AS A SUBGRADE</th> <td colspan="7">EXCELLENT TO GOOD</td> <td colspan="7">FAIR TO POOR</td> <td colspan="2">FAIR TO POOR</td> <td colspan="2">POOR</td> <td colspan="2">UNSUITABLE</td> <td colspan="2">UNSUITABLE</td> </tr> </table> <p style="text-align: center;">PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30</p>		GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)							SILT-CLAY MATERIALS (> 35% PASSING #200)							ORGANIC MATERIALS			GROUP CLASS.	A-1		A-3		A-2			A-4		A-5		A-6			A-7		A-1, A-2		A-4, A-5		A-6, A-7		SYMBOL	[Symbol]		[Symbol]		[Symbol]			[Symbol]		[Symbol]		[Symbol]			[Symbol]		[Symbol]		[Symbol]		[Symbol]		% PASSING	50 MX		30 MX		10 MX			5 MX		2.5 MX		1.25 MX			0.625 MX		0.315 MX		0.15 MX		0.075 MX		LIQUID LIMIT	5 MX		NP		40 MX			41 MX		40 MX			41 MX		40 MX			41 MX		40 MX		41 MX		PLASTIC INDEX	0		0		0			4 MX		8 MX		12 MX			16 MX		No MX		No MX		No MX		GROUP INDEX	0		0		0			4 MX		8 MX		12 MX			16 MX		No MX		No MX		No MX		USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND			SILTY SOILS		CLAYEY SOILS			SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER			HIGHLY ORGANIC SOILS		MUCK, PEAT		HIGHLY ORGANIC SOILS		GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD							FAIR TO POOR							FAIR TO POOR		POOR		UNSUITABLE		UNSUITABLE		<p style="text-align: center;">MINERALOGICAL COMPOSITION</p> <p>MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.</p> <p style="text-align: center;">COMPRESSIBILITY</p> <p>SLIGHTLY COMPRESSIBLE LIQUID LIMIT LESS THAN 31 MODERATELY COMPRESSIBLE LIQUID LIMIT EQUAL TO 31-50 HIGHLY COMPRESSIBLE LIQUID LIMIT GREATER THAN 50</p> <p style="text-align: center;">PERCENTAGE OF MATERIAL</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th></th> <th>GRANULAR SOILS</th> <th>SILT - CLAY SOILS</th> <th>OTHER MATERIAL</th> </tr> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>>10%</td> <td>>20%</td> <td>HIGHLY</td> </tr> </table> <p style="text-align: center;">GROUND WATER</p> <p>▽ WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING ▽ STATIC WATER LEVEL AFTER 24 HOURS ▽ PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA ○ SPRING OR SEEP</p>			GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME	HIGHLY ORGANIC	>10%	>20%	HIGHLY	<p style="text-align: center;">WEATHERING</p> <p>FRESH ROCK FRESH, CRYSTALLINE BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING, ROCK RINGS UNDER HAMMER IF CRYSTALLINE.</p> <p>VERY SLIGHT (V SLI.) ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALLS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.</p> <p>SLIGHT (SLI.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH, OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALLS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.</p> <p>MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.</p> <p>MODERATELY SEVERE (MOD. SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL</i></p> <p>SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED, ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT, SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, YIELDS SPT N VALUES > 100 BPF</i></p> <p>VERY SEVERE (V SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED, ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, YIELDS SPT N VALUES < 100 BPF</i></p> <p>COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.</p>	
GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)							SILT-CLAY MATERIALS (> 35% PASSING #200)							ORGANIC MATERIALS																																																																																																																																																																																																																				
GROUP CLASS.	A-1		A-3		A-2			A-4		A-5		A-6			A-7		A-1, A-2		A-4, A-5		A-6, A-7																																																																																																																																																																																																														
SYMBOL	[Symbol]		[Symbol]		[Symbol]			[Symbol]		[Symbol]		[Symbol]			[Symbol]		[Symbol]		[Symbol]		[Symbol]																																																																																																																																																																																																														
% PASSING	50 MX		30 MX		10 MX			5 MX		2.5 MX		1.25 MX			0.625 MX		0.315 MX		0.15 MX		0.075 MX																																																																																																																																																																																																														
LIQUID LIMIT	5 MX		NP		40 MX			41 MX		40 MX			41 MX		40 MX			41 MX		40 MX		41 MX																																																																																																																																																																																																													
PLASTIC INDEX	0		0		0			4 MX		8 MX		12 MX			16 MX		No MX		No MX		No MX																																																																																																																																																																																																														
GROUP INDEX	0		0		0			4 MX		8 MX		12 MX			16 MX		No MX		No MX		No MX																																																																																																																																																																																																														
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND			SILTY SOILS		CLAYEY SOILS			SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER			HIGHLY ORGANIC SOILS		MUCK, PEAT		HIGHLY ORGANIC SOILS																																																																																																																																																																																																															
GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD							FAIR TO POOR							FAIR TO POOR		POOR		UNSUITABLE		UNSUITABLE																																																																																																																																																																																																														
	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																																																																																																																																
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE																																																																																																																																																																																																																																
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE																																																																																																																																																																																																																																
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME																																																																																																																																																																																																																																
HIGHLY ORGANIC	>10%	>20%	HIGHLY																																																																																																																																																																																																																																
<p style="text-align: center;">CONSISTENCY OR DENSENESS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT²)</th> </tr> <tr> <td rowspan="3">GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE</td> <td>< 4</td> <td></td> </tr> <tr> <td>LOOSE</td> <td>4 TO 10</td> <td></td> </tr> <tr> <td>MEDIUM DENSE</td> <td>10 TO 30</td> <td>N/A</td> </tr> <tr> <td rowspan="3">GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>DENSE</td> <td>30 TO 50</td> <td></td> </tr> <tr> <td>VERY DENSE</td> <td>> 50</td> <td></td> </tr> <tr> <td>VERY SOFT</td> <td>< 2</td> <td>< 0.25</td> </tr> <tr> <td rowspan="4">GENERAL SOFT</td> <td>SOFT</td> <td>2 TO 4</td> <td>0.25 TO 0.50</td> </tr> <tr> <td>MEDIUM STIFF</td> <td>4 TO 8</td> <td>0.5 TO 1.0</td> </tr> <tr> <td>STIFF</td> <td>8 TO 15</td> <td>1 TO 2</td> </tr> <tr> <td>VERY STIFF</td> <td>15 TO 30</td> <td>2 TO 4</td> </tr> <tr> <td rowspan="2">HARD</td> <td>HARD</td> <td>> 30</td> <td>> 4</td> </tr> </table>		PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE	< 4		LOOSE	4 TO 10		MEDIUM DENSE	10 TO 30	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	DENSE	30 TO 50		VERY DENSE	> 50		VERY SOFT	< 2	< 0.25	GENERAL SOFT	SOFT	2 TO 4	0.25 TO 0.50	MEDIUM STIFF	4 TO 8	0.5 TO 1.0	STIFF	8 TO 15	1 TO 2	VERY STIFF	15 TO 30	2 TO 4	HARD	HARD	> 30	> 4	<p style="text-align: center;">MISCELLANEOUS SYMBOLS</p> <p>ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION SOIL SYMBOL ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT INFERRED SOIL BOUNDARY INFERRED ROCK LINE ALLUVIAL SOIL BOUNDARY DIP & DIP DIRECTION OF ROCK STRUCTURES</p> <p>TEST BORING WITH SPT DMT VST PHT AUGER BORING CORE BORING MONITORING WELL PIEZOMETER INSTALLATION SLOPE INDICATOR INSTALLATION CONE PENETROMETER TEST SOUNDING ROD</p>																																																																																																																																																																																								
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)																																																																																																																																																																																																																																
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE	< 4																																																																																																																																																																																																																																	
	LOOSE	4 TO 10																																																																																																																																																																																																																																	
	MEDIUM DENSE	10 TO 30	N/A																																																																																																																																																																																																																																
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	DENSE	30 TO 50																																																																																																																																																																																																																																	
	VERY DENSE	> 50																																																																																																																																																																																																																																	
	VERY SOFT	< 2	< 0.25																																																																																																																																																																																																																																
GENERAL SOFT	SOFT	2 TO 4	0.25 TO 0.50																																																																																																																																																																																																																																
	MEDIUM STIFF	4 TO 8	0.5 TO 1.0																																																																																																																																																																																																																																
	STIFF	8 TO 15	1 TO 2																																																																																																																																																																																																																																
	VERY STIFF	15 TO 30	2 TO 4																																																																																																																																																																																																																																
HARD	HARD	> 30	> 4																																																																																																																																																																																																																																
	<p style="text-align: center;">TEXTURE OR GRAIN SIZE</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <td>4</td> <td>10</td> <td>40</td> <td>60</td> <td>200</td> <td>270</td> </tr> <tr> <td></td> <td>4.75</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> </table> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>BOULDER (BLDR.)</th> <th>COBBLE (COB.)</th> <th>GRAVEL (GR.)</th> <th>COARSE SAND (CSE. SD.)</th> <th>FINE SAND (F. SD.)</th> <th>SILT (SL.)</th> <th>CLAY (CL.)</th> </tr> <tr> <td>MM 305</td> <td>75</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> <td></td> </tr> <tr> <td>IN. 12</td> <td>3</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.75	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)	MM 305	75	2.0	0.25	0.05	0.005		IN. 12	3						<p style="text-align: center;">ABBREVIATIONS</p> <p>AR - AUGER REFUSAL MED. - MEDIUM VST - VANE SHEAR TEST BT - BORING TERMINATED MICA - MICACEOUS WEA. - WEATHERED CL. - CLAY MOD. - MODERATELY % - UNIT WEIGHT CPT - CONE PENETRATION TEST NP - NON PLASTIC % - DRY UNIT WEIGHT CSE. - COARSE ORG. - ORGANIC S - BULK DMT - DILATOMETER TEST PMT - PRESSUREMETER TEST SS - SPLIT SPOON DPT - DYNAMIC PENETRATION TEST SAP. - SAPROLITIC ST - SHELBY TUBE e - VOID RATIO SD. - SAND, SANDY RS - ROCK F - FINE SL. - SILTY RT - RECOMPACTED TRIAXIAL FOSS. - FOSSILIFEROUS SLI. - SLIGHTLY TCR - TRICONE REFUSAL FRAC. - FRACTURED, FRACTURES TCR - TRICONE REFUSAL W - MOISTURE CONTENT FRAGS. - FRAGMENTS W - MOISTURE CONTENT V - VERY HI. - HIGHLY</p>																																																																																																																																																																																													
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																																																																																																																																																																																													
	4.75	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																																																																													
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)																																																																																																																																																																																																																													
MM 305	75	2.0	0.25	0.05	0.005																																																																																																																																																																																																																														
IN. 12	3																																																																																																																																																																																																																																		
<p style="text-align: center;">SOIL MOISTURE - CORRELATION OF TERMS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PL - PLASTIC LIMIT</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>SL - SHRINKAGE LIMIT</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </table>		SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	<p style="text-align: center;">EQUIPMENT USED ON SUBJECT PROJECT</p> <p>DRILL UNITS: ADVANCING TOOLS: HAMMER TYPE: CORE SIZE: HAND TOOLS:</p> <p><input type="checkbox"/> MOBILE B- <input checked="" type="checkbox"/> CLAY BITS <input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</p> <p><input type="checkbox"/> BK-51 <input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER <input type="checkbox"/> B- <input type="checkbox"/> N- <input type="checkbox"/> H-</p> <p><input checked="" type="checkbox"/> CME-450 <input type="checkbox"/> 6" HOLLOW AUGERS <input type="checkbox"/> TUNG-CARBIDE INSERTS <input type="checkbox"/> POST HOLE DIGGER</p> <p><input type="checkbox"/> CME-550 <input type="checkbox"/> HARD FACED FINGER BITS <input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER <input type="checkbox"/> SOUNDING ROD</p> <p><input type="checkbox"/> PORTABLE HOIST <input type="checkbox"/> TUNG-CARBIDE INSERTS <input type="checkbox"/> TRICONE <input type="checkbox"/> STEEL TEETH <input type="checkbox"/> VANE SHEAR TEST</p> <p><input checked="" type="checkbox"/> D-25 Marsh Buggy <input type="checkbox"/> TRICONE <input type="checkbox"/> TUNG-CARB. <input type="checkbox"/> MUD ROTARY</p>																																																																																																																																																																																																																		
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																																																																	
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																																																																	
PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																	
OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																																																																	
SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																	
<p style="text-align: center;">PLASTICITY</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table>		NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	<p style="text-align: center;">FRACTURE SPACING</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>TERM</th> <th>SPACING</th> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> </tr> </table> <p style="text-align: center;">BEDDING</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>TERM</th> <th>THICKNESS</th> </tr> <tr> <td>VERY THICKLY BEDDED</td> <td>> 4 FEET</td> </tr> <tr> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table> <p style="text-align: center;">INDURATION</p> <p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</p> <p>FRIABLE RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</p> <p>MODERATELY INDURATED GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</p> <p>INDURATED GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</p> <p>EXTREMELY INDURATED SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</p>		TERM	SPACING	VERY WIDE	MORE THAN 10 FEET	WIDE	3 TO 10 FEET	MODERATELY CLOSE	1 TO 3 FEET	CLOSE	0.16 TO 1 FEET	VERY CLOSE	LESS THAN 0.16 FEET	TERM	THICKNESS	VERY THICKLY BEDDED	> 4 FEET	THICKLY BEDDED	1.5 - 4 FEET	THINLY BEDDED	0.16 - 1.5 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET	THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																							
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																																																																																																																																																																																																	
LOW PLASTICITY	0-5	VERY LOW																																																																																																																																																																																																																																	
MED. PLASTICITY	6-15	SLIGHT																																																																																																																																																																																																																																	
HIGH PLASTICITY	16-25	MEDIUM																																																																																																																																																																																																																																	
	26 OR MORE	HIGH																																																																																																																																																																																																																																	
TERM	SPACING																																																																																																																																																																																																																																		
VERY WIDE	MORE THAN 10 FEET																																																																																																																																																																																																																																		
WIDE	3 TO 10 FEET																																																																																																																																																																																																																																		
MODERATELY CLOSE	1 TO 3 FEET																																																																																																																																																																																																																																		
CLOSE	0.16 TO 1 FEET																																																																																																																																																																																																																																		
VERY CLOSE	LESS THAN 0.16 FEET																																																																																																																																																																																																																																		
TERM	THICKNESS																																																																																																																																																																																																																																		
VERY THICKLY BEDDED	> 4 FEET																																																																																																																																																																																																																																		
THICKLY BEDDED	1.5 - 4 FEET																																																																																																																																																																																																																																		
THINLY BEDDED	0.16 - 1.5 FEET																																																																																																																																																																																																																																		
VERY THINLY BEDDED	0.03 - 0.16 FEET																																																																																																																																																																																																																																		
THICKLY LAMINATED	0.008 - 0.03 FEET																																																																																																																																																																																																																																		
THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																																																																		
<p style="text-align: center;">COLOR</p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>		<p style="text-align: center;">NOTES:</p> <p style="text-align: right;">ELEVATION: _____ FT.</p>																																																																																																																																																																																																																																	

TIP PROJECT: C-4901A


CONTRACT: C203160

NCDOT
RAIL DIVISION


DAVIDSON COUNTY



STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	C-4901A	2A	10
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
49010.1.STR03T1B		P.E.	
43219.2.STR02C4901		ROW	
49010.3.STR01T4A		UTIL. & CONST.	




PROJECT TITLE: NCRR/NS MAINLINE BOWERS TO LAKE RAILROAD ROADBED
(MP 309.8 TO MP 314.0)
TYPE OF WORK: GRADING, DRAINAGE, STRUCTURE



PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

SUBMITTAL: RIGHT-OF-WAY
DATE: JULY 31, 2012

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III
THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES



PROJECT LENGTH	
LENGTH OF RAIL TIP PROJECT	4.302 MILES
LENTGH OF STRUCTURES TIP PROJECT	0.092 MILES
TOTAL LENGTH OF TIP PROJECT	4.394 MILES

Prepared in the Office of:
HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

2012 STANDARD SPECIFICATIONS	ROBERT BURNETT, P.E. RAIL PROJECT ENGINEER
RIGHT OF WAY DATE: AUGUST 2012	COREY VERNIER, P.E. RAIL PROJECT DESIGN ENGINEER
LETTING DATE: MAY 2013	DAVID HAWKINS, P.E. STRUCTURE PROJECT ENGINEER
	JAMES BYRD, P.E. HYDRAULICS PROJECT ENGINEER
	JASON ORTHNER, P.E. NCDOT PROJECT MANAGER

RAIL ENGINEER
SIGNATURE: _____ P.E.

HYDRAULICS ENGINEER
SIGNATURE: _____ P.E.

NC DEPARTMENT OF
TRANSPORTATION
RAIL DIVISION

ENGINEERING AND SAFETY BRANCH
CAPITAL YARD
104 MAIL SERVICE CENTER
RALEIGH, NC 27609-1144



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

January 22, 2013

STATE PROJECT: 49010.1.STR03T1B (C-4901 A/D)
F.A. PROJECT: n/a
COUNTY: Davidson
DESCRIPTION: CP "Bowers" (MP 309.8) to CP "Lake" (MP 314.0) on the NCRR / NS Mainline
SUBJECT: *Revised* Geotechnical Report – Inventory for New Alignment Sections

Project Description

The project consists of constructing the second main line track (4.2 miles) and curve and safety improvements. The project is located Davidson County, between Thomasville, N.C., and Lexington, N.C, along the existing NCRR / NS main line. The project consists of the construction of a second main line track and two segments of new alignment designed to straighten existing main line curves. This project is part of the NCDOT Rail Division's American Recovery and Reinvestment Act (ARRA) Piedmont Improvement Program (PIP),

The geotechnical investigation was conducted in the late spring and summer of 2012 utilizing Summit Design and Engineering, LLC, personnel. Borings were advanced using CME-450 drill machine equipped with automatic standard penetration test (SPT) hammer. SPT borings were performed at specific locations to provide subsurface information for roadway design and construction. Representative soil samples were tested in Summit's NCDOT and AASHTO approved soils laboratory. This geotechnical roadway investigation concentrated on the areas of proposed railway realignment.

The following alignments were investigated for this project:

<u>Line</u>	<u>Station(±)</u>
-M1-	7591+00 to 7598+90
-M1-	7663+50 to 7679+00

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
GEOTECHNICAL ENGINEERING UNIT
1589 MAIL SERVICE CENTER
RALEIGH NC 27699-1589

TELEPHONE: 919-707-6850
Fax: 919-250-4237
www.ncdot.gov/doh/preconstruct/highway/geotech

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B-2
1020 BIRCH RIDGE DRIVE
RALEIGH NC 27610

Areas of Special Geotechnical Interest

- 1) Plastic Soils- Medium to highly plastic, alluvial clays were found to occur in the saturated area between Hamby Creek Tributary and 7673+00.
- 2) Alluvial Soils- Relatively recent flood plain deposits, typically consisting of medium to highly plastic silty clay and sandy silt, are found in the saturated area near Hamby Creek Tributary and near creeks that drain into Hamby Creek Tributary. Alluvial soils were found to range in depth across the project area from 3.0 to 7.9 ft. These soils have the potential to cause embankment stability/settlement problems and occur through the following sections:

<u>Line</u>	<u>Station (±)</u>
-M1-	7596+00 to 7598+90
-M1-	7661+00 to 7673+00

- 3) Crystalline Rock- No crystalline rock was encountered within 6 feet of proposed grade in areas of main line track realignment.
- 4) Ground Water- No areas were found to exhibit a high water table, seasonal high ground water, or the potential for ground water related construction problems.

Physiography, Geology and Surface Water

The project corridor is located in the Piedmont Physiographic Province, between Thomasville and Lexington, N.C. Topography in the project area is generally gently rolling and is comprised of farmland, pine and hardwood forest, and residential/commercial development.

Geologically the project area is located in the northern Charlotte Belt and is underlain by Cambrian/Late Proterozoic-age mafic meta-volcanic rock (CZv). Residual soils were derived from the weathering of the meta-volcanic rock they overlie. More recent alluvial deposits occur in and around streams and drainages across the project.

Surface water is drained from the corridor by Hamby Creek Tributary and Abbott's Creek as well as several smaller unnamed creeks that generally trend north/south across the project.

Soils Properties

Soils encountered at the project site include both alluvial and residual deposits.

Alluvial deposits are located within the floodplains of Hamby Creek Tributary, Abbott's Creek, and the ditches and wetland areas that traverse the project. These soils are primarily Brown, very loose, clayey sand (A-2-6) and orange brown to gray, very soft to stiff, sandy silt (A-4), plastic silty clay (A-7-6), and sandy clay (A-6).

Residual soils were encountered throughout the project. These soils consist of brown, dense, saprolitic, coarse sand (A-1-b) and silty sand (A-2-4); orange-brown, very stiff, saprolitic, silty clay (A-7) and clayey silt (A-5); gray and brown, hard, saprolitic, sandy silt (A-4), and Brown, stiff, sandy clay (A-6).

Rock Properties

Weathered rock was encountered during the roadway investigation. It originates from the underlying mafic meta-volcanic rock.

Crystalline rock was not encountered during the roadway investigation but was encountered during the structure investigation for the proposed bridge over Hamby Creek Tributary, near 7663+00. Crystalline rock that underlies the project area consists of dark green to black, fresh, hard, close-fractured, mafic meta-volcanic rock. No rock outcrops, or rock in the subsurface, was encountered within 6 feet of proposed grade.


Ground Water

Ground water data was collected during average rainfall conditions. Water levels across the project vary due to topographic relief and soil permeability. The presence of less permeable clayey soils may cause water levels to be relatively shallow. In upland areas adjacent to flood plains ground water levels occur at depths of 4 to 10 feet below natural ground. Within flood plains water levels were generally just below or at the natural ground surface. Groundwater may fluctuate with seasonal precipitation.

Surface Water



Surface water exist in the area of proposed track realignment, to the north side of the existing NCRR / NS mainline, between stations 7664+00 and 7672+50. Water depth varies with seasonal rainfall, but was observed during drilling to be 0.75 to 1.0 ft. During the property owner contact phase of the investigation, field personnel were told that the standing water was due to a beaver dam on a small creek that empties into Hamby Creek Tributary.

Respectfully Submitted,






Bradley D. Worley
Sr. Transportation Geologist

PROJECT REFERENCE NO. C-4901A	SHEET NO. 4
RW SHEET NO.	
RAILROAD DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	




130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150





140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150





140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150


130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150





140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

TO GREENSBORO

TO CHARLOTTE



PROJECT REFERENCE NO. C-4901A	SHEET NO. 9
RW SHEET NO.	
RAILROAD DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	



SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL (FT.)	AASHTO CLASS	LL	PL	% BY WEIGHT			% PASSING (SIEVES)			% MOISTURE	% ORGANIC	
							C. SAND	F. SAND	SILT	CLAY	10	40			200
SS-1	CL	7665+00	0.0 - 1.5	A-4 (3)	25	6	10.3	19.1	43.5	27.0	99	93	77	28.6	n/a
SS-3	CL	7667+00	0.0 - 1.5	A-7-6 (20)	49	35	13.5	23.6	17.6	45.3	99	93	68	26.1	n/a
SS-4	CL	7667+00	5.0 - 6.5	A-4 (0)	30	4	32.1	24.6	26.0	17.2	77	58	39	21.0	n/a
SS-8	CL	7669+00	0.0 - 1.5	A-2-4 (0)	15	NP	50.2	26.8	8.6	14.4	94	66	25	21.2	n/a
SS-9	CL	7671+00	0.0 - 1.5	A-4 (0)	28	2	13.5	44.1	34.6	7.8	100	94	54	19.0	n/a

